

# Final Design of the PANDA Target Beam Dump



**Philipp Brand**

WWU Münster, Institut für Kernphysik, Germany

PANDA collaboration meeting, Prague, June 12 – 16, 2023




# The Beam Dump System




# The Beam Dump System

- Similar to current design (3 stages, 7 pumps)
- 3 orifices with variable size






# The Beam Dump System

- Similar to current design (3 stages, 7 pumps)
- 3 orifices with variable size
- Can be equipped with several monitor systems
  - Absolute thickness monitor system (AMS)
  - Movable MCP system for 2D beam visualization and cluster velocity measurement
- Design finished; some parts already available




# The Beam Dump System

- Beam dump will be connected to target beam line by self-developed snap connector






# The Beam Dump System






# The Beam Dump System

- Beam dump will hang below the solenoid at four defined points, exact position can be adjusted



# The Beam Dump System


- Complete system can be tilted for perfect adjustment






# The Beam Dump System

- Complete system can be moved and lifted by a transport frame
- Last turbo pump has to be removed for this (limited height below the solenoid)




# The new Pumping Station

- Rotary vane pump and roots pump
- Remote controllable (pumps, pneumatic valves, gate valves)
- Movable for easy access in maintenance
- Placed under detector directly next to beam dump
- Separate ventilation line with clean gas




## Current progress

- Construction of pumping station has started last week
  - Next step: Installation of pipes, valves, ...




## Current progress

- Construction of pumping station has started last week
  - Next step: Installation of pipes, valves, ...
- First orifice system has been mounted
  - Next step: Commissioning and control of motors






## Current progress


- Construction of pumping station has started last week
  - Next step: Installation of pipes, valves, ...
- First orifice system has been mounted
  - Next step: Commissioning and control of motors
- Simplified MCP system has been mounted (see following talk by H. Eick)





# Backup



Oberfläche:  
Allgemeintoleranzen ISO 2768-fH-E  
Projektion ISO 5456-2: 

Arbeitsgruppe/Projekt Khoukaz-MCT_PANDA	Erstellt durch Rummler	Werkstoff	Menge 1	Maßstab 1 : 10
 Institut für Kernphysik Wilhelm-Klemm-Str. 9 48149 Münster	Dokumentenart Baugruppe	Kostenelement 3120058400		
	Bauteilnummer, Titel 02PAN20398 Pumpstand_Detektor	Zeichnungsnummer 02PAN20398-Pumpstand_Detektor		
	Änd. V218	Ausgabedatum 13.09.2022	Spr. de	Blatt 1