



# Technical Highlights (I)



Half CALIFA including forward sector



Detailed view of R<sup>3</sup>B Target area  
Recoil tracking Stage 1

## 2023-2024

- Full coverage of CALIFA calorimeter at forward angles  
Mitigation action for CEPA Phoswich
- Target recoil tracking Stage 1 commissioned  
Mitigation action for L3T Si Tracker
- Commissioning of HYDRA TPC inside GLAD
- Commissioning of full R<sup>3</sup>B setup for the 2024 campaign



Tracking detectors behind GLAD





HYDRA TPC inside GLAD



# Technical Highlights (II)




## HISPEC/DESPEC BGO Backcatchers for DEGAS




- DEGAS detector comprises 3 x HPGe and 3 x BGO
- BGOs operate in anti-coincidence with the HPGes, to reduce the Compton continuum measured by the HPGes
- 18 BGO backcatchers (JSI, Ljubljana) assembled, tested and delivered for use in upcoming FAIR Phase-0 experiments

Single (left) and triple (right) BGO modules




Main components of a DEGAS detector



G. Kosir *et al.*, BGO active shield for DEGAS, Nuclear Inst. and Methods in Physics Research, A (2024),  
doi: <https://doi.org/10.1016/j.nima.2024.169157>

# NUSTAR timeline: the 'simple' picture



**Green:** Budget available  
**Green:** Budget decision expected soon  
**Blue:** Civil construction complete  
**Orange:** Significant additional investment required


– Timeline dependent on Council decisions and timely delivery of SIS100 quadrupoles  
– Additional funding needed in 2026 for continuation of skilled workforce




# Overview of ES/FS at the S-FRS

## Three key focal points of the S-FRS:



- **FMF2** mid-point of main separator
- **FHF1** (tunnel)
- and **FHF2** (HEC) along high-energy branch






## NUSTAR High-Energy Cave

# Construction update – Q1 2024






The model comes to life – example: rack niche HEC




# Technical Building Infrastructure (TBI) progress update Q1 2024, inside HEC



Courtesy: P. Hofmann


# Technical Building Infrastructure (TBI) progress update Q1 2024, inside HEC




Courtesy: P. Hofmann



# NUSTAR High-Energy Cave Visualisation



Copyright: © GSI/FAIR, Zeitrausch



Copyright: © GSI/FAIR, Zeitrausch

# NUSTAR Strategy towards FS

Handover “cave  
ready for  
installation”



As soon as building is  
ready for installation, some  
infrastructure items can be  
installed (limited due to  
work on Super-FRS)

# NUSTAR Strategy towards FS

Handover "cave  
ready for  
installation"



HE Cave  
Handover from  
Super-FRS



As soon as HEB  
cave is "empty",  
handover MS from  
Super-FRS,  
installation of R3B  
can start



# NUSTAR Strategy towards FS

Handover "cave  
ready for  
installation"

HE Cave  
Handover from  
Super-FRS

S-FRS  
M12

Q4  
2027

Final S-FRS  
commissioning  
Milestone 12,  
Particle ID validation  
with simple detector  
setup inside HE  
Cave @ FHF2

# NUSTAR Strategy towards FS

Handover "cave ready for installation"

HE Cave Handover from Super-FRS


S-FRS M12

Q4 2027

Common NUSTAR experiment @ FHF2

**Common NUSTAR experiment.** S-FRS settings and setup likely to overlap with M12

Simple, compact setup, fast results needed!  
Lessons learned from FRIB (and RIKEN)



**Common NUSTAR Experiment @ FHF2**

# NUSTAR Strategy towards FS

Handover "cave ready for installation"

HE Cave Handover from Super-FRS

S-FRS M12

Q4 2027

Common NUSTAR experiment @ FHF2


NUSTAR Early Science

NUSTAR First Science

## NUSTAR ES and FS:

individual sub-collaborations (**Super-FRS EC**, **partial HISPEC/DESPEC** and **R3B**) running PAC-approved experiments at S-FRS focal planes, continuation of the **SHE** program at UNILAC and **ILIMA** at the ESR and CRYRING

Detailed installation timelines to be developed and refined in LCM workshops




# NUSTAR setups @ FHF1

- FHF1 to be shared between DESPEC and Super-FRS EC Ion Catcher
- Detailed discussion on a number of topics to ensure we will be ready in 2027
- **NUSTAR ES experiments will be the first at FAIR**
- Information on what, who and how equipment will be operated needed for safety considerations and planning
- Series of Workshops co-organised by NUSTAR and S-FRS

Participants from:  
NUSTAR Infrastructure Team  
Super-FRS project (SFS)  
Radiation Safety  
DESPEC  
Super-FRS EC

- A) Clarification of all components to be in use at FHF1 and their requirements
- B) How each setup (DESPEC or Ion Catcher) will be arranged at FHF1 in 'experimental mode'
- C) Transport of components to FHF1
- D) Exchange of setups
- E) Storage of experimental equipment in the tunnel






# NUSTAR setups @ FHF1

- **Main outcomes:**

- Detailed checks performed for the **DESPEC platform** and **Super-FRS EC Ion Catcher**
- 3 S-FRS diagnostic chambers currently planned – downstream chamber will be moved upstream to make space for NUSTAR components (details under discussion)
- **Both setups fit into the space**, with enough room for a common-use detector table, safety pathway and a beamdump downstream (if required)
- **A promising solution** for how to maneuver and align components without the use of rails has been identified
- Detailed checks of **component transportation** from the NUSTAR laboratories (and elsewhere) being carried out
- Next: **safe storage** of experimental equipment in the tunnel (along with S-FRS components)



Courtesy S.Purushothaman

NUSTAR ES/FS planning **fully endorsed by ECE/ECSG** at the November 2023 and April 2024 meetings

The committee compliments the collaboration for the excellent planning towards the Early Science (ES) and First Science (FS) phases and endorses performing ES&FS experiments at the Super-FRS high-energy branch (**R3B, DESPEC, S-FRS EC collaboration**) in view of the facts that it is

- **Technically feasible and scientifically sound**
- **Does not create delays**
- **Creates no additional costs (other than a small additional contribution already foreseen in the NUSTAR Common Fund)**

A document prepared by NUSTAR was submitted to the ECE/ECSG in October 2023, outlining details of the technical planning for Early and First Science. **A comprehensive evaluation** was carried out by NUSTAR of the infrastructure that will be available in the Early and First Science stages of FAIR when the S-FRS high-energy branch and the NUSTAR High Energy Cave will be fully commissioned and ready for experiments. The planning **optimizes the use of the available resources to maximize the scientific output of FAIR.** In conclusion, the ECE re-emphasizes that **equipment, formerly planned for the low-energy branch, such as DESPEC, shall be installed and operated at the HEB, to maximize the scientific opportunities offered at FAIR.**


- Installation of infrastructure in the NUSTAR areas **progressing well**
- NUSTAR ES/FS planning **fully endorsed** by the ECE/ECSG
- Detailed workshops for NUSTAR setups at FHF1 carried out; more planned for other S-FRS focal planes
- A strategy for **optimised operation** along the S-FRS for Early Science under development







# Anticipated NUSTAR Timeline



- Timeline pending Council decisions
- Assumes timely installation of SIS-100 magnets and release of new budget for > FS in 2025/2026

# NUSTAR Risk Register (Top items, status 03/24)



Risk ID	Scenario	Status	Description	Prob	Risk Score	Status/mitigating actions
402	ES	Mitigation ongoing	Energy resolution of CEPA scintillator detectors is insufficient due to position dependence.	90%	9	Mid-term mitigation in place for ES. No technical solution yet for long-term operation (probability increased since last report)
173	ES	Mitigation ongoing	No budget approved for NUSTAR infrastructure	10%	8	Mitigation: fund to be established via NUSTAR MoU. Signatures expected soon (probability reduced since last report)
358	ES	Mitigation ongoing	Detection threshold of Si tracker far too high	10%	8	Mitigation: TDR submitted, final stages of signing co-operation agreement (STFC-FAIR) (probability reduced since last report)