



Cryogenics for Large Accelerators

Dr. Sergiy Putselyk
Deutsches Elektronen-Synchrotron (DESY)
MKS Division
Notkestrasse 85
22607 Hamburg (Germany)
Phone: +49 40 89983492
Fax: +49 40 89982858
E-Mail: Sergiy.Putselyk@desy.de



- Present and Future 2K accelerators
- Accelerator Module Test Facility (AMTF)

Accelerator	Heat load @ 2K	Eq. Refriger. Power @ 4.5K
CEBAF	2*4.2kW	2*18 kW
LHC	8*2.4kW	8*18 kW
SNS	≈ 2.4 kW	≈ 11 kW
FRIB	≈ 4 kW	18 kW
XFEL/DESY	≈ 2.4 kW	≈ 11 kW
LCLS-II	2*4.6 kW	2*18 kW
ESS	≈ 3 kW	≈ 10 kW
ILC	14-28(?) *2.4 kW	
RHIC		≈ 14 kW
FAIR/GSI		6+18 kW (?)

There is quite substantial number of accelerators working at 2K level!

The number of accelerators with sc cavities is growing!




The large cryogenic system & refrigerators are required!


Note 1: for XFEL, it could be possible to cover 2K heat load with one 9kW@4.5K refrigerator (this will be cross-checked)

Note 2: some refrigerators require also non-negligible 4.5K refrigeration load (e.g. FRIB, Cornell's ERL) or 4.5K liquefaction load (e.g. SNS, FRIB, LCLS-II, ESS)


Accelerators with s.c. cavities at 2K: cross-sectional view




LCLS-II




CEBAF, C-100




**SNS,
ESS**



CEBAF, old cryomodule




FLASH, XFEL, ILC




Cornell ERL

Accelerators with s.c. magnets at 2 or 4K: cross-sectional view




LHC



RHIC




SIS300




SIS100


Accelerators with s.c. cavities at 2 or 4K for heavy ions: cross-sectional view




FRIB, Michigan



**ISAC-II/ARIEL,
TRIUMF**




HIE-ISOLDE, CERN




- Cavities assembled under clean conditions
- Separate beam and insulating vacuums

Rare Isotope Accelerator, Argonne

XFEL-cryogenic system -overview





Simplified flow scheme

40K -> 80K shield circuit (in series)

5K -> 8K shield circuit (in series)

2K circuit (supply in parallel, return in series)

warm gas collection pipe

40/80 K return, shield cooling

40/80 K forward

8 K return, shield cooling

5 K forward

2.2 K forward

2 K return

lead cooling


8 K return, shield cooling

5 K forward

2.2 K forward

2 K return

Simplified flow diagram of cryomodule string



- Complete cold performance tests of all XFEL cryomodules before tunnel installation (RF measurements, vacuum check, cryo-losses)
103 cryomodules, rate: 1 cryomodule/week
- Cold RF tests of all XFEL superconducting cavities before cryomodule assembly
824 cavities, rate: 6 cavities/week
- Cold tests of all superconducting magnet packages before cryomodule assembly
103 magnets, rate: 1 magnet/week



■ Vertical Cryostat



■ Radiation protection shielding



■ Cavity preparation area




■ Unloading of the cryomodule after transport



■ Cryomodule preparation area



■ XATB – module inside radiation protection shielding



Sub-system 1


Sub-system 2

Red = Wroclaw University of Technology+Kriosystem, Poland (in-kind)

**Blue = DESY MKS acting for XFEL company (no in-kind!)
-> DeMaCo, Netherlands**

Green= Budker Institute of Nuclear Physics, Russia (in-kind)

Manufacturer: Oerlikon Leybold



RUVAC

SOGEVAC

2 sets of compressors for 2K operation
at AMTF (2 x 20 g/s helium at 20 mbar)

1 set = 12 x parallel pump stations
(WS 2001 RUVAC roots vacuum pump +
SOGEVAC SV750B rotary vane vacuum
pump)

– simple, modular, redundant

In average: about 8000 h operation (status June 2015)

SPEC DESY

April 2009

Design & Construction

WUT&Kriosystem




Delivery & installation:

July 2012 – April 2013

Cavity Frame
Design:

DESY FLA

6 inserts for
AMTF





Courtesy of J.Schaffran

Spec DESY (February 2010) Design, Construction, Installation: BINP

First test stand delivered & installed May 2013 (cold commissioning July 2013)


Cold commissioning of 3rd test stand December 2013




2 cryostat adapters for the test of single dressed cavities at AMTF

DESY is acting for XFEL company
Manufacturer: DeMaCO


**Wessington
Cryogenics Ltd, UK**



Sub-Cooler Box XASB



Valve Box XAVB



L Helium Dewar XAST

- Supplied by HERA helium refrigerator.
- 33 g/s of LHe and cooling capacities of about 3 kW at 40/80K, 0.5 kW at 4.5K.
- Modular structure - independent operation of test stands from each other.
- Buffering of extra liquefaction in 10000 ltr liquid helium storage dewar (XAST).
- Missing of air condensation on cryogenic valves during exchange of modules or cavities.
- Capacity limits – return gas peak, screw compressor capacity during cool down/warm-up, 2 dynamic procedures in parallel.


Cool down and Warm up

XATC1, XATC2

- Manual pump and purge
- Cool-down to 4K, liquid helium transfer and warm-up in automatic mode
- Manual pump-down to 2K

XATB1, XATB2, XATB3

- Manual pump and purge
- Mainly automatically warm-up,
- Cool-down partially in automatic mode



All superconducting magnets are tested!

In total, >1200 Cavity tests were performed on vertical cryostats.

Specified test rate of accelerator modules is reached!

Total heat load (static+dynamic) in line with budget.

Testing rate is slightly reduced due to lower cryomodule delivery rate

Near all results above XFEL specification:

- accelerating gradient 23.6 MV/m
- cavity quality factor $Q_0 = 10^{10}$ at 23.6 MV/m

Some preliminary conclusions

- Deliveries & installation of XATCs,XASB,XAVB,XATL were “just-in-time“ for start-up of cavity production
- Deliveries & installation of XATBs were “just-in-time“ for start-up of cryomodule production
- No dedicated debugging of cryo-supply and other systems
- XATCs design capacities demonstrated
- Complexity of XATBs commissioning underestimated
- General effort for installation & commissioning underestimated
- 1 cryomodule test/week is reached (further ramping-up rate is under investigation)
- So far: in budget and almost “in time“ (not “on schedule“)



Thank you for your attention !