

Update on cooling and mechanics of the luminosity detector

Heinrich Leithoff

Helmholtz Institut Mainz


PANDA-Collaboration-Meeting Stockholm

June 5, 2018





Helmholtz Institute Mainz

Overview



- status of the cooling system
- update on mechanical structure


Cooling system: General setup



	sensors	LDO Voltage regulator	resistance in flexcables	Multiplexer etc.
worst case	1120 W	320W	160W	~100W
likely case	370 W	110W	20W	~100W



- Total estimated heat load per half detector: ~~~1 kW~~ ~350 W
- For cooling test: copper dummies and high power resistors

Half detector prototype




- production of halfplanes is finished
- First full half detector under preparation for cooling test
- First test in vacuum seems ok

Cooling test preparation



- PT100 sensors glued to half planes and copper dummies
- Resistors glued to copper dummies and connected
- Busbars prepared for installation

Mechanical setup: Beampipe installation



Three options for installing the inner beampipe:

- Glue everything outside, install everything at once
- Glue cone outside, connect cone and metal part in the box
- Install metal part, glue everything in the box.

All tricky.....

Summary and outlook

- production of half planes finished
- half plane prototype successfully tested
- new design vacuum box produced, first tests successful

What is next:



- extended test of new vacuum box
- test of half detector prototype
- extended cooling test
- production of final detector

Aluminum steel contact after cooling

after cutting:







after cooling to -40°C :




No gap between the materials, very good contact

Comparison of materials and processes




Test of the aluminum-diamond contact



- Setup with copper dummy
- Comparison of FEM results with measurements
- Test and comparison of several contact materials

FEM-simulation and measurement



- Simulated temperature difference $\sim 55^{\circ}\text{C}$
- Measured temperature difference (two Pt100): 50°C
- High radial temperature gradient (up to $2 \frac{\text{K}}{\text{mm}}$)

kein Material

$$\sim 2,2 \frac{^{\circ}\text{C}}{\text{W}}$$





Graphitfolie

$$\sim 0,88 \frac{^{\circ}\text{C}}{\text{W}}$$


PC93

$$\sim 0,72 \frac{^{\circ}\text{C}}{\text{W}}$$

Contact materials



Contact materials 2




Upper limit for the material transition temperature rise:

no material	graphit foil	PC94	vacuum grease	MX2
$\sim 2,2 \frac{^{\circ}\text{C}}{\text{W}}$	$\sim 0,86 \frac{^{\circ}\text{C}}{\text{W}}$	$\sim 0,86 \frac{^{\circ}\text{C}}{\text{W}}$	$\sim 0,37 \frac{^{\circ}\text{C}}{\text{W}}$	$\sim 0,27 \frac{^{\circ}\text{C}}{\text{W}}$

These contain $\sim 0,1 \frac{^{\circ}\text{C}}{\text{W}}$ due to the measurement setup

Temperature Gradient



- Temperature gradient varies on the diamond
- High values near the cooling structure ($> 1.5 \frac{K}{mm}$)
- interesting measurements are in region with $> 1 \frac{K}{mm}$

Melting aluminum around stainless steel pipes



- Casting mould with stop off and cooling pipe
- The pipe can move in one direction to minimize internal stress

Casting mould after first melting process



- First test done under vacuum
- good results, but the vacuum furnace gets really dirty