



# Status Forward Endcap EMC



PANDA Collaboration Meeting 18/3, GSI, November 7, 2018

Thomas Held

Ruhr-Universität Bochum  
Institut für Experimentalphysik I



# Outline

- VPTT Submodule Production
- APD Submodule Production
- Jülich Installation
- Coolant Flow Adjustment Simulation
- Inner Stiffener Ring



# VPTT Submodule Production


- Production of VPTT equipped submodules ran August to October
- All 54 submodules are produced (768 crystals) (42 16-crystal modules, 12 8-crystal modules)
- All submodules light pulser tested in Bochum
- Cosmics tests at Bonn University ongoing
- Constant production and delivery rate of 5 submodules per week
- 20 % (768 crystals) of forward endcap finished




# VPTT Submodule Production

- Very valuable cabling guide (6-page document, Bonn)


## VPTT HV Pin Assignment by submodule ch numbers



## APD HV Pin Assignment by submodule ch numbers



## Channel Numeration



View from the backside (cable side), looking towards the target

View as indicated:  
socket side



cable side

All views  
from cable side

LV Pin Assignment



cable side



socket side

LED Pin Assignment  
cable side



socket side

Assignment:




Figure 1: Materials and alveole

Start with screwing on the slanted metal interface. Be careful to use the correct one in the correct orientation.

The four crystals in each corner form a unit in regards of the connectors: top left (black), lower left (blue), top right (red) and lower right (green) (see Appendix 6). Each unit needs one black connector the high voltage, one white connector for low voltage and a cable comb for the signal wires. Additionally there are the yellow/green and brown/white LED wires, plus the big silver grounding wires, which should already be connected to the middle screw.







Figure 2: LED, LV, HV cables (from the left) and sleeving preparation; note the missing blue HV wires: this is a VPTT alveole

Now sort the wires of the four crystals in one corner. Then put the LED wires in a cable sleeve. Their plug is located in the middle of the top or bottom respectively. You can extend the sleeve by

# VPTT Submodule Production

- Color coded grouping of submodule cables




- 96 temperature sensors fitted
- 2 (1) per 16 (8)-crystal unit

-  X  Y  LfdNr: #

OK?

- In addition to QA “Production Test Sheets”:  
Checklist to be filled out during assembly

• Kristall-Seriennummern überprüfen	
• Kohlefaseraleveole auf Beschädigungen überprüfen	
• Aluminium-Schirmungen aller VPTT-Einheiten überprüfen	
• Ausheilungs-LEDs testen (Multimeter-Adapter, Einstellung: $\rightarrow$ )	
• Zugentlastungen für LEDs (Tesa-Streifen) überprüfen	
• Masseverbindungen zwischen Masseband und Aluminium-Klebeband, HV-Masse, LV-Masse, Signalkabel Schirmung prüfen (Multimeter Einstellung/Zielwert: $<1\Omega$ )	
• Temperatursensoren testen (Multimeter: $\Omega$ , Bereich $200\Omega$ )	
• Orientierung aller Kohlefaserkreuze prüfen	
• Kabel bündeln <b>vor</b> Montage der Mounplate Auf eingeklemmte Kabel achten!	
• Gewinde in der Mountplate testen	
• Korrekte Länge der Schrauben prüfen 1. Mountplate an Inserts: $16 \times M4$ ; Länge 12mm (!!) 2. Haltegriff an Mountplate: $4 \times M4$ ; Länge 16mm (etwas länger als Schrauben aus 1.)	
• Nach Zusammensetzen: Beweglichkeit der Kristalleinheiten in z-Richtung testen. <ul style="list-style-type: none"> <li>Bei zu großem Spiel (<math>&gt;0.5\text{mm}</math>) oder vielen wackelnden Einheiten <math>\rightarrow</math> Zerlegen, Capsules prüfen, evtl. Rand abschneiden</li> <li>Gesamtlänge des Submoduls messen (Messschieber, Angabe in mm)               <ul style="list-style-type: none"> <li>Oben</li> <li>Links</li> <li>Rechts</li> </ul> </li> </ul>	




## VPTT Submodule Production

- Losses: 1 broken crystal unit, 3 broken/vented VPTTs, 2 VPTTs w/ loose mesh dynode, 1 bad temperature sensor
- About 100 VPTTs and preamps spare left
- No spare submodules production, individual single channel exchange if necessary



# VPTT Submodule Production

- Constant delivery rate of 5 submodules per week by Fahrdienst RUB (to Bonn for cosmic tests)
- Submodules w/ handle bar individually enclosed in cushioned boxes (empty boxes returned)






## VPTT Submodule Production

- All VPTT submodules currently stored in Bonn, will go to Jülich in one batch when tests are finished



# APD Submodule Production

- 4 times as much APD submodules as VPTT submodules
- 4 times 3 months = 12 months  
⇒ need to speed up production!
- VPTT submodule mounting in Jülich in parallel!
- Preparation of electronics: Preamp cabling etc.
- APD screening ongoing: Increasing pool of screened APDs for grouping




# APD Screening Setup

- Bochum APD screening setup:  
Full capacity extension almost finished
- Will give twice the throughput:  
250/500 APDs a week (prior to/after irradiation) (shift work)
- Irradiation at Strahlencentrum Giessen running smoothly
- More details in Jan Reher's talk
- One rejection criterion: APD dark current at  $M=800(!)$  and  $-25\text{ }^{\circ}\text{C}$  after irradiation/annealing less than 10 nA (Headroom for future gain increase according to crystal light yield loss needed!)
- Additional selection criterion (forward endcap/barrel):  
Slope of gain curves ( $dM/dT$ ,  $dM/dU$ ) (statistics)

# Jülich Installation


- Forward endcap support frame and pedestal fixed in place in Cosy TOF hall
- Manipulator arm (CMS): Repair ongoing, submodule adapter design (J. Colienne, FZJ)



## Mounting subunits


Stress & displacement in interface when subunit (18kg) is carried by manipulator

$$\frac{18\text{kg} \cdot 9,81 + 0,19\text{m}}{0,096\text{m}} = 350\text{N}$$




## Mounting subunits

Mounting tool to hold the subunits when mounting




- Simulation of coolant flow through backplate and resulting temperature profile at maximum electronics power dissipation (Claudius Schnier)



- Circuit on top/below beam pipe hole: Equal piping drill lengths, no individual flow adjustment necessary
- In-/outlet temperature difference less than 0.1 K, flow of 52 l/min, pressure drop 366 mbar

# Cooling

- Circuit backplate side regions: Calibrated holes in copper disks sealing coolant hose joints to backplane piping drills
- a) no flow adjustment b) adjustment by hole diameter
- In-/outlet temperature difference 0.1 K, flow of 40 l/min, pressure drop 120 mbar





# Cooling

- Experimental verification of simulated coolant flow and temperature distribution (within T range accessible) in Bochum
- Chemical passivation of welded coolant piping needed: Establishing long term water/methanol mixture resistance



# Inner Stiffener Ring

- “Inner Stiffener Ring” completed:  
Inner closing of cold volume (beam surrounding)
- 0.8 mm aluminum sheets folded (2 identical parts)

