



Status Forward Endcap EMC



PANDA Collaboration Meeting 18/3, GSI, November 7, 2018

Thomas Held

Ruhr-Universität Bochum
Institut für Experimentalphysik I



Outline

- VPTT Submodule Production
- APD Submodule Production
- Jülich Installation
- Coolant Flow Adjustment Simulation
- Inner Stiffener Ring



VPTT Submodule Production


- Production of VPTT equipped submodules ran August to October
- All 54 submodules are produced (768 crystals) (42 16-crystal modules, 12 8-crystal modules)
- All submodules light pulser tested in Bochum
- Cosmics tests at Bonn University ongoing
- Constant production and delivery rate of 5 submodules per week
- 20 % (768 crystals) of forward endcap finished




VPTT Submodule Production

- Very valuable cabling guide (6-page document, Bonn)


VPTT HV Pin Assignment by submodule ch numbers



APD HV Pin Assignment by submodule ch numbers



Channel Numeration



View from the backside (cable side), looking towards the target

View as indicated:
socket side



cable side

All views
from cable side

LV Pin Assignment



cable side



socket side

LED Pin Assignment
cable side



socket side

Assignment:



socket side

cable side




Figure 1: Materials and alveole

Start with screwing on the slanted metal interface. Be careful to use the correct one in the correct orientation.

The four crystals in each corner form a unit in regards of the connectors: top left (black), lower left (blue), top right (red) and lower right (green) (see Appendix 6). Each unit needs one black connector the high voltage, one white connector for low voltage and a cable comb for the signal wires. Additionally there are the yellow/green and brown/white LED wires, plus the big silver grounding wires, which should already be connected to the middle screw.







Figure 2: LED, LV, HV cables (from the left) and sleeving preparation; note the missing blue HV wires: this is a VPTT alveole

Now sort the wires of the four crystals in one corner. Then put the LED wires in a cable sleeve. Their plug is located in the middle of the top or bottom respectively. You can extend the sleeve by

VPTT Submodule Production

- Color coded grouping of submodule cables



- 96 temperature sensors fitted
- 2 (1) per 16 (8)-crystal unit

Checkliste Submodulfertigung


- X Y LfdNr: #

OK?

- In addition to QA “Production Test Sheets”:
Checklist to be filled out during assembly

PRODUCTION TEST SHEET		- X Y		LfdNr: #					
PANDA FE EMC VPTT SUBMODULE									
Serial Number	Order Part	VPTT Serial	Part No.	BEFORE Electrical testing			After Electrical testing		
				Temp	Capacit	Induct	Temp	Capacit	Induct
AL	LINKER	08	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	09	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	10	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	11	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	12	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	13	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	14	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	15	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	16	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	17	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	18	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	19	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	20	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	21	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	22	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	23	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	24	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	25	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	26	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	27	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	28	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	29	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	30	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	31	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	32	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	33	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	34	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	35	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	36	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	37	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	38	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	39	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	40	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	41	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	42	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	43	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	44	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	45	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	46	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	47	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	48	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	49	15 15	15.0	15.0	15.0	15.0	15.0	15.0
AL	LINKER	50	15 15	15.0	15.0	15.0	15.0	15.0	15.0

• Kristall-Seriennummern überprüfen	
• Kohlefaseraleveole auf Beschädigungen überprüfen	
• Aluminium-Schirmungen aller VPTT-Einheiten überprüfen	
• Ausheilungs-LEDs testen (Multimeter-Adapter, Einstellung: \rightarrow)	
• Zugentlastungen für LEDs (Tesa-Streifen) überprüfen	
• Masseverbindungen zwischen Masseband und Aluminium-Klebeband, HV-Masse, LV-Masse, Signalkabel Schirmung prüfen (Multimeter Einstellung/Zielwert: $<1\Omega$)	
• Temperatursensoren testen (Multimeter: Ω , Bereich 200 Ω)	
• Orientierung aller Kohlefaserkreuze prüfen	
• Kabel bündeln vor Montage der Mounplate Auf eingeklemmte Kabel achten!	
• Gewinde in der Mountplate testen	
• Korrekte Länge der Schrauben prüfen 1. Mountplate an Inserts: 16 x M4; Länge 12mm (!!) 2. Haltegriff an Mountplate: 4 x M4; Länge 16mm (etwas länger als Schrauben aus 1.)	
• Nach Zusammensetzen: Beweglichkeit der Kristalleinheiten in z-Richtung testen. • Bei zu großem Spiel ($>0.5\text{mm}$) oder vielen wackelnden Einheiten \rightarrow Zerlegen, Capsules prüfen, evtl. Rand abschneiden • Gesamtlänge des Submoduls messen (Messschieber, Angabe in mm) • Oben • Links • Rechts	




VPTT Submodule Production

- Losses: 1 broken crystal unit, 3 broken/vented VPTTs, 2 VPTTs w/ loose mesh dynode, 1 bad temperature sensor
- About 100 VPTTs and preamps spare left
- No spare submodules production, individual single channel exchange if necessary



- Hamamatsu failure analysis report: Detached dynode "very rare case"



HAMAMATSU

HAMAMATSU PHOTONICS K.K.

ELECTRON TUBE DIVISION
3103-8585 (KAWASAKI, MAIWA CITY 430-0101, JAPAN)
TELEPHONE: 81 (0)53-62-0240
FAX: (81)53-62-2202

FAILURE ANALYSIS REPORT

Doc.No.72-0059

November 2, 2018

Customer	UNI BONN
Part Number	Head-on PMT R11375-01
Quantity	1
Serial Number (Shipping Month)	UA0162 (Feb. 2014)
Customer Reference Number	HO-148335

1. Description of concern / Reason of rejection

The detached 2nd grid and no signal

2. Team

HPK: Hiroki Moriya (Dept.22), Ryutaro Obata (QC)

3. Containment Actions/Inspection Result

We confirmed that the mesh dynode was detached as the following picture shows. Then, we checked 100 pcs of stock R11375-01 by X-ray transmission image, and no tubes had this defect.



4. Root Causes

There is a possibility that strength of this mesh dynode was already weak when manufacturing this tube. However, we concluded that this weak mesh dynode is a very rare case which only happened on UA0162, because no other stock tubes have this defect.

5. Corrective Actions

This tube will be replaced with a new one.

6. Verification of Corrective Actions

N/A

7. Prevention of Recurrence

N/A

8. Remarks (Disposition)


We will specially replace UA0162 though its warranty period already expired.

Reported by
Ryutaro Obata
QC department

Approved by
H. Tahara
Harutoshi Tahara
Manager, QC department

VPTT Submodule Production

- Constant delivery rate of 5 submodules per week by Fahrdienst RUB (to Bonn for cosmic tests)
- Submodules w/ handle bar individually enclosed in cushioned boxes (empty boxes returned)




VPTT Submodule Production

- All VPTT submodules currently stored in Bonn, will go to Jülich in one batch when tests are finished



APD Submodule Production

- 4 times as much APD submodules as VPTT submodules
- 4 times 3 months = 12 months
⇒ need to speed up production!
- VPTT submodule mounting in Jülich in parallel!
- Preparation of electronics: Preamp cabling etc.
- APD screening ongoing: Increasing pool of screened APDs for grouping




APD Screening Setup

- Bochum APD screening setup:
Full capacity extension almost finished
- Will give twice the throughput:
250/500 APDs a week (prior to/after irradiation) (shift work)
- Irradiation at Strahlencentrum Giessen running smoothly
- More details in Jan Reher's talk
- One rejection criterion: APD dark current at $M=800(!)$ and $-25\text{ }^{\circ}\text{C}$ after irradiation/annealing less than 10 nA (Headroom for future gain increase according to crystal light yield loss needed!)
- Additional selection criterion (forward endcap/barrel):
Slope of gain curves (dM/dT , dM/dU) (statistics)

Jülich Installation


- Forward endcap support frame and pedestal fixed in place in Cosy TOF hall
- Manipulator arm (CMS): Repair ongoing, submodule adapter design (J. Colienne, FZJ)



Mounting subunits


Stress & displacement in interface when subunit (18kg) is carried by manipulator

$$\frac{18\text{kg} \cdot 9,81 + 0,19\text{m}}{0,096\text{m}} = 350\text{N}$$




Mounting subunits

Mounting tool to hold the subunits when mounting




- Simulation of coolant flow through backplate and resulting temperature profile at maximum electronics power dissipation (Claudius Schnier)



- Circuit on top/below beam pipe hole: Equal piping drill lengths, no individual flow adjustment necessary
- In-/outlet temperature difference less than 0.1 K, flow of 52 l/min, pressure drop 366 mbar

Cooling

- Circuit backplate side regions: Calibrated holes in copper disks sealing coolant hose joints to backplane piping drills
- a) no flow adjustment b) adjustment by hole diameter
- In-/outlet temperature difference 0.1 K, flow of 40 l/min, pressure drop 120 mbar



Cooling

- Experimental verification of simulated coolant flow and temperature distribution (within T range accessible) in Bochum
- Chemical passivation of welded coolant piping needed: Establishing long term water/methanol mixture resistance



Inner Stiffener Ring

- “Inner Stiffener Ring” completed:
Inner closing of cold volume (beam surrounding)
- 0.8 mm aluminum sheets folded (2 identical parts)

