


STT Activities in Jülich

Outline

- **Design optimisation**
- **Prototype construction**
- **Status STT @ COSY**

PANDA-STT Layout

Cross section view



CAD drawing by Dario Orecchini

From inner to outer radius..

- axial straw layers
- skewed straw layers
- axial straw layers including filling layers


Prototype setup



STT Design Update

Optimisation of skewed layers ..

- minimal gaps at corners
- skewed double-layer close-packed
- 1.98mm space to outer axial layer
- one more axial straw layer
- **4400 straws**
- ~ 85% active volume (full cylinder vol. = 100%)
- **21-27 straw layers in radial direction**
 - 8 inner axial layers
 - **8 skewed layers ($\pm 2.89^\circ$)**
 - 5-11 outer axial layers




Straw Wire Crimping

Assembly of straw wire

- wire is stretched by 50gram
- centred and fixed by crimping in both end plugs
- copper crimp pins, gold-plated, 1mm outer diameter
- 0.1mm crimp bore hole
- 20 μm (\varnothing) W/Re wire, gold-plated





straw parts





Straw Wire Crimping Methods

Cut through crimp pin:

crimping
in 1 direction



crimping
in 2 directions





Cutting & photographs
provided by ZAT-FZJ

- **Difficult to fix straw wire position perpendicular to crimp direction**
- Crimp hole diameter 0.1mm
- 1-directional crimping: $\Delta x = \pm 40 \mu\text{m}$ wire position uncertainty
- **2-directional crimping better**


New Wire Crimping Method

- **2-directional crimping leaving**
- **Space for excess material**
- **Homogenous crimping**
- $\sigma_r \sim 20\mu\text{m}$ precision
- **No further improvement**
by 3-directional crimping
- **Tolerance pin in endplug in tube: $\sigma_r \sim 30\mu\text{m}$**
- **Wire sag by gravitation: $\Delta Y^{\text{max}} \sim 23\mu\text{m}$ (1.2m length)**




➔ **Expected wire centring precision: $\sigma_{\text{center}} \sim 40\mu\text{m}$**
(to be verified by data)

Quad-Layer Modules




- **Straw module consists of 4 close-packed layers, glued together**
- **Increased rigidity** compared to double-layer
- **Replacement of single, faulty straws possible**
- **Even number of straws and gas lines per module**

Straw Electric Coupling Layout




Kapton film strip containing..


- crimp pin contact rings
- grounding spots
- HV resistor + capacitor
- **option: (transimpedance) preamplifier**
- **16 channel connector to readout board**
- **only ~ 2-3 cm longitudinal space required**



Straw Modules



Kapton film strips




16ch signal out

Assembly method

- glue straws to a close-packed quad-layer
- add frontend supply and electric contacts
- insert module into STT frame structure

Straw module connections

- signal out ($\times 16\text{ch}$) to RO-boards
- gas manifold pipes, in series to next mod.
- HV cable to supply
- **all at backward end of STT**



Proposed gas manifolds:


- insulated, non-magnetic steel pipes (0.1mm wall)
- 2 pipes for in-/outlet

Test System: STT @ COSY-TOF

Test system for PANDA-STT

- **2740 straws**, stack of 26 planar layers
- **same straw materials & diameter**
- operated inside vacuum at $p_{\text{vac}} < 10^{-3}$ mbar
- **Ar/CO₂ (10%) at p=1.25 bar (abs.)**
- readout: preamps in vacuum, 13m cables, discr.(ASD8) + TDC(GPX)
- **similar calibration method:**
isochrone radius \leftrightarrow drift time

- **~ 1.5 years vacuum environment (2008-2010)**
- no straw gas leakage (no material cracks, diss. glue, ..)
- upcoming beam time: 4 weeks, Jul-Aug 2010



1st beam time in May 2009, 2 weeks
p p \rightarrow pK Λ at 2.95 GeV/c

\rightarrow Status report by Matthias Röder