

© R. Limbach, FZ Jülich

STT & STS1 NEWS

Pre-Installation Straw System QA

Peter Wintz (IKP, FZ Jülich) for the STT group

• STT News

- Readout System
- PANDA Infrastructure & Risk Assessment
- STT Hit Efficiency In-Beam ($\epsilon(r) > 98\%$)

(→ STT / FT readout report in FEE session, M. Idzik & A. Maligne)

(→ talk by G. Perez)

• STS1 Status

- Operation Status and Timelines
- TRB-DAQ and ASIC Tests

(→ talk by P. Kulesa)

• Straw Systems QA

- ASIC/FE-Board Teststand
- Pre-Installation Full Functionality Test (STS1)

STT/FT Readout System

- PASTTRECv1 ASIC order in preparation, contact person: Marek Idzik (AGH Krakow)
- Chip housing option promising, study together with HADES-MDC group
- ASIC technical specifications:
 - Baseline level (BL) dispersion ~ 7 mV (σ), BL trimming range ± 30 mV (2 mV DAC steps), noise level NL ~ 2 -5 mV
 - Common discriminator threshold per chip (2mV DAC steps)
 - Observation: up to few 10 mV BL differences channel-to-channel
- Channel-individual BL tuning for each ASIC mandatory (\rightarrow BL lookup table)
 - Krakow: BL detection method and auto script using noise rates, check with ^{55}Fe (X-ray) and time-over-threshold alignment
 - Jülich: BL tuning off-detector (testpulse & NL), on-detector check with ^{90}Sr (β -tracks) and time & time-ovr-threshold alignment
 - Results: off-detector BL = on-detector BL, independent on gain factor and shaper parameters

PANDA Experiment Infrastructure




Technical Design Report & Risk Assessment

- Technical Design Report paper by TCs et al. (L. Schmitt, A. Belias et al.), 109 p.
 - PANDA installation with sub-systems coordination, installation scheme and timelines
 - Infrastructure and resource requirements
- STT specific issues (next slides)
 - Central systems frame in TS
 - TS mounting platform w/ clean room close-by
 - Gas supply infrastructure
- Workplace safety & risk assessment by FAIR upcoming
- STT risk assessment document in preparation

Central Systems Frame

Taken over by GSI/Part of Experiment Infrastructure

- Carbon-Fiber structure on insertion rails






- Support for beam pipe, MVD, STT semi barrels
- Separate support for MVD upstream routing
(no load on thin beam pipe)
- CAD design by S. Koch (GSI)

TS Mounting Platform Layout

Central Systems Requirements


- Extended platform with more surrounding space for assemblies, target system devices and clean room
- Central systems on elevated installation platform
- Platform will be lowered to exact insertion height



Gas Supply Infrastructure

Gas Supply & Mixing Sections for Detector Subsystems

- Gas bottle storage area
- Gas supply area with mixing stations
- Gas distribution to detectors
- STT gas system:
 - Mixing station MS1
 - Driftgases: Ar, CO₂, (Ar/CO₂)
 - N₂ (Flushing)
 - Optional: addit. quencher: C₂H₆, i-C₄H₁₀
 - Pressure controlled gas supply lines (up to 24)
 - Gas flow / pressure controls and alarm modes
 - Generic test system (EPICS) set up by IFIN Bucharest



Reminder: STS1 System For Phase-0

PANDA-FT3/4 Layout & Dimensions

- 4 Straw double-layers
 - Orientation: $\varphi = 90^\circ, 0^\circ, 0^\circ, 90^\circ$
 - Z-distances: 118.6 mm, 281.4 mm, 118.6 mm (d-layer middle z posi.)
 - 20 modules w/ 16 straws each
 - Beamhole by split straws (2x8 straws per d-layer)
 - Module perp alignment by Rohacell/CF bars (2x0.3 mm CF tapes)
- Straw specs
 - 27 μ m Al-mylar film, \varnothing_{ID} =10.00 mm, 766mm length
 - Straw pitch: 10.14mm, z-pitch in d-layer: 8.78 mm
 - Ar/CO2 at 2 bar (abs.)
- Electronics:
 - 704 readout channels
 - 44x FEBv3 w/ 88x PASTTRECv1 (a 8 ch)
 - 4x TRB3, 1x RO crate

FEBv3 with two ASICs



STS1 Station




STS1 Operation Status

System Set-Up in Julich

- Detector gas tightness on permeation level since 3 months OK
- Detector fully cabled, FE-boards mounted OK
- All FE-boards tested & tuned off-detector OK (but no spares!)
- High voltage operation (OK)
- EMI/noise level seems rather low ($\sim 2\text{mV}$) OK
- Final system QA with 90Sr and test of all channels (ongoing)
- Old DAQ (single TRB3) running, Root-based data format & analysis SW
- New DAQ (multi TRB3, new firmware) prepared
 - TRB multiplicity trigger in preparation by Pawel (support by Jan Michel, GSI)
 - Cosmic data-taking started
- STS1 Installation in HADES in 2nd half 2020

MQT signal
cables




HV boxes


Gas in-/outlet lines

STS1 System QA

^{90}Sr Detector Scan



^{90}Sr source movable
with finger scintillator
(trigger)







Settings:

- Gas mixture: Ar/CO₂ (20%)
- HV: 1750V, gas gain $A \sim 1 \times 10^4$
- ASIC: gain=2, pkt=20ns, thr=10mV
- Noise level ~ 2 mV (= DAC step size)
- ASIC BL tuned off-detector with pulser
- ^{90}Sr β -source scan along detector
- 1mm thin scintillator for trigger
- Drift time and time-over-threshold measurement

System QA Test with ^{90}Sr Source

Comparison Drift Time and Time-over-Threshold Measurement








- Similar spectra for β -tracks and proton beam tracks
- ^{90}Sr ideal for complete system functionality test

System QA Test with 90Sr Source

ASIC Tune Check by Drift time and Time-over-Threshold


- TDC time spectra & fitted time offsets
- Time-over-threshold fit per channel
- Off-detector BL tune taken
- 6 (from 144) channels to be further checked (red arrow marked)




ASIC Tuning Example

TDC Time-over-Threshold before & after BL Tuning

Coarse/improper BL setting



After BL tuning



Pre-Installation Straw System QA



Proposed Procedure

- Off-detector ASIC/FE-board (teststand):
 - Single ASIC/FE-board control and failure test (no bit errors, no missing channels)
 - BL determination by noise scaler rate, BL lookup table for all FE-boards and individual channels
 - Observation so far: ASIC BL off-detector = BL on-detector, BL is gain and shaping parameters independent
- System full-functionality QA test:
 - Connect FE-boards to straw modules and to TRB readout, straw module connected to gas and HV
 - Scan of all channels with ^{90}Sr source & trigger scintillator
 - TDC time and time-over-threshold spectra and alignment check for each channel
- Reminder: STT front-end space and access restricted, failure detection & component replacement difficult
- QA of STT modules (4-layer) with ^{90}Sr scan should be done before the main detector assembly

*Thank you
for
your attention*

Backup

