

# Control System towards FAIR Commissioning

Workshop on Controls Development for FAIR Commissioning  
and GSI Operation of Existing Acc. Complex

Ralph C. Bär

16.09.2020

# FAIR Commissioning Phase

## Commissioning

*“Process of assuring that all systems and components are designed, installed, tested, operated, and maintained according to the design and operational requirements of the project owner (e.g. WPL, equipment specialist, SPL) until the final handover to operation”.*

## Key Aspects of Commissioning

- Comprehensive unit tests → testing procedures, sequences, check-lists
- Definition of interfaces → which & when a given functionality required, definition of entry conditions & lead times to achieve these functionalities)
- Definitions of goals → exit conditions
- Documentation of executed tests

## Targets


- Commissioning of the Control System itself  
→ While being the fabric and tool for other equipment, the CS is by itself is a complex collection of sub-systems that also need to be commissioned.
- Control system support to commission accelerator components, systems, the accelerator
  - Individual component/system tests
  - Integration tests
  - Higher level tests → Dry-runs → Commissioning with beam

# Control System Commissioning

## Iterative Development Approach

The control system is not a monolithic single system that follows (or for the matter can follow) a simple start/stop development paradigm

- CS is a collection of sub-systems bound by a robust middleware, timing system, settings management system, ...
- Evolving standard best tracked by CI (continuous integration), continuous delivery and agile programming paradigms rather linear start/stop, functionality and interfaces are often complex and require re-iterations.



## Accelerator Control System Commissioning

- The Controls infrastructure team provides technical networks (Ethernet, Profinet, WR Timing, Interlocks) → pre-requisite for all equipment groups  
Installation and commissioning of the technical networks as soon as the civil construction progress/conditions allows (and installation makes sense)
- Control system commissioning strategy  
→ test as much at the existing facility prior to starting FAIR hardware commissioning  
→ work out commissioning plans for functions not testable at existing machines

# Control System Commissioning Support

## Commissioning Support

CS needs to provide tools to support to commission components, systems, the accelerator

- Individual component/system tests (responsibility WPL)
- System integration tests
- Higher level tests → Dry-runs → Commissioning with beam (responsibility SPL)

Essential tools for this phase:

- Sequencer service (automation, semi-automation)
- Archiving (measurement DB) to store test results and PM data
- Diagnostic logging system

Further technical support requests shall be identified after the FAIR machine presentations of this workshop

# Sequencing and Semi-Automation


## Sequencer

- Essential tool for operation and commissioning
- Sequencer service under development → presentation by Stefan Krepp (ACO)
- Optimize routine tasks so that operation crew and commissioning team can focus on more important tasks that cannot be automated
- Sequencer tasks: big time-saver for large-scale equipment acceptance/integration tests, re-commissioning, or dry-runs

## Testing Approach

- Controls provides the sequencer service ("the tool")  
however: exploitation of the sequencer needs to be done by users
- Users need to define precise test procedures, entry conditions, dependencies to other systems, etc.
- User writes sequences/tasks with the sequencer (code)
- Controls can support coding of sequences/tasks on best effort and resource capacity
- Equipment specialists need to follow complete development cycle of their equipment (including controls integration)
- Lead-times must be considered (i.e. resource load)
- need to practise on small scale tests before ramping up procedures to full FAIR

based upon/learn from previous experience  
<https://edms.cern.ch/document/874724/>

CERN CH-1211, Geneva 23 Switzerland		
EDMS NO. 874724	REV. 4.1	VALIDITY RELEASED
REFERENCE LHC-MPP-HCP-0006		
Date: 2016-01-08		
 LHC		
<b>MP3 Procedure</b> <b>Test Procedure and Acceptance Criteria for the 60 A Circuits</b>		
ABSTRACT: This document describes the test procedure and the acceptance parameter specification for the 60 A circuits. A list of the parameters to acquire during the tests is given.		
PREPARED BY: MP3	CHECKED BY: MP3 Oddi Andreassen Annalia Ballarino Jean-Christophe Garnier Mirko Pujer Felix Rodriguez-Mateos Rudiger Schmidt Matteo Soffiani Carlinucci Yusei Thuret Jörg Weieringer Markus Zentgraf	APPROVED BY: Luca Bottura Jean-Paul Burnat Dimitri Delikaris Mike Lamont Andrzej Siemko

# Activities, Contributors and Priorities

The control system is not exclusively the product of the Controls department, several other departments/partners contribute to the full set of the CS

→ Biggest workload/effort is **software development**

Overview table for Software Development prepared\* (Draft RFC)

- Tool to visualize, organize, and prioritize developments
- Harmonize and coordinate developments, avoid (unintended) double-developments
- Define clear scope of responsibilities

→ **Table should be carefully reviewed by the sub-projects**

further input should be added, suggestions to improve welcome!

Definition of priorities:

- 1: Essential function: no operation without
- 2: Important function: operation at the expense of personnel resources & (in)efficiency
- 3: Required function for quality- and high intensity operation
- 4: Operation with degraded operational efficiency possible

Project phases:

- HWC: Hardware commissioning
- BC: Beam commissioning
- OP: Operation

*\*special thanks to SIS100 project team (Spiller/Ondreka/Steinhagen)*





## Activities, Contributors and Priorities

	Activities		Executing Departments (directly involved in SW development)											SPL Requester Anforderer	Phases Phasen			Prio (1-4, Erläuterung siehe rechts)	Status		
			ACO	BIT	BEA	SFR	SRP	RRF	OPE	SYS	DEC	APH	CRY		EXP	HWC (& controls)	BC (& dry runs)			OP (user)	
	Description	Kürzel																			
Facility Control	Cryogenic Controls																				
	Cry plant (Cryo2) control (integration only)															COM				1	
	Cryo distribution control															COM				1	
	SIS100 dynamic load predictions															SIS				3	
	Vacuum Controls															COM					
	Vacuum control and safety															COM				1	
	Cryo insulation vacuum control															COM				1	
	Building services engineering (TGA) Monitoring																				
	Monitoring of accelerator media																			4	
	Electrical load monitoring (pulse/common mains)															SIS				3	
	Cooling water temperatures																			4	
	Cooling plants																			4	
	Ventilation/cooling																				
	Sequential Facility Control incl. Apps	Timing																		1	
	Timing Master															ACC				1	
	Timing Director															ACC				1	
	Request Processor															EXP				1	
	Scheduling	BSS Control														ACC				1	
	Pattern Creation	Scheduling App														ACC				1	
	Machine and Beam-Mode Control															ACC				1	
	Timing Monitor & Diagnostics															ACC				2	
	Personnel Safety																				
	Radiation Protection System															SRP				1	
	Acc. Personnel Access System (PAS)	PAS														SRP				1	
	Machine Protection																				
	Device Status Monitoring and Interlocking	MASP														all				1	
	Fast-Beam-Abort-System – SIS18/SIS100	FBAS														SIS				3	
	Fast-Beam-Abort-System - primary beam lines	FBAS																		3	
	Fast-Beam-Abort-System – SuperFRS	FBAS														SFR				3	
	Fast-Beam-Abort-System – Experimente	FBAS														EXP				3	
	Fast BLM System																			3	
	Permit-Service (Powering, Movable Devices)	MASP																		3	
	Acc. Facility Overview																				
	Status Machine(s)																			1	
	Beam Production Chain Status																			1	
	Online Timing & Scheduling Monitor															ACC				1	
	Status Industrial systems (vac, cryo)																			2	
	Fixed-Display (web-based)																				
	Accelerator Facility Status															ACC				1	
	Ind. Machine Status															ACC,SIS				1	
Beam-Production-Chain Status	BPC Status														SIS				1		
Experiment Status															EXP,ACC				1		
Machine Availability Analysis Tools															OPE				4		
...																					

## Activities, Contributors and Priorities

Activities	Executing Departments (directly involved in SW development)														SPL Requester Anforderer	Phases Phasen			Prio (1-4, Erläuterung siehe rechts)	Status			
	Description	Kürzel	ACO	BIT	BEA	SFR	SRP	RRF	OPE	SYS	DEC	APH	CRY	EXP		HWC (& controls)	BC (& dry runs)	OP (user)					
<b>Settings Supply</b>																							
Device and beam parameter settings	ParamModi														ACC							1	
Machine modelling	LSA make-rules														ACC							1	
<b>Beam Monitoring</b>																							
Beam-Transmission-Monitoring	BTM														ACC							2	
Beam-Quality-Monitoring	BQM														SIS,DEC							3	
Multi-Parameter-Beam GUI															APE							3	
<b>Beam-Based Control Systems</b>																							
inj./extr. trajectories (BPM-based)															SIS							1	
trajectory control HEST	"Benno"														COM							2	
closed-orbit and radial-loop															SIS							1	
Q/Q' control															SIS							3	
Multi-Turn-Injection	MTI														SIS,DEC							3	
Bunch2Bucket beam-transfer	B2B														SIS							1	
Slow-Extraction															SIS							3	
Slow extraction optimisation (spill form/structure)																						2	
optics measurement & correction															SIS							3	
Collimator/Cleaning set-up – SIS100															SIS							3	
Collimator/Cleaning set-up – SFR															SFR								
MPS validation – SIS100															SIS							3	
MPS validation – Super FRS															SFR								
beam-cooling optimisation															SIS							3	
final-focus control ( $x/y, x'/y', \beta, \dots$ )															COM							3	
RF bunch gymnastics															SIS							2	
Post-Mortem-Analysis															SIS,SFR							3	
PM data acquisition readout and persistence	PM																						
superconducting magnets (quench analysis)															SIS,SFR							1	
beam-related losses (FBAS, pBar operation, ...)															SIS,PLI							3	
<b>Control local cryogenics</b>																							
Visualisation, semi-automatic control (sensors, pressure, temp., actuators, heater, ...)															SIS,SFR,COM							1	
Automation processes/sequences															SIS, COM							3	
<b>Other semi-automated procedures</b>																							
Parameter scan															SIS,OPE							4	
...																							



# Activities, Contributors and Priorities


	Activities		Executing Departments <small>(directly involved in SW development)</small>													SPL <small>Requester Anforderer</small>	Phases Phasen			Prio <small>(1-4, Erläuterung siehe rechts)</small>	Status			
			Description		ACO	BIT	BEA	SFR	SRP	RRF	OPE	SYS	DEC	APH	CRY		EXP	HWC <small>(&amp; controls)</small>	BC <small>(&amp; dry runs)</small>			OP <small>(user)</small>		
	Description	Kürzel																						
Equipment Control	Accelerator equipment control & tools/GUIs		FESA																			1		
	Power converter control (all)			█																COM			1	
	Ring RF equipment control								█											COM			1	
	Pulsed power systems control			█																COM			1	
	Stepping motor control			█		█														COM			1	
	Beam instrumentation systems					█														COM			1	
	Maschine-specific FESA classes (various)			█																COM			1	
	Digitizer Systems & Generic DAQ App			█																COM			1	
	...																							
	Expert tools & GUIs (per device/machine)																							
	DCT					█																		
	ACT					█																		
	FCT Ring and Transfer Lines					█																		
	BPM (by type/machine)					█																		
	RSA, SIS-Radio					█																		
	Lassie					█																		
	IPM					█																		
	BIF					█																		
	Profile grids					█																		
	Cameras					█																		
	HV control					█																		
	MAPS2					█																		
	BIF					█																		
	BTF Scan					█																		
	IonSource GUI			█							█													
	UNILAC Energy measurement (ToF)					█																		
	Schottky – Machine											█								SIS			3	
	Schottky – Experiments															█								
...																								
Fast-Beam-Abort-System (Controller)			█							█												3		
Bunch-2-Bucket System (low-level timing)			█							█										×		1		
Device Control GUI			█																			1		
Actual-vs-Reference-Monitoring/Interlocking											█								SIS		×	2		
Integration of generic sensor data and actuators (e.g. cryogenics, vacuum)												█										2		
Data Concentrators (PBM, ...)			█																			2		

# Activities, Contributors and Priorities

	Activities		Executing Departments (directly involved in SW development)													SPL Requester Anforderer	Phases Phasen			Prio (1-4, Erläuterung siehe rechts)	Status	
			ACO	BIT	BEA	SFR	SRP	RRF	OPE	SYS	DEC	APH	CRY	EXP	HWC (=& controls)		BC (=& dry runs)	OP (user)				
	Description	Kürzel																				
<b>Generic Services</b>	LSA-Settings-Management	LSA																				
	Device setting supply (drive)																				1	
	Multi-Parameter-Beam infrastructure																				3	
	Management of Critical Settings	MCS																			3	
	Front-End Software Architecture	FESA																			1	
	Generic Control Room Apps (not machine specific)																				1	
	Beam Request System to users (App, API)																				1	
	Machine-Experiment Data Exchange Interface																				4	
	Archiving-Service																					
	Archiving System																ACC				1	
	Generic data visualisation and retrieval																					
	Role-Based-Access Management	RBAC																			1	
	Sequencer Service	Sequencer																			1	
	Diagnostic Logging																				1	
	Post-Mortem-System	PM																			1	
Generic Digitizers (non-BI)																SIS				1		
Measurement data visualisation	chart-[fx,Qt]															SIS				1		
Middle-Tier-Services (equip. & beam-based))																SIS				1		
...																						
<b>IT Infrastructure</b> (for services / für Dienste)	Accelerator IT cluster system																			1		
	General services															SIS				1		
	Development environment & tools																			1		
	Continuous int. & dev. Environment (CI/CD)															SIS				1		
	Container management services																			2		
	Version control systems																			1		
	Electronic log book (operation)															ACC				1		
	User-account management (auth services)															ACC				3		
	Accelerator Databases																			1		
	Network Infrastructure (technical networks)																			1		
	Ethernet, Profinet, White Rabbit																			1		
	Active components (switches, firewall, ...)																			1		
	Technical equipment Control Room (FCC)															ACC				1		
...																						

# Structured Communication

## Controls Internal Organisation



Development and Commissioning phase require clearly structured responsibilities and communication.

### MCC (Machine Controls Coordinators)

- Meetings and communication is usually organized “per accelerator”
- MCC serves as contact person for all matters concerning specific machine
- MCC organizes activities for respective machine within the Controls group



thank you!