



APPA Experiments at FAIR: integration in the control system

A.Bräuning-Demian
for APPA collaborations,

with support from: A. Blazevic, Ch. Gräff, A.
Kalinin, B. Merk, W. Nörthershäuser, N.
Petridis, R. Pleskac, R. Sanchez, D.
Winters.....



Finland



France



Germany



India



Poland



Romania



Russia



Slovenia



Sweden



UK



Czech Rep.



APPA at FAIR: who are we?

- Collaborations
- Working areas
- Setups / Experiments

What for do we need support?

- permanent and temporary component integration in the accel control system
- special information from the controls to be integrated in the experiment DAQ
- users access to the controls for optimisation
- implementation of special features
- assistance by configuration changes

What kind of support?

- specialized man power for design, implementation and commissioning
- specialized assistance by non standard applications
- starting with now, a permanent support will be needed



What I will not present today : a detailed list of activities and a time line.

We do have a catalogue draft which we can provide to help the evaluation of the needed resources.

Minutes Controls APPA cave

Anwesend: F. Hagenbuck, A. Krämer, R. Bär, D. Severin, A. Braeuning-Demian

Date: 25.08. 2017

Subject: For the beam transport and control along the two beam lines from APPA cave, the APPA collaborations propose to include the magnets, beam diagnostics and vacuum valves along the beam lines in the HEBT control system. For beam transport to the target points, placed at the end of the two beam lines, and the initial beam setting **the operators need access** to the above mentioned components. Therefore, the collaborations suggest integrating them in the accelerator/beam transfer lines control system. However, **local control over the beam is requested** also, for final settings and changes during the experiments without the intervention of the operators from the main control room.

For a decision concerning the feasibility (technical requirements and man power) following points still need some clarifications from the collaborations:

-
-
-

- **Who is APPA?**

- BIOMAT: Biophysics and Material science

- HED@FAIR: Plasma physics

- SPARC: Atomic physics

- **Who is APPA?**

BIOMAT: Biophysics and Material science


HED@FAIR: Plasma physics

SPARC: Atomic physics

- **Working areas (FAIR Green paper)**

@FAIR: APPA cave,
SIS100, HESR, CRYRING

Experimental areas for Day-1 experiments



Who is APPA?


- BIOMAT: Biophysics and Material science
- HED@FAIR: Plasma physics
- SPARC: Atomic physics

Working areas (FAIR Green paper)

@FAIR: APPA cave, SIS100, HESR, CRYRING



@GSI: cave M, cave a, M-branch, ESR, HITRAP

Experimental areas for Day-1 experiments







APPA Setups and Experiments

'small', variable setups




- fix-target
- in-ring
- irradiation/scanning





- all collaborations
- two beam lines
- 5 target points
- variable setups
- no parallel operation
- beams from SIS18 and SIS100

The HED beam line




HED beam line control requirements

System	Component	Room
Beam transport	<ul style="list-style-type: none"> • 4 nc Quadrupole • 4 sc Quadrupole + Feedbox und Quenchprotection • 5-6 Valves 	Control from HKC Control room HED
Beam Diagnose	<ul style="list-style-type: none"> • 2 Screens • 2 FCT 	Control from HKC Control room HED
Vacuum control	<ul style="list-style-type: none"> • 2 Turbo-/Rough pumps Beam line • 5 Turbo-/Rough pumps form the Cryostat und Feedbox • 3 Turbo-/Rough pumps target chamber • Vacuum gauges 	Control from HKC Control room HED
Timing and Timing Laser	<ul style="list-style-type: none"> • 1 Trigger 50 μs vor Ionenstrahl in TK, $\Delta t \leq 1 \text{ ns}$ • 1 periodisches Signal, $f = 50 \text{ hz}$, 100 ms vor Strahl, $\Delta t = 0,1 \text{ ns}$ • 1 periodisches Signal, $f = 0,5 (+-10\%) \text{ Hz}$, 400 μs von Ionenstrahl in TK, $\Delta t \leq 0,5 \text{ ns}$ • 1 Triggersignal 4 μs von Ionenstrahl in TK, $\Delta t \leq 0,5 \text{ ns}$ 	Control room HED
Work protection	<ul style="list-style-type: none"> • Interlock signals for cave and laser protection system 	Control room HED

Specials:

- variable setup
- control also local, in the HED own control room
- Special beam manipulations
- stringent timing requirements



- magnets, FAIR standard and non standard
- beam diagnostics
- valves
- vacuum pumps
- stepping motors
- compressed air actuators

Control:
standard and special request
for the different experiments

General requirements

- (standard) beam diagnostic components included in the accelerator control system (BIOMAT beamline)
- (standard) vacuum components included in the accelerator control system (BIOMAT beamline)
- possibility to connect/disconnect components defined in the accelerator control system (BIOMAT beamline)
 - request on high flexibility of the BIOMAT beamline, especially at its end in the target area
 - on average, it happens once a year
- FAIR timing system (BIOMAT control room)
- analog signals from accelerator (BIOMAT control room, digital → analog signal)
- access to database of the accelerator control system (necessary for advanced analysis of experimental data)

Special requests

- beam on/off request (BIOMAT control room)
- fast cutoff of the beam delivery (BIOMAT control room)
- spill-start/spill-stop analog signal (BIOMAT control room; digital → analog signal)
- scanning of the beam (BIOMAT beamline + BIOMAT control room + FCC)
 - own scanning control system communicating with the accelerator control system
 - scanners are fully controlled by user himself including switching them on/off
- double-scattering system included in the accelerator control system (BIOMAT beamline + BIOMAT control room)





General requirements

They are exactly the same as those for BIOMAT facility.

Special requests

*They are exactly the same as those for BIOMAT facility **except for these two differences:***


- ✓ *there is no double-scattering system in cave M / cave A*
- ✓ *scanning control system in cave M / cave A: a simplified 2D-table with set values for beam energy and intensity implemented into the accelerator control system*
 - *scanners are fully controlled by user himself - own scanning control system*



- variable setups, at different positions in the ring
 - integrated in the ring
 - detection system which are decoupled from the ring
 - any change in the setup means intervention in the ring vacuum
 - laser systems coupled to the ring
 - the operation of the experiment is closely connected with the beam manipulation in the ring; some experiment component must be 'touched' by the control system at a defined time.
 - user's own control systems needs signals from the machine
- + once some functionalities defined for one ring they can be transferred to the next storage ring

Internal Jet Target at Storage Rings

- 14 turbomolecular pumps
- 1 roots pump and 2 fore-pumps
- 10 pressure gauges
- 4 vacuum valves (gate and venting valves)
- 10 gas-line-valves
- 4 stepping motors
- 2 pressure-regulators
- 2 manometers
- temperature controller
- target-switch (on/off)



Vacuum Controls

Measurement of 12 input channels (analog signals) – inlet and dump chamber, fore-vacuum, in-ring vacuum

Control of 2 gate valves protecting the in-ring vacuum, control of 2 venting valves

Control of the gas line hydrogen security valve

Control of the start-up and close-down sequence of the target station vacuum

A detailed functional description will be provided by the target group

SCU unit: target parameters

The input of the vacuum controls is needed (current values)

Control of the temperature controller (external company: Lakeshore) - measurement and control of the temperature

Control of 2 pressure regulators (analog signal, 2-10 V)

Measurement of 6 temperature sensors (cooling water, control cabinet – analog in 0-2 V)


Control signal ,target on/off' within the FAIR control system (timing)

Control of a flowmeter device (already implemented)


Control of 10 gasline valves (pressurized air, on/off, analog signal)

Cosylab controllers

Control of 4 stepping motors (Beam Diagnostics Department)



Stand: 21.02.2020




Injection
from CR

PANDA

Stand: 21.02.2020


SPARC at HESR: variable, non permanent setup



- magnets, non FAIR standard
- valves
- vacuum pumps
- stepping motors
- linear actuators
- internal target
- laser
- particle detectors
- scrapers
- timing signal for synchronization

Laser

Stand: 21.02.2020



Will be discussed with the SIS100 control system

- the large experiment diversity of APPA experiments will be reflected also in the implementation of the control for the beam setting, experiment components control, access to setting data and selected parameters
- the collaborations are ready to provide more detailed information about their special needs
- a discussion about the technical and resourced-based feasibility of our request is needed
- the prioritisation and the time line for the realisation depend on the civil construction time line and can be only partially specified today
- a close exchange between the users and the control groups, as already practiced in FAIR Phase zero is highly desired from our side