



Collector Ring Beam Diagnostics Status



Yury Rogovsky

on behalf of the Budker INP team

10 November 2020, Novosibirsk



Collector Ring Beam Diagnostics Status



Yury Rogovsky


on behalf of the Budker INP team

10 November 2020, Novosibirsk

**The half a year progress
will be reported.**

Beam Instrumentations @ CR machine

Device	Qty	Parameter	Application
DC Transformer	1	DC current	Stored current, beam lifetime
Cryogenic Current Comparator	1	DC current	Stored current, beam lifetime
BPM	19	Beam center-of-mass	Closed orbit, turn-by-turn, K-modulation, lattice functions
BTF Exciter	1	Frequency of Schottky sidebands	Tune by BTF, tune by noise excitation, tune by Q-kick
Schottky pickup	1	Momentum distribution	$\Delta p/p$, tune, chromaticity
Fast Current Transformer	1	Broadband bunch structure	Longitudinal emittance, bunch gymnastics
Residual Gas Profile Monitor	2	Beam profile	Transverse emittance, injection matching
Beam Loss Monitor	Distributed	Beam loss	Mis-steering of magnets, halo detection at scrapers
Scintillating Screen	5	Beam profile	First turn diagnostics
Beam-Stopper	2	Stop the beam	First turn diagnostics
Scrapers	2x4 2x4	Beam size	Transverse beam size and beam alignment



- TCR1 beam instrumentation not covered by this talk, but has the same design mainly (except one BPM @ final part which is not developed fully).
- SFRS / Pbar “lost diagnostics” – beyond the scope of this talk.

Efforts in 2020 short overview

Spec			FoS	FAT	SAT
------	--	--	-----	-----	-----

- Pickups – FDR done in Nov-2019. Wide prototype is under intensive study. Small prototype manufacturing is ongoing. One of TCR1 pickup still not designed yet.
- Scrapers – FDR done in Nov-2019. Docs are finalized. Wide type manufacturing is ongoing (> 80%).
- Scintillators – CDR released. FDR coming soon. Scintillating plates partially produced. Optical components are received. Manufacturing has been started (>10%). Procurement stage.
- Stoppers – CDR released. Design is finished. FDR upcoming.
- RGM – CDR docs are nearly finished. MCP will be ordered.
- FCT, DCCT – CDR, FDR released. Purchase via FAIR is assumed. Annoying item: TCR1 FCT is not contracted!




Wide pickup prototype




Pickup preamplifier prototype

Scrapers vacuum chamber parts



Test Stand Discussions



RGM 3D-model



Scraper 3D-model



Scintillating screens: manufactured plates, received objectives & CCDs



FCT and DCCT for CR

December 2019


	NPCT-CF8"-147.6-120-UHV-	6"	DN160 NW150CF	147.6	120.0
~120 k€	NPCT-CF10"-198.4-120-UHV-	8"	DN200 NW200CF	198.4	120.0
	FCT-CF10"-147.6-40-UHV	6"	DN/NW200CF	147.6	
~40 k€	FCT-CF12"-198.4-40-UHV	8"	DN/NW250CF	198.4	
			Axial length H		40.0

Now (Price List November 9th, 2020) stay the same as in April. **Next year?**

125 k€ and 42 k€




Purchase letter for FAIR preparation started.

- CDR / FDR passed.
- Commercially available devices from BERGOZ (Genève). We keep contact.
- Purchase via FAIR is assumed. Looking forward for any news or procedure.
- **NB: Budker INP team must be involved in process. Not all options still available from BERGOZ.** (for an additional k€ => NPCT with 2 mA range)
- **Annoying item: TCR1 FCT is not contracted! Must be clarified this year.**



- DCCT: comes with electronics
- FCCT: amplifier required (selected one – DUPWA-1-70 by FEMTO)

Beam Position Monitor for CR (I)




- Concept finished. Mechanical development was done. **Minor changes in electrodes shape for Type-1, caused by optimization of production technology.**
- **All 3D Models (1,2,3) ready are ready.** Procurement of most components done.
- **FDR presented. FDR documents pack** – 1st, 2nd internal review passed;
- **Many discussions with GSI QA. FEM analysis ready for Type-1. Other in progress.**
- **FoS: 100% of Type-1 BPM combined with vert. dipole corrector done.**
- **Open questions:** Libera A110 – 19pcs – not in 2nd Amendment for the "FAIR orders components for BINP". The same for TCR1 – 5pcs.
- **Minor changes in VGA control. Not finished with FZJ. Will be discussed later.**




Beam Position Monitor for CR (II)

Type-1 Electrodes was reviewed against: Mechanical stability and rigidity; Production efficiency; EM properties; Positioning and tolerances.


Change the shape (only it) of electrodes: **super-elliptical** => **octagonal**.



Simulations:
No valuable changes in freq. response @ 0 – 10 MHz;
Capacity 5% lower (~150 pF);
Cross-talk approx. “the same”.



Beam shape @ BPM Type-1 for Pbar optics.
Proposed shape is shown in red color.




Beam shape @ BPM Type-1 for RIB optics.
Proposed shape is shown in red color.

Beam shape in different BPMs shown as pink. We still fit the requirements.

All drawings for the octagonal electrodes are in production. Passed technical checks. Tooling produced. Waiting for materials.


Beam Position Monitor Test Stand (I)




Interface to PC, RSI profile for whole stand, motors and LIR (with encoders).

DELIVERED TO BINP.

- LNA and VGA parts prototypes from FZJ delayed due to COVID.
- Production of the test stand is ongoing. About 90% ready.
- Test stand commissioning is expected in Q1 2021.




Test stand development finished.




Beam Position Monitor Test Stand (IV)

- The 3D view of the whole installation.
- The stand concept can be modified for Type-2,3 detectors.



Beam Scraper for CR (I)




Received




Oriental 5-phase motor. Micro Switch.



Received



Item	#	Status
Standard Metric Inverted Rotating Screw Actuators: DE2626-0310, DE2626-0210,	22	Waiting for Delivery
Ball Splines SSPF Type: SSPF40A-1-430, SSPF40A-1-405 , SPF40A-1-320	22	Delivered
Coupling): BKL/003/10/	22	Delivered
Stepper Motor: PKP569FN24A2	22	Delivered
Switch: S880W2G6k	150	Delivered
Linear Motion Conductive Plastic Potentiometers CFL300, CFL200	22	On the way to BINP
Bellows Units DN102,5/150-35, DN102,5/150-50, DN102,5/150-55	22	Waiting for Delivery
Connector Souriau Type UTG01412P 9.	22	Delivered
Pin Souriau Type RM16M23K	264	
Connector Souriau Type UTG0128P	22	
Pin Souriau Type RM24M9K	176	
Lemo Connector - Lemo PCA 0S 302 CLLC 42	44	





- Concept finished. Mechanical development was done.
- **Model / Drawings ready.** Procurement of most components done. Production.
- **FDR presented. FDR documents pack – 1st, 2nd, 3rd internal review passed;**
- **Many discussions with GSI QA was in Spring (comments was taken into account).**
- **FEM analysis done (Fiducials shift less than 50 um), no valuable deformations.**
- FDR for final check will be uploaded soon (after BINP QA check).
- **Open questions:** MBOX PDC – 5pcs – not in 2nd Amendment for the "FAIR orders components for BINP".

Beam Scraper for CR (II)

Produced at BINP

Stepper Motor


Mechanical Coupler



SSPF Ball Spline

Vacuum Chamber

Mechanical Stand




Produced at BINP Workshop

POTENCIOMETERS in a way to BINP!

From Carles Sadurni (MEGATRON Elektronik Manager):


“Our distributor in Russia (Elcompribor) did buy from us 8 pieces of the CFL 200 and 14 pieces of the CFL 300, which were sent on October the 7th to them. I assume they have already been delivered to the BINP in Russia, so unless this is a different subject, I don't understand where the problem lays: We have already quoted und delivered the items.”

Beam Scraper for CR (III)



All these stuff produced at 2020



Scintillating Screen for CR (I)




Vacuum / mechanics ordered.

Waiting for payment.


- Concept finished. Mechanical development was done.
- Model / Drawings ready. Procurement of few components done.
- CDR presented. FDR documents pack – 1st, 2nd 3rd, internal review passed;
- Many discussions with GSI QA was in Spring (comments was taken into account).
- FEM analysis in final stage (~ no problems). Production of parts was started.
- FDR for final check will be uploaded soon (after BINP QA check).
- Components: IDS UI-5240SE camera and Computar MG1616FC objective lens is “standard” solution for FAIR. FESTO pneumatic cylinder is well-known.



Scintillating Plates for CR (II)




P43 coverage in Moscow Institute of Physics named after A.M. Prokhorov, December 2019.




Delivery of Detectors to BINP, February 2020.
First pack for Type-1. Delayed due to COVID.

- Quality tests of the P43 coverage was performed in August at BINP.
- Phosphor coverage thickness is about 100 μm ($1.2\text{-}1.4 \text{ g / cm}^2$).
- Test was done with defocused electron beam: 0.5 mA, $E = 60 \text{ keV}$ as well as X-Ray beam $E = 40 \text{ keV}$ (see figures below).
- The photon flux looks enough for the operations even at low intentions @ CR.
- Next pack of Detectors Type-2 delivery (from Moscow) still delayed due to COVID restrictions.
- We are looking for possibilities of detector / screen production in a local area (in institutions around the BINP).




Beam spot observed by CCD on the detector surface. Typical transverse size $\sim 10 \text{ cm}$.




Under the X-Ray the layer surface structure is viewed also. This method reveals some points.

Beam Stopper for CR (I)

Received



Oriental 5-phase motor.
Micro Switch. Ball Spline.
Potentiometer.




Vacuum / mechanics
components ordered.

Delivery delayed due to COVID

Waiting for Reduction Gear

Expected in Q1 2021



- Concept finished. Mechanical development was done. **Minor changes last time.**
- **Features:** Sensitive to bunch charge (80 mV for 10^7 pBar @ 20 pF).
- **Model / Drawings ready.** Procurement of most components done (see pictures).
- **FDR documents pack** – 1st and 2nd internal review passed.
- **FEM:** Stress analysis on final stage.
- **Production started (see pictures).**
- **Open questions:** MBOX PDC – 2pcs – not in 2nd Amendment for the "FAIR orders components for BINP".

Beam Stopper for CR (II)


Mechanical Coupler



Stepper Motor




Future Vacuum Chamber




End Switches and Connectors



SSPF Ball Spline



Mechanical Parts



Residual Gas Monitor for CR (I)

Camera
Calibration



Prosilica GE680 CCD camera



HAMAMATSU PHOTON IS OUR BUSINESS **HAMAMATSU** PHOTON IS OUR BUSINESS



L7293 deuterium lamp (L2D2 lamp)

C9598 power supply deuterium UV lamp

▲Left: C9598, Right: M9596



MCP detector
100 x 100 mm

For Electric Field Box + Detector
8-channel High Voltage power supply is needed.

Matsusada Precision



RA/RB series power supply modules up to 40 kV DC.


- Concept finished. Mechanical development was intensive for the last year (except MCP / Phosphor screen detector surroundings).
- CDR documents pack – 1st and 2nd internal review passed.
- Model / Drawings 90% ready. Procurement of components – AFAP.
- **Restrictions:** Aperture 160 mm (chamber diameter), Bunch size 140 mm as in Specification, **Detector size (MCP + Scintillator) 100-110 mm** (biggest available on the shell). Negotiations was slow due to COVID situation.

Residual Gas Monitor for CR (II)

Revision of construction was performed.

Optimization of the EFB was made (sizes and geometry).



Obtained field homogeneity $\approx 10^{-3}$ instead of $\approx 10^{-2}$ (better spatial resolution)



Old

Side view of the EFB


New



- Negotiations was continued in September 2020. Drawings was sent do BASPIK.
- MCP size is 100x100 mm (max size provided by firm, one of the biggest in market).
- Detector consists of stack of two MCPs and phosphor screen of K-67 (analog of P-43)
- BASPIK already ordered P43 layer for tests (will be delivered to Vladikavkaz till December)
- Invoice will be sent to BINP next week (6 k€ / detector). Contract preparation will be started.
- Estimated time of the detector production is Q1 of 2021 (if we order it tomorrow).
- Mechanical design of the Detector surroundings will be continued.

CR beam instrumentation in tunnel designed GSI / ITEP

CDR of Schottky noise detector (ITEP, Russia In-Kind)



The FAIR CCC prototype (GSI In-Kind) tests will be done at CRYRING facility. Next steps depends on those results.

Dedicated talk by Dmitry Lyakin will be during
Session 2 @ 10:55, 10.11.2020

Private Communication: O. Dolinskii, October 2020. Thanks.

Summary

- Sub-packages for CR Beam Instrumentation one by one goes forward from design phase to the manufacturing phase.
- The documentation / models / drawings matching that are needed for milestones passage takes significantly more time than we expected.
- Various managing efforts **still needed (not all done yet)**.
- Nearest FoS CR BD delivery (Type-1 Scraper, Type-1 Screen) shifted and expected @ FAIR site in Q4 2021.
- FoS Type-1 BPM also shifted to the Q1 2022. Proposed octagonal electrodes must be produced and well tested @ Stand.
- FDR for Scraper and Screen waits for BINP QA check.
- **Thanks to all BINP BD team and BINP employers involved for a good job!**

Thank you for your attention!