

CR stochastic cooling system (1-2 GHz)

Dr. Christina Dimopoulou (on behalf of Work Package 2.5.10 team)

6th BINP FAIR Workshop, April 2021


(zoom: 3d wave Covid-19 ☹)



I.K. Aiwasowski
The 9th wave

Main task of the CR = efficient collection & fast stochastic cooling of hot secondary beams (antiprotons, rare isotopes) coming from production targets

3D stochastic cooling (band 1-2 GHz) of coasting secondary beams, max. 10^8 ions (antiprotons @ $v = 0.97c$, rare isotopes @ $v = 0.83c$)




CR Stochastic Cooling System 1-2 GHz



CR UHV aim for requested beam lifetimes of 100 s:
 basic static $P \leq 3 \cdot 10^{-9}$ mbar (N_2 equivalent) at room temperature, **without in situ bakeout**

$C=221.45$ m
 $B_p=13$ Tm



$$\eta = \frac{1}{\gamma^2} - \frac{1}{\gamma_{tr}^2}$$

$\eta=+0.014/-0.011$ pbars
 $\eta=0.18$ RIBs


System bandwidth 1-2 GHz

Kickers: Design

- slot-rings 1-2 GHz; 140 mm aperture
- one tank transverse cooling (H+V)
- one tank longitudinal cooling



preliminary 




Engineering: R. Greven, ZEA-1, FZJ

Challenges:

- Space limitations close to TCR1 injection line lead to constraints for splitter board size
- Minimization of signal run-time from power amps to kickers
- Heat transfer from splitter boards

R. Stassen, B. Breitkreutz, FZJ



CR 2x64 Slot-ring structure (incl. splitter boards)
inside one vacuum tank

Kickers: Integration




Tank flanges **DN 400 COF**, to flanges/bellows DN 200 CF

Top: 4-5 NEXTTorr 1000 l/s standard CR pumps; 1 free port for turbo/roughing

Side: feedthrough flanges RF power signal; UHV diagnostics; assembly flanges

Bottom: flanges for water cooling pipes



Challenging Cryogenic Plunging Pick-Ups FAIR




Ordered 2 vacuum tanks according to GSI spec/manufacturing drawings.

Expected delivery & SAT Q3/2021


Ordered supports and assembly tools for the 2 tanks

Finalizing 3D engineering & procurement of inner subsystems

16 Motor Drive Units: ready



pre-assembled in house
all parts (incl. spares) stored




Engineering:
R. Böhm/GSI



**~3500 Ag/CuBe plunging foils
and their Ag/Cu holders (incl. spares)**

CuBe foils thermally treated in vacuum oven GSI TechLAB

2021-2023: galvanic Ag-plating (1 provider, manually),
procedure for high numbers pending



UHV soldering of foils on holders (1 succesful provider)




**Flexible
Ag/CuBe
foils at 30 K**

Slotline electrode module




- re-designed, feasible by providers
- contract for full scope (pre-series, series, spares) metallised ceramic RF boards
- Prototype module: ready (without ceramic electrodes)
- pre-series ceramics Q3/2021
- full assembly & RF tests Q3-Q4/2021

Pick-up Double-Module PU17B




5



2019 C. Peschke
Engineering: M.Meister/GSI


8 single slot PCB
with one hole and 3 slots

Pick-up Module PU17B Beam Side



6

Pick-up Module PU17B Combiner Side
combiner printed circuit board (PU17BC01D, 1.91mm Al₂O₃)






layers:



Palmer Pick-Up

Palmer pick-up (Faltin rail electrodes) for precooling of RIBs



- Installed at COSY



2021-2022: its RF response will be tested with 0.83 c protons at COSY

Microwave Damping-Coated Ceramic Absorbers

Preseries mechanics (holders, assembly tooling): ready





Q4/2021-Q1/2022: testing assembly mechanics + UHV benchmarking with modules inside BINP chamber.

Engineering:
R.Böhm/GSI

Microwave Damping-Coated Ceramic Absorbers



For 140 modules: ~15000 series ceramic tubes coated by NiCr sputtering



2.5.10	CR Stochastic Cooling System
2.5.10.1.1	Cryogenic Plunging Pick-ups >> <i>ongoing (see following slides)</i>
2.5.10.1.1	Palmer Pick-up >> <i>at COSY for beam test, FDR prepared</i>
2.5.10.1.2	Kickers >> <i>FZJ designs towards CDR, pending FZJ-GSI contract</i>
2.5.10.2.1	Low Noise Preamplifiers >> <i>SAT of series done, FDR prepared</i>
2.5.10.2.2.1	Power Amplifiers 1-2 GHz >> <i>SAT ongoing (34/34 delivered, 15 passed SAT, FDR released)</i>
2.5.10.2.3	RF Signal Processing
2.5.10.3	Instrumentation
2.5.10.5	Microwave Damping CR Chambers >> <i>series tubes: ~15000 coated ceramics tubes delivered</i> >> <i>prototype mechanics done (holders, assembly tooling)</i> >> <i>Q4/2021: assembly+UHV testing of tubes inside BINP quad chamber</i>

Спасибо за внимание !

Thank you for your attention!



1961-2021

Поехали!

