

# Update on mechanics and cooling of the luminosity detector

Heinrich Leithoff


Helmholtz Institut Mainz

PANDA-Collaboration-Meeting Darmstadt  
June 15, 2021




Helmholtz Institute Mainz

# Overview of the luminosity detector




- 4 retractable layers of active sensors in secondary vacuum
- rigid vacuum box for good position information of the sensors
- active cooling necessary

## Vacuum box middle part




- houses inner beampipe and position sensors
- glueing of foil cone in the box after positioning the inner beampipe
- minor changes on the outside expected
- rework of the inner beampipe compared to the prototype

## Inner beampipe changes




- connection to vacuum box changed to CF type flange
- seamless pipe from titanium grade 2
- outer pipe diameter 68 mm, wall thickness  $\leq 750 \mu\text{m}$

# Vacuum box lid 1




- houses half detector and LSM with all feedthroughs
- allows easier installation and testing
- next steps: LSM and prototype installation

## Vacuum box lid 2




- lower lid installation procedure successfully tested
- repeatability of lid position good ( $\sim 50 \mu\text{m}$ ), see talk by Jannik

## Vacuum box lid 2



- lower lid installation procedure successfully tested
- repeatability of lid position good ( $\sim 50 \mu\text{m}$ ), see talk by Jannik



## Mechanics: Vacuum box



- mechanical rigidity within expected parameters, see talk by Jannik
- vacuum tests under preparation



## Cooling system: General setup



	sensors	LDO Voltage regulator	resistance in flexcables	Multiplexer etc.
worst case	1040 W	320 W	160 W	~100 W
likely case	380 W	120 W	20 W	~100 W

- Total estimated heat load per half detector: 310 W to 810 W
- Worst case:  $7 \text{ mW mm}^{-2}$ , likely case:  $2.5 \text{ mW mm}^{-2}$
- For cooling test: copper dummies and high power resistors

# Cooling cycle test

## Cooling cycle:

- Set bath temperature to  $-20^{\circ}\text{C}$
- When  $-20^{\circ}\text{C}$  is reached wait 10 min
- Switch on power supply and wait 15 min
- Switch off power supply and set bath temperature to  $20^{\circ}\text{C}$
- When  $20^{\circ}\text{C}$  is reached wait 10 min

>500 cycles run with 340 W (14 W/module)

>500 cycles with 465 W (19 W/module)

expected case: 10 W/module

- no changes in cooling behaviour

# Summary and outlook


- vacuum box prototype successfully tested for mechanical stability
- vacuum box handling tested
- half detector cooling working

What is next:


- extended vacuum testing of the box
- production of half detector prototype with sensors
- production of final detector

# Cooling cycle result I

First cycle:




Last cycle:




- No change in 500 cycles for 340 W
- Placement of modules difficult due to stiff copper cabling and heavy weight
- Well-placed modules show acceptable temperature under realistic conditions

## Cooling cycle result II

First cycle:




Last cycle:





- Small changes after 500 cycles for 465 W
- Three copper dummies lost contact
- Well-placed modules still ok
- Contact loss due to mechanical collision of resistors and inner beampipe aligner (not a problem with sensors)

## Contact loss during cycle test



# Simulation



- No transition or radiative effects
- Inlet temperature  $-20\text{ }^{\circ}\text{C}$ , pressure difference 1 bar
- diamond in nominal thickness
- maximum temperature:
  - worst case:  $\sim 39\text{ }^{\circ}\text{C}$
  - expected case:  $\sim 0\text{ }^{\circ}\text{C}$