

Status of



PANDA

L. Schmitt, GSI/FAIR

FAIR RRB PANDA Breakout Session
Online Meeting, February 22, 2022

General News on PANDA

System Highlights and Updates

Infrastructure Updates

Antiproton Production at FAIR




Antiproton production

- Proton Linac 68 MeV
- Accelerate p in SIS18 / 100
- Produce \bar{p} on Ni/Cu target
- Collection in CR, fast cooling
- *Full FAIR*:
 - Accumulation in RESR, slow cooling
 - Storage in HESR
 - PANDA luminosity $< 2 \times 10^{32} \text{ cm}^{-2} \text{ s}^{-1}$
- *FAIR MSV*:
 - Accumulation in HESR
 - Luminosity $10^{31} \text{ cm}^{-2} \text{ s}^{-1}$

FAIR Intermediate Objective

- North site plus S-FRS, NUSTAR, APPA hall, pBar target
- Work on all accelerators & exp

Buildings for CR, pLinac, HESR and PANDA in construction phase 2



Contracting

- STT-FT-FEE in-kind contract at work: ASICs delivered, mass testing
- FT contract at work: procurement started
- Preparations for Barrel Muon Detectors CC with Dubna
- Assignment of Czech funds for more EMC PWO crystals

Reports

- DAQT TDR approved
- Infrastructure and Installation report approved
- GEM Tracker TDR draft reviewed, testbeam with RD51 at CERN

Progress highlights

- Solenoid magnet: production of SC strands, first samples exceed specs
 - Barrel DIRC: production of PMTs started
 - PANDA@HADES Straw Trackers currently in HADES physics run
- PANDA schedule was updated w.r.t. new building schedule in Q1 2021, architectural planning resumes in 2022

Current status

- Construction of many Phase 1 systems has started
- Integration and infrastructure planning progressing
- Delays in several parts due to delayed funding or contracting
- Covid-19 still has effects on the schedule

Installation periods according to present plans:

- **Installation period 1:** solenoid, dipole, supports etc.
in parallel with installation of technical building infrastructure
- **Installation period 2:** all other systems after building completed

Commissioning strategy:

- Device commissioning synchronised with installation
- Experiment commissioning without beam: dry runs, cosmics
- First beam commissioning with protons from SIS18
→ Ready for physics when first antiprotons arrive

PANDA Progress Scorecard



PANDA		TDR / Specs	Cost [k€ 2005]	% Funding (Sec / RUS / EoI / TBA)				Construction	Construction complete	Test/ Commissioning
Day-1	Cluster Jet Target		771,00						10/2025	
	Micro Vertex Detector (MVD) - Str		2.550,00						01/2025	
	Straw Tube Tracker (STT) (1)		2.603,00						09/2025	
	Planar GEM Tracker - 50%		555,00						03/2025	
	Barrel DIRC		2.782,00						10/2024	
	Barrel Time of Flight (TOF)		310,00						10/2024	
	Forward Tracking (w/o FT 5/6) (1)		1.145,00						08/2025	
	Forward TOF (2)		362,00						12/2024	
	Barrel EMC System		8.258,00						12/2025	
	Barrel EMC Crystals - 75% (2)		8.712,00						12/2025	
	Backward Endcap EMC		1.267,00						06/2025	
	Forward Endcap EMC		5.714,00						12/2023	
	Forward Shashlyk Calorimeter (2)		1.447,00						12/2025	
	Luminosity Detector		666,00						03/2025	
	Muon Detectors (2)		2.318,00						06/2024	
	Solenoid		5.800,00						04/2024	
	Interaction Region		151,00						12/2024	
	Infrastructure		2.441,00						06/2024	
	DAQ Hardware (3)		609,00						06/2025	
		99% value weighted	48.461,00	75%	17%	6%	2%	44% value weighted		1% value weighted
Changes since RRB #10		+7%	-7.7%	+5.6%	+1.3%	-7.1%	-2.0%	+5%		

(1) if synergies between STT and Fw. Tracking realised
(2) if German-Russian Roadmap realised

(3) DAQ computing via operation funds



PANDA TDR Schedule



System	Submission <i>Expected</i>	M3 (Approval) <i>Expected M3</i>
PANDA PHASE 1		
Target Spectrometer EMC		18/08/2008
Update Report		17/06/2021
Solenoid		21/05/2009
Dipole		
Micro Vertex Detector (MVD)		26/02/2013
Straw Tube Tracker (STT)		29/01/2013
Cluster Jet Target		28/08/2013
Muon System		22/09/2014
Forward Shashlyk Calorimeter		03/03/2016
Barrel DIRC		20/08/2017
Barrel Time of Flight (TOF)		14/02/2018
Forward TOF		16/10/2018
Forward Tracking		16/10/2018
Luminosity Detector		04/04/2019
Controls		12/10/2020
DAQ		25/08/2021
Infrastructure		17/11/2021
Planar GEM Trackers	<i>3/2022</i>	<i>9/2022</i>
PANDA PHASE 2		
Endcap Disc DIRC		08/11/2011
Forward RICH	<i>6/2022</i>	<i>12/2022</i>
Pellet Target	<i>6/2023</i>	<i>12/2023</i>
Hypernuclear Setup	<i>7/2022</i>	<i>1/2023</i>

Status 17/11/2021

Phase 1: 15 TDRs approved

- EMC TDR Update Report approved June 17, 2021
- DAQT TDR approved August 25, 2021
- Infrastructure report submitted, in review


- GEM TDR draft passed internal review, work on revision along recommendations

Phase 2: 1 TDR approved


- Disc DIRC: approved Nov 2019
- Pellet Target: in preparation
- Forward RICH
- Hypernuclear Setup

For the item "Interaction Region" no TDR is planned, only a specification document. Computing TDR together with FAIR Computing TDR.

PANDA Day-1 / Phase 1 / Phase 2



PANDA System News



Solenoid Magnet



Project Status:


- Contract with BINP since March 2017
- Yoke complete, test assembly done
- Cryostat component procurement ongoing
- Local cryogenics design close to FDR

Critical Items:


- Superconductor procurement
 - Contracts signed, purchasing in process
 - **First SC strands tested within specs**
- Schedule:
 - Coordination of installation at FAIR
 - Field-mapping to be done before at BINP
 - Insertion of muon detectors

Specifications:

- 2 T field, 1% homogeneity
- Bore of 90cm radius
- 3 sub-coils for target gap
- Segmented yoke



Solenoid: Progress




Coil Winding Device

- Design completed
- Tools in production, delivery in December '21

Electrical Systems

- Dump resistor ready
- Power supply units TDK Lambda
- Racks in production
- Bus bars with ATLAS conductor

Cryostat
3D model






Cryostat and Cold Mass

- Production at Votkinsk ZA
- QC of welds by BINP controls dept. done
- Delivery Q2/22

Control Dewar: FDR Q2/22

- Drawings in preparation for FDR and TÜV







Superconductor Production

- SC strand production started, first samples better than specs
- Extrusion of pure Al at SARKO, contract for 1km test piece
- Conditioning Al gives good RRR
- Delivery till 12/22

Solenoid: Progress



Cryostat
3D model



Coil Winding Device

- Design completed
- Tools in production, delivery in December '21

Electrical Systems

- Dump resistor ready
- Power supply units TDK Lambda
- Racks in production
- Bus bars with ATLAS conductor

Cryostat and Cold Mass

- Production at Votkinsk ZA
- QC of welds by BINP controls dept. done
- Delivery Q2/22


Control Dewar: FDR Q2/22

- Drawings in preparation for FDR and TÜV



Superconductor Production

- SC strand production started, first samples better than specs
- Extrusion of pure Al at SARKO, contract for 1km test piece
- Conditioning Al gives good RRR
- Delivery till 12/22

Solenoid: Progress



- 1) Coil Shell
- 2) Shield end-face
- 3) Cryostat flange



Coil Winding Device

- 🟡 Design completed
- 🟡 Tools in production, delivery in December '21

Electrical Systems

- 🟡 Dump resistor ready
- 🟡 Power supply units TDK Lambda
- 🟡 Racks in production
- 🟡 Bus bars with ATLAS conductor

Cryostat and Cold Mass

- 🟡 Production at Votkinsk ZA
- 🟡 QC of welds by BINP controls dept. done
- 🟡 Delivery Q2/22

Control Dewar: FDR Q2/22

- 🟡 Drawings in preparation for FDR and TÜV

Superconductor Production

- 🟡 SC strand production started, first samples better than specs
- 🟡 Extrusion of pure Al at SARKO, contract for 1km test piece
- 🟡 Conditioning Al gives good RRR
- 🟡 Delivery till 12/22

HESR PANDA Chicane Dipole





Specifications:


- Normal conducting Spectrometer Dipole
- Integral component of the HESR
- Beam deflection angle 40 mrad (2.29°)
- Dynamic range 0.2 T·m ... 2.0 T·m
- Ramping speed from 25% to 100% in 60s

Project Status:


- Final report of magnet design received
- Preliminary design of Power Converter started
- Construction contract signed with BINP
- **Material procurement and production preparation:**
 - Steel order from Magnetogorsk delivered
 - Yoke production contract signed
 - Copper material ordered at Luvata
 - Tooling design for coil winding in progress



Detailed design of coil



3D CAD of Power Converter







Cluster Jet Target Developments



Experiments at COSY:

- Studies of beam-target interaction till 2024
- Performance of beam cooling in presence of the cluster jet
- Vacuum situation at IP and improvements
- Latest campaign took place May 2021:
 - 3.0 GeV/c p beam, $2 \times 10^9 - 5 \times 10^9 \text{ s}^{-1}$, target $1 \times 10^{13} - 2 \times 10^{15} \text{ atoms/cm}^2$
 - HESR stoch. cooling & barrier bucket cavity: $\Delta p/p = 10^{-4}$ after 100 s
 - MAD-X simulation of beam-target interaction
- Design study for **cryo pump** prototype
- Automatic nozzle adjustment in development: **steady luminosity**



Micro Vertex Detector



● MVD Layout

- Barrel: 2 pixel layers, 2 strip layers
- Forward: 6 disks, 2 mixed strips and pixels
- Advanced mechanical engineering
- ToPix ASIC prototype with full functionality



Pixel part currently on hold

● First priority: strip barrel


- New 64 ch ASIC ToASt for strips:
 - 60 Chips delivered in October
 - Successful chip tests
 - Preparation of SEU tests
- Mechanical design progress at FZ Jülich: stave prototypes produced in autoclave
- Further barrel strip sensors ordered in Gießen

● Further progress:

- FE board design at KIT
- MDC ASIC design at KIT



ToASt ASIC
wire bonded
to test PCB



Straw Trackers in PANDA



Central Tracker STT


- 4600 straws, \varnothing 1 cm
- Ar CO₂ at +1 bar
- 20 parallel layers, 8 skewed layers
- 0.05% X_0 / layer
- ASIC readout

Forward Tracker 1-4

- 2+2 planar stations, 5600 straws, \varnothing 1 cm
- Ar CO₂ at +1 bar
- 4 DL/station (x,u,v,x)
- ASIC readout

Outer Tracker (LHCb straws)

- Inner half length modules 2.4m
- 10800 straws, \varnothing 0.5 cm
- 0.1% X_0 / layer
- Readout from LHCb + interface



Progress of PANDA Straws




Status of electronic readout (AGH):

- All PASTTREC ASICs delivered
- Mass testing of FEBs
- Est'd FEB yield >94% (PASTTRECs>97%)

PANDA@HADES STS:

- Successful start of physics beam time: online tracking



Central STT design work:



- FEE air cooling design studies
- Preparation of frame assembly

Forward Tracker FT1-4

- In-kind contract with JU Krakow, procurement of material started
- Aging studies with varied CO2 and 4 glues
- Detailed mechanical production design in progress




Outer Tracker

- Interface board to connect LHCb FEE ready
- Preparation of system test
- Mechanics design with SLRI, Thailand



GEM Tracker

- GEM-Production
 - QA, classification & selection
 - Considering available suppliers
- Laboratory tests of framed foils
- GEM-TPC beamtime at FRS 12/19
- Readout design
 - CTR16 prototype ASIC submitted: CSA and analog Transient Recorder
 - VMM3 readout from CERN for tests
- TDR draft reviewed by PANDA, recommendations from review



GEM2D in RD51 Lab at CERN

L. Schmitt, GSI/FAIR



Barrel DIRC




Baseline design


- Fused silica (SiO_2) radiator bars and prisms
- MCP PMT for readout
- Focusing by 3-layer spherical lenses
- Fast readout to suppress BG

Project status

- Series production of DIRC bars at Nikon
- **All 112 bars** delivered to GSI
 - detailed evaluation ongoing
 - preparation of order for spares
- MCP PMT procurement:
 - evaluation of samples completed
 - order placed 22/12/2020
 - **delay due to problems with ALD device**
- **Prototype lenses received, laser tests at CUA (USA) ongoing**
- Phase 0: Participation at GlueX DIRC



GlueX DIRC



Kaleidoscopic image of a HeCd laser beam a DIRC bar on test bench



3-layer lens prototypes

PANDA PWO Crystals

- PWO is dense and fast
- Low energy threshold
- Increase light yield:
 - improved PWO II (2xCMS)
 - operation at -25°C (4xCMS)
- Challenges:
 - temperature stable to 0.1°C
 - control radiation damage
 - low noise electronics
- New producer CRYTUR




Barrel Calorimeter

- 11360 PWO Crystals
- LAAPD readout, 2x1cm²
- $\sigma(E)/E \sim 1.5\%/\sqrt{E} + \text{const.}$

Forward Endcap

- 3856 PWO crystals
- High occupancy in center
- LA APD and VPTT



Large Area APDs



5x5 mm² 10x10 mm² and 7x14 mm²

**Backward Endcap for hermeticity,
524 PWO crystals**

Barrel EMC Status



Mechanics

- All alveoles produced
- First slice fully assembled, cooling implemented
- Installation with annealing LEDs
- Mechanics FDR in preparation

Crystals

- New producer Crytur
- 4000 crystals for Day-1 needed





Readout

- APFEL ASIC, all available, flex PCBs ordered
- Hit Detection ASIC: ATR16 prototype delivered
- Protocol ASIC for control
- HV regulation board

Services

- Light pulser monitoring
- Stimulated recovery with LED






EMC Endcaps





Forward Endcap

- Assembly of VPTT modules done
- APD modules: ~160/214 done, 3/wk
- 1500 new APDs delivered
- Cosmics calibration at U Bonn
- Front lid, cooling pipes, SADC crates
- Pre-assembly planned at FZJ in '22



Backward Endcap

- Assembly of Phase 0 system (640 ch instead of 524 for PANDA)
- All alveoles produced
- Delays in assembly process
- Beamtime at MAMI in 2023
- HV distribution board done
- Al support plane delivered



Muon Detectors




Status


- TDR approved in 2015
- Baseline design ready
- Prototype (10t) test results at CERN:
 μ , p and n easily resolved
- **Prototype setup (1.5t) at Nuclotron/JINR**


Ongoing activities

- Detailed simulation, PID software
- Digital FEE: **Artix FPGA board ready**
Synergy with NICA SPD
- **FAIR Council: first funds for barrel chambers**
- Preparation of specs
- JINR PAC approves work
- Renew supplier contacts for components:
 - Al profile extrusion
 - Readout ASICs (Integral, Minsk)
 - Plastic furnishings from Yerevan
- Next step: Collaboration Contract




Range System Prototype at CERN
mounted for cosmic tests






Full DAQT Scheme
for Phase 1/2

- Prototypes for all required hardware available
- Data rate 10 GB/s at Phase 1&2 (<2 MHz rate)
- TDR approved by FAIR August 2021, work by M. Kavatsyuk, RU Groningen
- From 2022 DAQT coordination taken over by G. Korcyl, JU Krakow



Initial DAQT Scheme
for Day-1 and Tests



- Prototypes for all required hardware available
- Data rate 10 GB/s at Phase 1&2 (<2 MHz rate)
- TDR approved by FAIR August 2021, work by M. Kavatsyuk, RU Groningen
- From 2022 DAQT coordination taken over by G. Korcyl, JU Krakow


Updates on Infrastructure



Technical Report for the: \bar{P} ANDA Detector
Infrastructure and Installation

(Anti)Proton Annihilations at Darmstadt
Strong Interaction Studies with Antiprotons

May 14, 2020



Continuing work since Infra Report:

Project topics

- Safety risk assessment
- Alignment strategy
- Commissioning strategy

Support structures

- Solenoid Platforms
- Installation procedures
- Rack placement


Supply infrastructure

- Leakless rack cooling
- Technical gases


Recommendations by ECE/ECSG:

- Approval of report by FAIR
- Consider as living document to update regularly
- Technical personnel for safety and infrastructure


Solenoid Platforms



Solenoid Magnet Yoke



Solenoid Platforms



Solenoid Magnet with additional supports

Proposal for an add-on contract for BINP:

- Production of yoke and platforms unified
- Early implementation of interfaces
- Certification of stability in one hand

Supplies: Rack Cooling, LN2 Supply





Planning of under-pressure rack cooling

- Distribution circuits planning and seizing
- Pumps and reservoir below floor level
- Under-pressure systems:
 - MVD and EMC detector cooling
 - Rack cooling
- Current layout of pit to small: enlarge 2x
- Pressure drop calculations

LN2 Supply

- LN2 to cool GHe of Solenoid shield in parking position
- LN2 to produce GN2 to flush detectors
- Combine circuits to save LN2 consumption
- Better long cool GHe line than long LN2 line
- (in consultation with FAIR Cryo Dept.)



Supports: CSF and FWE Mounting




Central Space Frame (CSF)

- Interfaces with beam target pipe, MVD, STT, and Barrel DIRC
- Modular construction
- Mix of CFC frame and Al pieces
Prototype assembled end of 2021
- Load tests in preparation



Forward Endcap Mounting Device

- Common tool to insert into forward endcap of solenoid:
 - Forward Endcap EMC (with and w/o Disc DIRC)
 - GEM Tracker
- Insertion movement on precision rail
- Raising and lowering
- Adjustment of all angles



PANDA Achievements:

- Solenoid construction in full swing, **first SC strands, cryostat production**
- Barrel DIRC procurement progressing, **PMT delivery starting**
- Barrel EMC first slice assembled, **finalisation of cooling, readout PCBs**
- Cluster Jet Target: **Tests at COSY with HESR beam cooling successful**
- **TDRs approved by FAIR: DAQT, Infrastructure**
- **Forward Tracker component procurement**

Upcoming milestones:

- Solenoid:
 - Delivery of cryostat and cold mass **spring 2022**
 - Super-conductor production **to finish by 12/2022**
- **GEM Tracker TDR 2022**
- **Barrel Muon Chamber IKC**
- **Construction MoU and Common Fund**

PANDA on track for Day-1, turning risks into opportunities