

# Status and future scientific program of RAON

Byungsik Hong

*Center for Extreme Nuclear Matters ( **CENuM** ) &*

*Department of Physics*

*Korea University*


# Outline

1. Overview of the RAON construction project
2. Accelerator systems
  - Status of beam commissioning
3. RI & experimental systems
4. Summary
  - Ideas for early-time experiments with light stable-ion beams

# Part 1.

---


Overview of the RAON construction project



- Goal: To build a heavy-ion accelerator complex RAON for rare isotope science research
  - **RAON**: Rare isotope Accelerator complex for **ON**-line experiments
- Budget: Total ~U\$ 1.4 B for phase I
  - Accelerator & experimental facilities: ~U\$ 500 M
  - Civil engineering & conventional facilities: ~U\$ 900 M, including ~U\$ 270 M for purchasing land
- Project period: 2011-2022 (1<sup>st</sup> phase), 2023-2025 (R&D for 2<sup>nd</sup> phase to develop high-energy Linac)

## System installation project

Development, installation, and commissioning of the accelerator systems that provides the high-energy (200 MeV/u) and high-power (400 kW) heavy-ion beams




## Facility construction project


Construction of the research and support facility to ensure the stable operation of the heavy-ion accelerator, experimental systems, and to establish a comfortable research environment in Korea




- Providing high-quality RI beams by ISOL & IF
  - ISOL: direct fission of  $^{238}\text{U}$  by 70 MeV proton beams
  - IF: 200 MeV/u  $^{238}\text{U}$  (intensity: 8.3  $\mu\text{A}$ )
- Providing high-intensity neutron-rich beams
  - For example,  $^{132}\text{Sn}$  with energy up to 250 MeV/u and intensity up to  $10^9$  particles per second
- Providing more exotic RI beams
  - Combination of ISOL and IF

- Accelerator System
- RI production System
- Conventional Utilities
- Experimental System







SCL1 postponed



	KoBRA	ISOL	IF separator
RIB production & acceleration mode	ECR (SIB) → SCL3 → KoBRA Prod. Target (RIB)	Cyclotron (p) → TIS (RIB) → SCL3	ECR (SIB) / ISOL (RIB) → SCL3 → SCL2 → IF (RIB)
Production mechanism	Direct & multi-nucleon transfer reactions	p induced U fission	PF, U fission
RIB energy	< a few tens of MeV/u	> a few keV/u	< a few hundreds of MeV/u




RAON will eventually combine ISOL and IF to access more neutron-rich region of the nuclear chart.



# Part 2.


---

## Accelerator systems






## SCL3 (Phase I)






## SCL2 (Phase II)



- Two ECR IS's
  - 14.5 GHz ECR ion source
  - 28 GHz superconducting ECR ion source
- LEBT ( $E = 10$  keV/u)
  - 10 keV/u, Dual bending magnet
  - Chopper & Electrostatic quads, Instrumentation
- RFQ ( $E = 500$  keV/u)
  - 81.25 MHz, Transmission efficiency > 95%
  - CW RF power 94 kW (SSPA: 150 kW)
- MEBT ( $E = 500$  keV/u)
  - Four RF bunchers (SSPA: 20, 15, 2 X (4 kW))
  - Simple quadrupole magnets, Instrumentation




● Beam commissioning in Oct. 2020

Transmission at RFQ



28 GHz SC ECR IS

Ar<sup>8+</sup> 10μA @ Beam Viewer('21)



- Performance test of SCL2 and SCL3 cavities and cryomodules at cryogenic temperature
- Onsite test facility: 3 VT pits with 3 cavities per pit + 3 HT bunkers
- RAON cavities: QWR (81.25 MHz), HWR (162.5 MHz) and SSR1/SSR2 (325 MHz)



■ SCL3 cryoplant (4.2 kW @ 4.5 K)



Compressors and Oil Removal System (WCS)



Cold Box(CB)

■ SCL2 cryoplant (13.5 kW @ 4.5 K)



Compressors and Oil Removal System (WCS)



Cold Box (CB)  
(Left warm side, right – cold side)

🕒 SCL3 cryoplant and cryogenic distribution system were commissioned in August 2022.

- Cryomodules (CM) & warm sections were assembled in the clean booth in the tunnel.
- Total counts of particles for the size larger than  $0.5 \mu\text{m}$ /10 minutes were less than 30.
- Installation was completed in 2021 and beam commissioning was finished in May 2023.


↓ Cryogenic distribution to cryomodules

↓ QWR+HWR (2021)



← CM/cryogenic control rack and SSPA


## The 1<sup>st</sup> SCL3 beam commissioning (Oct. 7, 2022)




- Ar<sup>9+</sup> beams were accelerated by QWR #1~#5.




## The 2<sup>nd</sup> SCL3 beam commissioning (Dec. 16, 2022)



- Ar<sup>9+</sup> beams were accelerated by entire QWR #1~#22.



## The 3<sup>rd</sup> SCL3 beam commissioning (May 23, 2023)




- Ar<sup>9+</sup> beams accelerated by entire SCL3(QWR+HWR) on May 23.
- Ar<sup>9+</sup> beams delivered to the KoBRA target on May 31.  
→ **First RIBs were produced by Ar + C & transported to F3 of KoBRA.**
- SCL3 warm up and maintenance started from June.
- Plan to deliver Ar beams to KoBRA for experiments for a short period in early 2024.

# Part 3.


---


RI & experimental systems








# RAON Overview of RI & experimental systems





- Driver beam: p,  $35 \leq K \leq 70$  MeV up to 70 kW
- Target: SiC, BN, MgO, LaC<sub>2</sub>, UC<sub>x</sub>, CaO, BeO etc.
- Ion Source: Surface, RILIS, Plasma
- RIB:  $6 \leq A \leq 250$ ,  $10 \leq K \leq 80$  keV,  $10^8$  pps (Sn), Purity > 90% @ Exp.
- Incident to RFQ of post accelerator with 10 keV/u
- Full remote maintenance system with TIS modularization



- In Dec. 2021, ISOL beamlines were commissioned with a Cs source.
  - Horizontal beam size ~2 mm (2σ) at F2
  - Mass resolving power of pre-mass separator ~1,000 (2σ)

Target Ion Source  
( $^{133}\text{Cs}^{1+}$ , 20 keV)




Pre-Separator  
( $m/\delta m \approx 1,000$ )

RFQ Cooler  
( $> 10^8$  ions/bunch)

EBIS  
( $> 15\%$   $^{133}\text{Cs}^{27+}$ ,  $A/q < 6$ )

$A/q$  Separator  
( $m/\delta m \approx 250$ )

Post Linac  
( $^{133}\text{Cs}^{27+}$ , 10 keV/u)



- $A/q$  spectrum and resolving power (preliminary)
  - Momentum dispersion of  $A/q$  magnet: 1.244 m
  - Beam size in  $2\sigma \sim \pm 5$  mm from slit width dependence of beam current  $\rightarrow$  Resolving power  $\sim 250$  ( $2\sigma$ )
- With much more careful tuning, higher resolving power  $\sim 400$  in  $2\sigma$  can be achieved.

## ● Specifications

- Proton beams at 35~70 MeV
- Maximum beam current: 1 mA (currently at 0.75 mA)
- Two beam lines to the ISOL TIS bunker

## ● History

- Jun. 2019: Contract
- Apr. 2020: Design finalized
- Jun. 2021: Factory Acceptance Test (FAT)
- Aug. 2021: Shipping
- Nov. 2021~Apr. 2022: Installation
- Oct. 2022: Site Acceptance Test (SAT)








Cyclotron



Cyclotron beam line installation


- First RI production and transportation by the ISOL system was demonstrated using SiC.
  - Production and measurement of half-lives of Na isotopes ( $^{21,22,24,25}\text{Na}$ ) on March 3, 2023
  - Second RI production test produced  $^{26\text{m}}\text{Al}$  in addition to Na isotopes on May 23, 2023.




- Experimental conditions
  - Proton beam: 70 MeV, 1.2  $\mu\text{A}$
  - SiC target temperature
  - $\sim 1,400^\circ\text{C}$  (Ta heater ohmic heating 1.8 kW)
- ↓ Measured RIs until June 1

	Si- 22 29ms	Si- 23 42.3ms	Si- 24 140.5ms	Si- 25 220ms	Si- 26 2.2453s	Si- 27 4.15s	Si- 28 92.223	Si- 29 4.685	Si- 30 3.092	
	Al- 21 p 6.4E-22s	Al- 22 91.1ms	Al- 23 446ms	Al- 24 2.053s +130.9ms	Al- 25 7.183s	Al- 26 71.7E5y	Al- 27 100	Al- 28 2.245m	Al- 29 6.56m	
	Mg- 19 4.0ps	Mg- 20 90.8ms	Mg- 21 122ms	Mg- 22 3.8755s	Mg- 23 11.317s	Mg- 24 78.99	Mg- 25 10.00	Mg- 26 11.01	Mg- 27 9.458m	Mg- 28 20.915h
	Na- 18 1.3E-21s	Na- 19 p 150ns	Na- 20 447.9ms	Na- 21 22.49s	Na- 22 2.6027y	Na- 23 100	Na- 24 14.997h +20.18m	Na- 25 59.1s	Na- 26 1.077s	Na- 27 301ms
6 s	Ne- 17 109.2ms	Ne- 18 1.6654s	Ne- 19 17.22s	Ne- 20 90.48	Ne- 21 0.27	Ne- 22 9.25	Ne- 23 37.24s	Ne- 24 3.38m	Ne- 25 602ms	Ne- 26 197ms

- Korea Broad acceptance Recoil spectrometer & Apparatus
- Spectrometer for **nuclear structure** and **nuclear astrophysics** using stable or RI beams in the energy range of 1~40 MeV/u
  - Stable ions up to ~40 MeV/u from ECR IS ( $\leq 40$  MeV/u for  $A \leq 40$  and  $\leq 20$  MeV/u for  $A \geq 100$ )
  - RIB production at a few MeV/u using the stable ion beams from ECR IS
  - Role of the recoil mass separator for RIBs from ISOL at beam energies less than a few MeV/u





Magnetic rigidity	0.25 – 3.0 Tm
Angular acceptance	80 mrad (H) 200 mrad (V)
Momentum acceptance	8%
Momentum resolving power at F1	2100 at 2 mm beam size
Mass resolving power (with Wien filter)	750 at 2 mm beam size
Beam swinger	up to 12 degree for 3 Tm
High order correction	up to 4 <sup>th</sup> order
Degradator at F1	Homogeneous




## ● Nuclear Data Production System

- d+C for white neutrons
  - n intensity at the end of the collimator  $\approx 10^8$  neutrons/cm<sup>2</sup>/sec for 10  $\mu$ A
- p+Li for monoenergetic neutrons
  - n intensity at the end of the collimator  $\approx 10^5$  neutrons/cm<sup>2</sup>/sec for 10  $\mu$ A



Beam species	proton, deuteron
Maximum Beam energy	49 MeV/u for deuteron 83 MeV for proton
Maximum Beam current	$\sim 10 \mu$ A
Target	C for white neutron Li for monoenergetic neutron
Bunch length	$\sim 1$ ns (FWHM)
Repetition rate	1 – 200 kHz
Flight length	5 – 40 m
Neutron flux	$\sim 10^8$ cm <sup>-2</sup> sec <sup>-1</sup> at 5 m





**October 2020**





**July 2022**




## ● Large Acceptance Multi-Purpose Spectrometer

- Beam energies up to 250 MeV/u for  $^{132}\text{Sn}$  with an intensity as large as  $10^8$  pps
- Comprehensive detector system to investigate the nuclear equation of state (EoS) and symmetry energy
- All detector components and magnet were already developed, manufactured, and assembled.
- Integration and commissioning of the whole LAMPS system is being planned at the end of 2023.





Beamline (Left: IF side, Right: LAMPS side)



SC solenoid magnet  
( $B_{max} = 1\text{ T}$ )




TPC





Installation of TPC inside the magnet



Neutron detector array



**ToF & Trigger array (BTOF/FTOF)**




**BDC (left) & SC (right) in beam diagnostic vacuum chamber**



**Low-energy detectors**  
(Left) SC magnet with  
 $B_{max} = 1.5 \text{ T}$   
(Above) AT-TPC (prototype)



**Low-energy detector**  
KHALA LaBr<sub>3</sub> gamma array



**Low-energy detectors**  
(left) Si-CsI telescope  
(Above) Prototype  
FAZIA FEE board  
produced in Korea

- Injector beam commissioning
  - Measurement of the beam parameters (emittance and beam size, etc.)
  - Controlling LEBT and MEFT beam optics as needed
  - Achieved beam transmission of 95% max (routinely > 90%)
  - Machine verification including diagnostics devices
- Linac (SCL3) beam commissioning
  - **Ar<sup>9+</sup> beams were, for the first time, delivered to the KoBRA production target on May 31, 2023.**
  - As soon as the cryoplants started operation, it took just a month to cool the linac and transmit the RF.
  - SCL3 warm-up and maintenance is planned from June 2023.
- Constraints from RAON
  - **Very limited beam (Ar) delivery to KoBRA for experiments is expected in early 2024**
  - **Light RIB (e.g., Na or Al isotopes) from ISOL may be available in 2025.**
  - **The beam energy will be ~20 MeV/u until approximately 2030 when SCL2 is completed.**
  - **The first PAC is expected in the second half of 2024.**
  - ***The high-energy accelerator SCL2 will be available in 2030 or later.***

# Proposed experiments at KoBRA with stable ion beams in early phase

- Study on neutron-deficient nuclei using proton-induced fusion-evaporation
- $3n$  fusion-evaporation reactions to study MEDs in  $T_z = -3/2$  nuclei
- Fusion reaction studies related to stellar evolution
- Lifetime of isotopes near doubly magic  $N = Z$  nuclei  $^{40}\text{Ca}$
- Optical model potential studies using stable beams at KoBRA
- Decay spectroscopy and fast-timing measurements by using KHALA at RAON
- High-resolution in-beam  $\gamma$ -ray experiments: Internal conversion electron spectroscopy
- Spectroscopy of proton, neutron and alpha emitters
- RI experiments probing isospin symmetry
- Measurement of RI production cross sections
- Symmetry energy at low densities using isospin mixing in fusion reactions
- Cluster structure of nuclei