




Paris, Sep. 10-14 2012



# Status of day-one experiment commissioning at COSY

Huagen Xu


# Goals of day-one experiment at HESR





- Pbarp elastic scattering
- Coincidence (forward&recoil)
- Large range of  $t$  :  $0.0008-0.1 \text{ GeV}^2$

- Test method
- Recoil arm construction
- Commissioning at COSY


## Cluster target at ANKE



# Recoil Arm




Top view



- 2 Si : 76.8 x 50 x 1 (mm) (1.2 mm pitch)
- 2 Ge: 80.4 x 50 x 5/11 (mm) (1.2mm pitch)

# Part 1: Detectors




## Achievements:

- Both have been tested at room temp and cooling temp;

## To do:

- Final assembly



## Achievements:

- 5 mm thick one has been tested;

## To do:

- High leakage current study
- 11 mm thick one test
- Final assembly

## Part 2: FEE solution

### Mesytec:

**MPR16:** 16ch with variable gain


**MPR1:** for rear side

**MSCF16:** 16ch with LED output

**MADC32:** peak sensing ADC, input range and bit resolution selectable

### Received:

- |            |          |
|------------|----------|
|            | quantity |
| 1. MPR-16  | 12 / 12  |
| 2. MPR-1   | 5 / 5    |
| 3. MSCF-16 | 12 / 12  |
| 4. MADC-32 | 6 / 6    |




### Achievements:

- Requested new FEE complete

### To do:

- Test with final setup
- Logic modules, NIM crate, Rack



**To do:**

- To search the missing parts



# Cables

## Cabling in vacuum (between feedthrough and detector)

**Signal (262 strips):** 262 strips => 178 FEE channels (Kapton insulated)

**HV:** 4 stranded core single cable (Kapton insulated)

**TempMon:** 5 pairs twisted Kapton insulated cable

**Heater:** 1 pair twisted Kapton insulated cable

## Cabling in air (between feedthrough and preamp)

**Signal (178 channels):** 178 channels

**HV:** 4 channels (SVH-MHV)

**TempMon:** 5 pairs twisted

**Heater:** 1 pair twisted

### Achievements:

- Order of cable for vacuum side has been made

### To do:

- Making cables

## DAQ hardware:

- VME crate and 6 MAD32 + 1 CAEN V785


## DAQ software:

- IRQ mode
- Time stamping
- Online display



## Test chamber with cooling:

- Vacuum pressure:  $10^{-6} \sim 10^{-7}$  mbar order
- Temp at cooling plate:  $\sim 94\text{K}$  (best case)



## Achievements:

- Hardware are complete

## To do:

- Code work for DAQ
- Better chamber for Ge test



## Part 4: Confirmation of existing cluster target

- The expected specification of existing cluster target at ANKE location has been verified by target operating group.
- The relevant change of the cluster target will be done together with the installation of recoil arm.

**Proposal to use the ANKE cluster target  
has been accepted by ANKE collaboration!**

### **Achievements:**



- Specification of target verified by target group

### **To do:**

- Modifying the collimator and test the spec

## Part 5: Detector chamber

Existing target chamber



- Construction will be finished by the end of January of 2013

### Achievements:

- Drawings is being transferred to workshop

### To do:

- Fix the details for temperature sensor and heater on the cooling plate



## Part 6: Cooling and Temperature controller

### Cooling for test chamber

- LN2 solution

### Cooling for experiment

- Coldhead has been ordered (CRYOMECH)



### Temperature controller

- Lakeshore 336 module for temperature controller
- Heater for desired temperature setting

#### Achievements:

- Delivery of coldhead on Oct.

#### To do:

- Investigate the temperature controlling with heater
- To order heater resistor

## Part 7: HV and Accessories



Relay changes the active status of HV



### Temperature controller

- Temperature monitor, 5 channel
- Safety loop if over-temp

#### Achievements:

- Hardware are complete

#### To do:

- Implement over-temp safety loop
- Test the remote control

### HV module:

- 8ch with 4ch 500V & 4ch 2000V
- High precision, e.g. 100pA
- Safety loop protection, i.e. 5-20mA

### Crate:

- Mini Mpod (4 slots)
- Versatile accessing interfaces

# General Topics

- **Infrastructure at site (to be fixed in Oct. )**
  - Power supply
  - Space to put FEE rack
  - Space to put coldhead compressor
  - Cooling water for coldhead compressor
  - Ventilation status at site
  
- **Installation schedule**
  - Target modification
  - Day-1 chamber installation
  - Pumping time requested
  
- **Slow control system for day-1 setup**
  - Pumps (integrated into COSY slow control system)
  
- **Beam time window**
  - May. 13 – Jul. 13, 2013

**Thanks for your attention!**



# Status of recoil arm construction

- **Part 1: Detector**
  - Silicon detector has been tested and ready for use
  - Ge detectors tested by supplier and being tested (high leakage current problem)
- **Part 2: FEE (incl. cabling)**
  - Received including preamp, shaping amp, ADCs etc.
  - Outgas of cabling is being tested
- **Part 3: DAQ and Test system**
  - Optimized data taking strategy is required
  - Current chamber is not qualified for Ge test?
- **Part 4: Cluster target**
  - Availability of cluster target at ANKE has been confirmed
- **Part 5: Detector chamber**
  - Drawings is nearly finished.
- **Part 6: Cooling**
  - Coldhead has been ordered, to be delivered on Oct.
- **Part 7: Accessories**
  - HV is ready for use
  - Temperature controller 336 is available

- **Part 1: Detector**
  - Performance test for Ge; Investigation on high leakage current
- **Part 2: FEE (incl. cables)**
  - Functional check of modules
- **Part 3: DAQ & test system**
  - Code work for online display
  - IRQ working mode with time stamp
- **Part 4: Cluster target**
  - Double check for target performance
  - Schedule confirmation
- **Part 5: Detector chamber**
  - Fix the details on drawings
- **Part 6: Cooling**
  - Temperature controller with coldhead and heater;
- **Part 7: Accessories**
  - Orders for missing components
  - Implementation of safety loop for over-temperature case

# Performance evaluation with pure elastic events

## Setting for event generator(DPM):


$P_{lab}$  : 6.2 GeV/c, pure elastic events  
 $\Theta_{min}$  :  $0.113^\circ$  ( $\sim 1.98\text{mrad}$ )  
 Events : 5M  
 Parameters :  $\sigma_{el} = 18.97\text{mb}$ ,  $\sigma_{tot} = 64.50\text{mb}$ ,  
 $b = 11.89(\text{GeV}/c)^{-2}$ ,  $\rho = -0.063$

$$\frac{dN}{dt} = L \left( \frac{d\sigma_c}{dt} + \frac{d\sigma_{int}}{dt} + \frac{d\sigma_n}{dt} \right)$$

$$\frac{d\sigma_c}{dt} = \frac{4\pi\alpha^2 G^4(t)(\hbar c)^2}{\beta^2 t^2}$$




$$\frac{d\sigma_n}{dt} = \frac{\sigma_T^2 (1 + \rho^2) e^{-b|t|}}{16\pi(\hbar c)^2}$$

$$\frac{d\sigma_{int}}{dt} = \frac{\alpha\sigma_T G^2(t)(\hbar c)^2}{\beta|t|} e^{-\frac{1}{2}b|t|} (\rho \cos\delta + \sin\delta)$$



**The measurable  $t$  is limited to a small range!**

# Parameters correlation



**Fixing the parameters is needed to determine the absolute luminosity!**

# Parameters determination

## Typical parameterization


$$\frac{1}{L} \frac{dN_{el}}{dt} = \frac{d\sigma}{dt} = \frac{d\sigma_c}{dt} + \frac{d\sigma_{int}}{dt} + \frac{d\sigma_n}{dt}$$

## Optical theorem

$$\sigma_{tot}^2 = \frac{1}{L} \frac{16\pi}{1+\rho^2} \frac{dN_{el}}{dt} \Big|_{t=0} \quad \Rightarrow \quad \frac{1}{L} = \frac{\sigma_{tot}^2 (1+\rho^2)}{16\pi \frac{dN_{el}}{dt} \Big|_{t=0}}$$





## Parameterization for slope b

$$\frac{d\sigma_n}{dt} = A e^{bt} \quad \text{for } |t| < 0.8 \text{ GeV}^2, \text{ moderate energies (5-30 GeV)}$$



**Luminosity independent analysis is feasible!**

# How large t-range?




Expected t range : 0.0008 – 0.1 GeV<sup>2</sup>






# Sketch of day-one experiment

Large t-range (pbarp):  
0.0008-0.1 GeV<sup>2</sup>



# Sketch of recoil arm



**Fixed plane for commissioning**

- 2 Si : 7.68cm x 5cm x 1mm (64ch, 1.2 mm pitch)
- 2 Ge: 8.04cm x 5cm x 4 & 10mm (67ch, 1.2mm pitch)<sup>22</sup>