


A detailed 3D wireframe model of a particle accelerator complex. The model shows a large, roughly oval-shaped ring structure in the foreground, with various smaller structures, pipes, and components extending from it. The entire model is rendered in a light gray wireframe style, highlighting the complex geometry of the facility.


Test of Super-FRS detectors in Cave C

Chiara Nociforo
GSI Helmholtzzentrum für Schwerionenforschung
Darmstadt - Germany

SFRS BI (ES)



Pre-Separator



Main Separator





SFRS BI (ES)

- IPM
- SciFiber detectors for tracking
- MUSIC with its own drive
- Plastic Scintillator with its own drive
- PDC and SEM detectors at the target
-


Challenges concern the FoS which are currently under production

In-beam tests are an essential prerequisite for developing or improving technologies needed for the Super-FRS project




SFRS IPM at FTF1

The IPM is a non-destructive diagnostic device operating on primary electrons after residual gas ionization.




comini - IPM 4 SFRS 3


Double 3D Design



T. Giacomini - IPM 4 SFRS



MMS 16.06.2024




Simulations by T. Giacomini

The peculiarity of the SFRS IPM is the design able to provide the beam position and the beam profile for a **400 mm** wide chamber with MCP x/y detector widths smaller than the beam diameter.

SFRS IPM test


- 7-9 Feb 2025, Kr primary beam $E_{\text{SIS}}=0.4$ GeV/u up to 10^8 ions/s



- 2 weeks min. access to cave and 1 week to dismount
- entrance through the chicane feasible, no valves needed, fixed vacuum windows (Ti 0.1 mm) will be used
- stand-alone pumping system available
- electronics (rack, PC, ...) stays below the mechanical support, ACC network and machine timing to be used
- beam dump made of 3x20cm steel (same as for ASYEOS), better if “movable” -> **GLAD OFF**

Proposed setup (Feb 2025)

In parallel, transportation and preparation of FMF1DK1 is desirable, like in Dec 2023.




- After the IPM test, we aim for a low intensity detector test behind GLAD
 - FoS 2xSciFiber (C. Caesar et al.)
 - FoS MUSIC (B. Voss et al.)
 - FoS Plastic Scintillator (M. Czogalik et al.)



SFRS PID test

- 3-5 Jul 2025, U primary beam $E_{\text{SIS}}=0.5 - 1 \text{ GeV/u}$ up to 10^7 ions/s



- 3 weeks min. access to cave, entrance possible only from the lateral wall
- stand-alone pumping system available
- stand-alone DAQ
- beam dump made of 3x20cm steel (same as for ASYEOS) behind FMF1DK1
- calibration runs (3 SIS energies) - > **GLAD OFF**
- projectile-like fragments run (1 SIS energy) with target to produced - > **GLAD ON**


FoS Scintillating Fiber detector

- Scintillating Fiber detector (GSI detector plan B)

FoS 3D model by J. Tuunanen (JYU)

CDR: approved (June 2024)

Contact: C. Caesar (DTL)




Drives delivered to GSI last week.

SFRS installation schedule



	2023	2024	2025	2026	2027
Super-FRS (early science)					
Super-FRS - Procurement	[Green bar from 2023 to Q3/2024]				
SuperFRS - Installation		[Yellow bar from Q3/2024 to Q3/2025]			
SuperFRS - Commissioning			[Light yellow bar from Q3/2025 to Q4/2027]		
Early Science - ready for beam (M11)					Q3/2027 ◆
Early Science - ready for operations (M12)					Q4/2027 ◆



First Installation: Lateral iron shielding (Jun-Aug-24)

- According to 2025 beam time schedule (v. 5) , there are **no major collisions** between the SFRS detector tests and the scheduled R3B experiments.
- The support and contribution needed from the local R3B coll. will be kept **minimal**.
- The SFRS IPM test is our first priority in **Feb 2025**. Tests of other detectors will follow as much as possible according to their preparation and status.
- The SFRS PID test can be divided in **2 parts** (Feb and Jul 2025) compatibly with the SFRS installation schedule and the man-power available.