





The CBM DAQ system



- > CBM DAQ in a nutshell
- > mCBM - technology testbench
- > Timing and Fast Control System
- > Entry Nodes, Processing Nodes, Virgo Cluster
- > Core DAQ component: CRI1 and future CRI2



Generic DAQ scheme (LHCb)




The CBM data flow at SIS100

2028 CBM: a fixed target, high interaction rate, free-streaming heavy ion physics experiment

DAQ room: data pre-processing on FLES entry nodes

Green IT Cube: online event selection and storage




10^9 beam particles/s
1 % target (gold)
 $\Rightarrow 10^7$ interactions/s


10.000 optical connections




CBM to Green-IT-Cube connection









The CBM readout and control architecture (CRI based)
















mCBM – technology testbench




The screenshot shows a web browser window with the URL <https://facilitystatus.acc.gsi.de/acceleratorstatus/#/overview>. The page title is "AcceleratorStatus". On the left, there is a 3D model of the accelerator components, including a long blue beam pipe and several pink and green structures. On the right, there is a schematic diagram of the accelerator layout with orange and green lines. Below the 3D model, there is a table with three rows of machine parameters.

	HTD S000 Machine study	238U ⁷³⁺	1.02 GeV/u	adjust 
	CRYRING C000 Machine study	20Ne ⁷⁺		adjust 
	UCW U000 Machine study	4He ²⁺	1.4 MeV/u	beam on target 


CBM – pre-series detector components





Evolution of the readout chain at CBM in the past 5 years





FLES EN – entry node
 FLES PN – processing node
 FAIR CN – compute node




mCBM @ SIS18 - data transport with CRIs





FLES
processing
nodes



Entry Node configuration - CRI data path



2 CRI cards installed in one entry node




ASUS ESC8000
-> prototype for mCBM


basic configuration of CRI entry nodes for 2021:

- > 2x CRI - max 235 Gbps (in)
- > 1x HDR HCA - max 120 Gbps (out)

> 13x CRI boards are installed in the CRI rack



The CRI DAQ rack prototype



- > This is the CBM DAQ prototype rack (est. September 2020)
- > all data from mCBM subsystems are transiting here (scale-up 24x for SIS100)

mcbmcri - JTAG server
devel09 - 1x TFC-Master

> this rack hosts the TFC system and FLES Entry Nodes fitted with CRI1

devel08 - 1x CRI

devel07 - 2x CRI

devel06 - 3x CRI

devel05 - 2x CRI

devel04 - 2x CRI

devel03 - 1x CRI


devel02 - 1x CRI



Up to 3 CRI cards and 1 HDR HCA are installed in each Entry Node

Information and usage details are in the Redmine Wiki:

https://lxcbrmredmine01.gsi.de/projects/mcbm/wiki/CRI_operation



White Rabbit and PTP interface to GSI

At mCBM we are commissioning prototype DAQ components to be used for the day-1 readout of CBM.




- mCBM is linked to the White Rabbit network of GSI
- serves as time source to the TFC and PTP master to FLES
- allows to receive spill on/off information from the accelerator


WR interface added 09/2021

TFC System – Synchronous operation of CRI and attached FEE


- > The Timing and Fast Control system (TFC) synchronises the data processing electronics experiment-wide over optical fibres
- > Organised as a hierarchical network for scalability
- > Distributes timing information to endpoints (CRI)
- > Based on CRI cards



TFC-Master CRI




1x TFC-Master commissioned at mCBM in July 2021.
To be scaled up with TFC-Submasters for operation at CBM.




TFC with 1:47 or 1:24 hardware

The TFC system needs to synchronize 213 CRI (Online TDR Part I, Table 5.1) to one common time source (WhiteRabbit accelerator interface).

- > Using CRI1:47 with 1 input and 47 outputs
- > $213 / 47 \Rightarrow 5$ TFC-Submaster (max 235)
- > $5 / 47 \Rightarrow 1$ TFC-Master
- > TFC System consisting of $5+1 = 6$ CRI
 - > Using CRI1:24 with 1 input and 24 outputs
 - > $213 / 24 \Rightarrow 9$ TFC-Submaster (max 216)
 - > $9 / 24 \Rightarrow 1$ TFC-Master
 - > TFC System consisting of $9+1 = 10$ CRI




The link between FLES and Virgo (= GSI IT cluster) inside the GC



This is the connection of the CBM FLES to the Virgo cluster of the GSI IT. The links were upgraded to HDR in 2023.




mCBM optical links to DAQ container and GreenCube





432x multi-mode OM4 fibers, **50 m** long:

mCBM cave – DAQ container (installation April 2018 - March 2021) **144x** each



144x single-mode OS2 fibers, **300 m** long:

DAQ container – Green Cube (installation in March 2018)




Matching of fiber lengths between CBM / mCBM and the GreenCube




We will send our mCBM data forward, backward and forward to bridge a similar distance as later with CBM @ SIS100.

Data path performance – FLES input and output data rates


FLES input



FLES output




run 2448
 June 16, 2022
 Au + Au, T = 1.23 AGeV
 av. collision rate: 300 - 400kHz
 av. data rate 2.4 GB/s to disc



The DAQ rack water cooling system

NEW



Day-1 setup:

> 16 deg C inlet to rack


> 18 deg C return from rack

> Connected to the cooling backbone of the TH hall (03/2024)

> Heat exchanger and pump for secondary circuit cooling two DAQ racks

The CBM DAQ cooling


This cooling setup is a **GAMECHANGER!!!**




DAQ operation during any season

- Racks were installed in September 2020, but only air cooled with for the first 3 years
- Cooling configuration in the **CBM DAQ** identical to racks in the **Green IT Cube**
- Significantly lower temperature in the container (FPGA $<70^{\circ}\text{C}$)
- Reduction of noise level due to closed doors in the backside

Temperature difference with water cooled racks




> High power load to be tested next week with dry runs



> FPGA temperature reduced to below 70 °C




The Common Readout Interface card (CRI1) aka BNL-712 v2



- > All CBM subsystems are using the CRI1 from 2021 to transfer data into the FLES
- > Development of BNL for ATLAS (FELIX)
- > CBM owns ~ 32 CRI1 by now (2024)
- > Common production with sPHENIX (BNL)
- > Some components are EOL since spring 2021
- > CBM@FAIR will need **200 pcs** of a successor, the CRI2


The FELIX family

CRI1



> FLX-182 (2023) and FLX-155 (2024) are both an option for a CRI2!

FLX-182



1x ✓
to be
ordered

- CBM will buy a FLX-182 (Versal) prototype card (price tag 13 kUSD)
- The FLX-155 will provide 48x links (= 2x FLX-182) on same footprint
- Both are similar to our CRI2 specs, with faster PCIe and Versal FPGA

Three CRI2 hardware options




**Common Readout Interface Board
(CRI) 2.0
Hardware Specifications**

Version 1.4


DAQ Working Group
October 23, 2023


There are 3 options to choose from for a CRI2:

- > 1) – development of a readout board (36 GBT links) according to our own specification
- > 2) FLX-182 – development of BNL for ATLAS HL-LHC phase (24 GBT links), CBM will buy 1 board
- > 3) FLX-155 – development of BNL for ATLAS HL-LHC phase (48 GBT links), available from autumn 2024
- > This is a technology choice, which will define our readout system until ~2035
- > CBM needs to pick one of these options




- > CBM has setup a prototype DAQ chain over the past ~5 years
- > The full data readout and processing chain is being commissioned
- > The mCBM setup needs to be scaled up (x20) for CBM @ FAIR
- > CBM will require 200x PCIe based FPGA cards (CRI2) for day-1
- > A hardware platform for the CRI2 card will be selected till 2025






Thank you
for your attention

Thank you
for your attention




Bonus slides



mFLES Status

- > The mFLES setup is our workhorse for FLES development and mCBM
 - Sole readout and control system for mCBM
 - Demonstrator and development platform for FLES software
- > Constantly evolving and growing setup
 - First installation in Green-IT-cube in 2012
- > Setup includes all key components needed for CBM@SIS100



mFLES Entry Stage

- Located in the Target Hall mCBM DAQ container next to the mCBM cave
- White Rabbit uplink to GSI machine timing system
- Multimode fiber connection to detector systems
- Two TFC master nodes
- 6 entry nodes with a total of 12 CRIs
- 300m long-range InfiniBand connection to GC
 - 800 GBit/s bandwidth
- Nodes can work in two modes:
 - Stand-alone development (develXX)
 - FLES clusters node (enXX)



Master Clock

TFC System

Entry Node with CRIs



mFLES Build and Processing Stage


- Build/Processing stage in Green-IT cube
- Heterogeneous setup
 - 8+4 local processing nodes
 - up to 32 cores/64 threads, 256 GB RAM
 - Head node for infrastructure services and login (cbmfles01)
- Local buffer storage for data recording
 - 56 TB fast NVMe SSD buffer
 - 320,8 TB HDD buffer
- 200 GB/s InfiniBand HDR to mCBM and Virgo
 - Application level routing between separate IB fabrics
- Local online processing or timeslice forwarding to Virgo cluster

2nd gen
Processing Nodes
with local storage


Head Node

2nd gen
Processing Nodes
with local storage


1st gen
Processing Nodes



DAQ / Data Transport using CRIs



- > This is the CBM DAQ prototype rack
- > 1x Timing and Fast Control (TFC) server
- > 6x Entry Nodes (EN)




- > 1x JTAG server
- > 13x CRI-1 cards (= BNL-712)




Single mode fiber (as used between mCBM and Green-IT-Cube)

**144x
core
trunk
fibers
for
mCBM**





**six
144x
core
trunk
fibers
in C17**

300 m long OS2 cable: mCBM to Green-IT-Cube
about 1/3 of the length required at SIS 100 / FAIR



FAIR construction site – October 2021





Thank you
for your attention