



Status of day-one experiment commissioning at COSY

Huagen Xu

2012/12/9



Goals of day-one experiment at HESR

LICH





Recoil Arm





2012/12/9 Fixed plane for commissioning

- 2 Si : 76.8 x 50 x 1 (mm) (1.2 mm pitch)
- 2 Ge: 80.4 x 50 x 5/11 (mm) (1.2mm pitch)





Part 1: Detectors



Achievements:

- Get rid of pump oil accident
- To do:
- Test after rework
- Final assembly



- High leakage current problem has been fixed
 To do:
 - Test with new chamber
 - Final assembly



Part 2: FEE

Mesytec:

MPR16: 16ch with variable gainMPR1: for rear sideMSCF16: 16ch with LED outputMADC32: peak sensing ADC, inputrange and bit resolution selectable

ceived:	quantity
MPR-16	12 / 12
MPR-1	5 / 5
MSCF-16	12/12
MADC-32	6 / 6
	ceived: MPR-16 MPR-1 MSCF-16 MADC-32

Achievements:

- All new required modules received
- Test with final setup







2012/12/9

To be Received:

quantity

- 1. New NIM crates
- 2. Long cable set
- 2 14

- Crates, cables clarified and ordered
- Logic modules, NIM crates, rack **To do:**
- Final assembly







Cabling in vacuum (between feedthrough and detector)

Cables

Signal (262 strips): 262 strips => 178 FEE channels (Kapton insulatedHV:4 stranded core single cable (Kapton insulated)TempMon:5 pairs twisted Kapton insulated cableHeater:1 pair twisted Kapton insulated cable



Cabling in air (between feedthrough and preamp)

Signal (178 channels):178 channelsHV:4 channels (SVH-MHV)TempMon:5 pairs twistedHeater:1 pair twisted



- Part of the cables have been made.
- Making the left cables



Part 3 : DAQ and test system



DAQ hardware:

- VME crate and 6 MADC32 + 1 CAEN V785

DAQ software:

- IRQ mode (under work)
- Time stamping (under work)
- Online display (step progress)

Test chamber with cooling:

- Old chamber has been contaminated
- New chamber is being built with coldhead

Achievements:

Hardware are completed

To do:

- Code work for DAQ
- Better chamber for Ge test









Part 4: Cluster target

- The expected specification of existing cluster target at ANKE location has been verified by target operating group.
- The relevant change of the cluster target will be done together with the installation of recoil arm.

Proposal to use the ANKE cluster target has been accepted by ANKE collaboration!

- New collimator has been prepared
- To do:
- Changing the collimator and test its spec





Part 5: Detector chamber



• Construction will be finished by the end of January of 2013

Achievements:

Construction of the chamber is ongoing at ZAT

To do:

• Fix the details for temperature sensor and heater on the cooling plate





Part 6: Cooling and Temperature controller

Cooling for test chamber

LN2 solution & coldhead

Cooling for experiment

- Coldhead has been received and tested (CRYOMECH)
- e.g. ~50K with 20 minutes running



Temperature controller

- Lakeshore 336 module is being tested and tuned.
- Heating function is working properly with PID control

- The coldhead has been received and tested
- Heating resistor has been ordered and tested for outgas
 To do:
- Operate coldhead with detector and temperature controller





Part 7: HV and Accessories







Temperature controller

- Temperature monitor, 4 channels
- Safety loop of over-temp

Achievements:

20

- Hardware is complete
- Remote control of HV module

HV module:

- 8ch with 4ch 500V & 4ch 2000V
- High precision, e.g. 100pA
- Safety loop protection, i.e. 5-20mA Crate:
 - Mini Mpod (4 slots)
 - Versatile accessing interfaces

12





General Topics

- Infrastructure at site (to be fixed in Oct.)
 - Power supply (available)
 - Space to put FEE rack (fixed)
 - Space to put coldhead compressor (to be found in tunnel)
 - Cooling water for coldhead compressor (existing)
 - Ventilation status at site (Rack will be outside of tunnel)

Installation schedule

- Target modification (after ANKE experiemnt)
- Day-1 chamber installation (during COSY pause)
- Pumping time requested
- Slow control system for day-1 setup
 - Pumps (integrated into COSY slow control system)

Beam time window

• May. 13 – Jul. 13 (still pursuing this time window)





Thanks for your attention!





Sketch of day-one experiment







Performance evaluation with pure elastic events







Parameters correlation







Parameters determination



for $|t| < 0.8 \text{ GeV}^2$, moderate energies (5-30GeV)

Luminosity independent analysis is feasible!





How large t-range?



Expected t range : 0.0008 – 0.1 GeV²





Sketch of recoil arm

60



Fixed plane for commissioning



- 2 Si : 7.68cm x 5cm x 1mm (64ch, 1.2 mm pitch)
- 2 Ge: 8.04cm x 5cm x 4 &10mm (67ch,1.2mm pitch)₂₀