


UNILAC Control System Upgrade

Jutta Fitzek, Hanno Hüther
2024-09-19

- Introduction and Motivation
- Strategy and Timeline
- Most Relevant Changes for OPE
- Current Developments in APP
- Architecture Comparison
- Project Organization
- Milestones
- Report from the Dry Run in July
- Preparation for the Dry/Wet Run in October/November
- Outlook on the Wet Run in Summer 2025

- Injector Controls Upgrade (ICU) project
 - Provide modern, sustainable control system for GSI linacs
 - Focus on UNILAC, consolidate with overall system
 - Enable moving the main control room to FCC
- UNILAC: Facility of its own with rapid and complex operation



- Hard- and software of existing UNILAC control system from the 1990s
 - Obsolete, outdated, deprecated, not maintainable anymore
 - Stuck with operating system running beyond extended support contract, leading to compatibility issues and security risks
 - Drain of expert knowledge due to retirement
 - Moving the main control room to the FCC requires control system upgrades
 - GSI can not maintain two separate control systems
- ➔ Adapt the (not so new anymore) control system established at SIS18, ESR and CRYRING and apply to UNILAC

- Functionally, UNILAC would be able to serve ES/FS today
 - Integrate UNILAC into FAIR control system
 - Use existing legacy control system as template
 - Replace analog cables and appliances with digital signals and software
- Several improvements result from introducing new technology
 - Maintainability, transparency, traceability, extensibility, flexibility, usability, ...
- Make the transition as painless as possible for operators
- ➔ New concepts and features only where necessary for now (e.g. timing system, LSA) or high benefit at low effort

- ✓ Step 0 (done):
Secure UNILAC beam operation for beamtime 2025
 - Replace existing operating cluster with virtual machines
 - Implement IT security measures


- Step 1 (in progress, until beamtime 2025):
Develop „emergency“ control system
 - Intermediate step towards full system, useful for testing and feedback
 - First viable version with reduced and simplified feature set
 - Emergency backup for beam time 2025 in case of a (very unlikely) major failure or security breach in the legacy control system

- Step 2 (until beam time 2026):
Develop production control system
 - Based on emergency control system
 - Replace simplifications by full-fledged solutions, implement full feature set
 - Enhance usability and efficiency

- Step 3 (beam time 2026 and onward):
Bug fixing, tuning and enhancements
 - Further development, implement feedback from operators
 - Streamlining and consolidation with the other machines
 - Include other linear accelerators


Strategy and Timeline [3/3]

- Develop emergency control system as intermediate step until beam time 2025, regular operation with legacy system
- Regular operation with new control system from BT 2026
- Interleave tests with beamtimes and shutdowns




Most Relevant Changes for OPE

- UNI-PZ will be replaced by UNILAC Data Master
 - Pre-planned schedules instead of ad-hoc decisions
- Settings calculation and storage will be performed by LSA
 - Dedicated settings management system with settings database instead of calculation directly in apps and settings storage in front end computers
- Fortran-based programs will be replaced by Java applications
 - Many general purpose applications already known from SIS/ESR/CRYRING operation, but also dedicated apps for UNILAC





- Mapping of functionality as basis for development




- Implementation – Adaptation of existing Applications
 - All Apps: UNILAC support development ongoing
 - MASP GUI, UNILAC support **completed**
 - Snoop GUI, UNILAC support (BEA) **completed**
 - Profile Grid App, UNILAC support started

■ Implementation – New Applications

- UNILAC Emergency App **used for Emergency System**
- IonSource **first test version in place**
- Spectrum App **development ongoing**
- PotiBoard App **development “phase 1” ongoing with external work**
- UNILAC What’s Running **conceptual work done, API design started**
- Faraday-Cup-Panel App **2024/25**
- BTM GUI **2025, external work**
- HF App **2025**




Architecture Comparison



Note: This is a (very) simplified view on the control system's architecture. Several integral components have been omitted for the sake of comprehensibility. If you would like to gain a more comprehensive understanding or have any questions or comments, please feel free to call Hanno at -3089 or write to h.huether@gsi.de.

Project Organization



✓ Dry Run 2023

- first test of new control system components at UNILAC (settings generation and data supply)

✓ Beamtime 2024

- operation of user beam time with legacy control system on extended support

✓ Dry Run 2024

- verify main capabilities of emergency control system

■ Wet Run 2024

- test emergency control system with beam

- **Beamtime 2025**
 - Operation of user beam time with legacy control system beyond extended support
 - Only if necessary: operation with emergency control system

- **Wet Run 2025**
 - Test new production control system with beam
 - First test of beam injection into SIS18 with new control system


- **Beamtime 2026**
 - first regular operation with new control system

Milestones [3/3]


✓ achieved

⇒ in progress

🕒 delayed



Dry Run 24_2: 2024-07-01 to 2024-07-24



excerpt from [ICU Project Test and Release Plan](#)

- Dry run was very successful: Almost all goals achieved, requirements for the milestone even exceeded in some areas
- Thanks to everybody that contributed!

- WR-2-MIL-Gateways provided, connected and successfully tested
- Dedicated Data Master for UNILAC provided, installed and successfully tested
- 50 Hz synchronization of Data Master integrated into timing schedules and successfully tested
- Chains for realistic multiple-beam scenario successfully scheduled using Emergency App prototype

Please refer to the [dry run wiki page](#) for the full list

- Settings for various magnet and RF devices (including LEBT magnets, MAZ) successfully supplied
- Chain timing (i.e. timing for Virtual Accelerators) successfully tested with actual devices
- Pulses on various RF devices verified using BEA's UniMon application
- All relevant UNILAC devices integrated into MASP for monitoring


Please refer to the [dry run wiki page](#) for the full list

- Shortened pulses, no beam and profile grid protection timing schedules successfully tested
- Stabilization and conditioning chains successfully scheduled and tested
- Non-interruptive trims and non-interruptive changes to timing schedules successfully tested
- PotiBoard prototype hardware and software tested and trim response times verified to be adequate

Please refer to the [dry run wiki page](#) for the full list

- Phase advance magnets (scheduled for 24_3)
- Solenoids (scheduled for 24_3)
- Transfer channel preparation / MAGN_DOWN (after 24_3)
- Remaining Device Access LSA compatibility issues (after 24_3, workarounds in place)


Dry/Wet Run 24_3: 2024-10-21 to 2024-11-08



excerpt from [ICU Project Test and Release Plan](#)

- Preparation status: Still in rough planning, timeframe for commissioning currently in negotiation
- Proposal for detailed planning to be prepared by Peter & Hanno

DR/WR 24_3: Major Phases




excerpt from [ICU Project Test and Release Plan](#)

- Ensure dry operation of all required devices
- Verify chopper control and machine protection
- Produce beam and use beam diagnostics to analyze

Currently planned as next steps for dry run preparation:

- Detailed planning in preparation, to be discussed in ICU JF on 2024-10-02)
- Coordination with equipment specialists regarding requirements for beam production and commissioning
- Follow-up progress on Chopper Control Interface implementation
- Suggestions and issue reports welcome!


Outlook: Wet Run in Summer 2025




- Preparation status: Time frame and machine availability confirmed by OPE & considered by CAM

PotiBoard?


→ Martin's presentation



**Questions?
Suggestions?
Comments?**



ICU Architecture Overview




Project Overview 2024



General Plan of Accelerator Operations 2024

General Plan of Acc.Ops
status 20.12.2023

status ACO-planning: V9.0 - 22.04.2024




Project Overview 2025



General Plan of Accelerator Operations 2025

status 12.04.2024
General Plan of Acc Ops

status ACO-planning: 22.04.2024



Herausforderungen im ICU-Projekt

