



MYRRHA phase 1  
MINERVA

# The MYRRHA-Accelerator Driven System and its accelerator

Ulrich Dorda

03.04.2025, GSI

# SCK CEN

- The Belgian Nuclear Research Center
- Founded in 1952
- $\approx 950$  employees,  $\approx 250$  MEuro annual budget
- Reactors for
  - 1/3 of worldwide radio-pharmaceuticals
  - High power semiconductor doping
  - Calibration
  - One just completed dismantling (BR1)
  - One "tiny" one already coupled to a 30keV accelerator (zero-power ADS)
  - ...
- $\approx 4$ h drive from GSI




# Background on nuclear reactors

- IPCC, IAEA, IEA: Nuclear energy crucial part for CO<sub>2</sub> neutrality by 2050
- End 2023:
  - 417 reactors in operation in 31 countries
  - 58 reactors in construction
  - Electricity contribution: worldwide  $\approx 10\%$ , USA:  $\approx 19\%$ , EU:  $\approx 25\%$ , BE:  $\approx 48\%$
- Nov'23 at COP28: 22 countries commit to nuclear energy in their energy mix
  - x3 installed nuclear power by 2050
  - Confirmed by 36 countries at the Nuclear Energy Summit 2024 (March 2024)

# The issues of nuclear reactors

- Nuclear waste with very long half-life
- Critical operation (chain reaction)
- Weapon capable material
- Limited natural resource of fuel

# Fission generates high level radioactive waste




**1 ton fuel = electricity for  
100,000 Belgian families for  
4.5 years**




**Spent fuel contains:**

- **94,7% of resources we can recycle (U+Pu)**
- **5,1% of nuclear waste with low radiotoxicity (FP's)**
- **0,2% of high radiotoxicity nuclear waste**

# Transmutation




# Three options for Minor Actinide (MA) transmutation



Transmutation rates:  
**Fast Reactor: 2 to 4 kg/TWh**  
**ADS<sup>1</sup>: 35 kg/TWh**

(Core safety limits amount of MA in a critical core for transmutation)

# Resource usage





# Inherent safety


- Subcritical reactor – the ACC stops, the reactor “stops”

# MYRRHA Reactor

Parameter	Unit	Value
Maximum core power in critical configuration	MW <sub>th</sub>	63
Maximum core power in sub-critical configuration	MW <sub>th</sub>	55
LBE flow rate	m/s	2
Core height	M	1
LBE core inlet temperature	C	220
Spallation target temperature	C	450
LBE core out temperature	C	380
Final proton beam drift length	m	12

Other:

- Beam line must be removable
- Beam line must not create radiation above reactor



# ACC requirements

- Protons
- > 500 MeV
- MW class average beam power
  - mA CW beam current
  - duty factor adaptation
- Reactor cycle operational schedule
  - MYRRHA: 90 day cycle
  - industrial ADS: quasi continuous
- High reliability
  - no beam interruption > few s
  - to avoid thermal stress on reactor components
- High availability
  - To get uptime
- Cost/Energy efficiency (CAPEX/OPEX)
  - Industrial approach


# Options & worldwide efforts

- SC-Linac:
  - **MYRRHA – 1<sup>st</sup> stage (100 MeV) in implementation**
  - **CiADS – in implementation**
  - JADS – design study
  - ...
- Cyclotron
  - Transmutex company – design study
  - TEXAS A&M university – design study for stacked cyclotrons
  - ....



Purpose:

- ADS technology demonstrator at pre-industrial scale
- Flexible irradiation facility (Radio isotope production, reactor fuel research, ...)





# 2018: Belgian government decision on MYRRHA

- Belgium decides **to build MYRRHA**, a new large research infrastructure in Mol
- Belgium decides **to establish a non-profit organization MYRRHA IVZW/AISBL**
  - in charge of the MYRRHA facility international outreach and serving as the legal structure for welcoming international partners
- Belgium decides **to establish governmental support** for promoting MYRRHA international partnerships
- Belgium decides to **allocates a budget of € 558 m** towards the **project's phased approach**

# MINERVA = MYRRHA phase 1 implementation

- ✓ **100 MeV**
  - ✓ **1 injector**
  - ✓ **1 SC cavity type**
- ✓ **Test the reliability concepts (RF-fault tolerance)**
- ✓ Two target stations:
  - **ISOL system (PTF):** *reduced duty factor (50kW)*
  - **Full power Facility (FPF):** *Fusion material research, 400 kW*
- ✓ Spreading the investment costs
  - ✓ Phase 1 funded
  - ✓ Funds for R&D for phase 2 & 3 available
  - ✓ Implementation of phase 2 & 3 subject to international funding



42 m


≈ 160 m

# Starting up

- Accelerator team
  - 1<sup>st</sup> hires on site beginning 2020
  - By now  $\approx 35$  persons -> heavily relying on collaborations and industry
  - Multinational with various backgrounds
  - During Corona, at remote location, unknown to ACC-community
- Critically reviewed the pre-existing designs
  - Significant rework needed on layout, beam optics, operational concept, component designs, ...
- Nuclear license was approved by FANC in Nov. 2022



# 17 MeV Injector





176 MHz normal conducting RF  
4-rod RFQ with up to 160 kW to 1.5 MeV  
2 Quarter-wave resonators  
15 accelerating + 2 rebunching CH-cavities  
RFQ & Cavity design by IAP/Bevatech  
CH-cavity production started at RI

30 keV ECR-DC-proton source  
(Pantechnik)  
LEBT: 2 solenoids, chopper & BD


- Need for gas injection for space charge compensation still under investigation. (takes time to build up)
- Electrostatic Chopper defines the macro beam structure: 2 beam destinations within 4ms
- 2 Solenoids
- Allisson scanner

TraceWin - CEA/DRF/Irfu/DACM





# Injector test stand

- Experimentally validated up to exit RFQ in R&D manner
- Test stand now dismantled and being completely refurbished/rebuilt




Emittance	Horizontal ( $\pi \cdot \text{mm} \cdot \text{mrad}$ )	Vertical ( $\pi \cdot \text{mm} \cdot \text{mrad}$ )
Simulation	0.114	0.113
Scan	0.080(7)	0.093(5)




# CH-section

TraceWin - CEA/DRF/Jrfu/DACH



6 $\sigma$  sizes




RFQ exit

MEBT1: Matching section with 2  
quarter wave rebunching cavities


MEBT2: Rebunching with CH-cavity



# Crossbar H-mode cavities (CH)




- Up to 40kW RF
- T stabilized to  $\approx 1^\circ\text{C}$
- Design by IAP Frankfurt
- Production at RI ramping up



# Crossbar H-mode cavities (CH)


- Critical by design and to be verified experimentally
- 1) Water cooling efficiency, specifically for stems
  - 2) Fundamental mode tuning and avoiding tuner modes

CH-01 measurement




Accompanying CST Simulations

	WP (mm)	f0 (MHz) in air	f0 (MHz) in vacuum	tuner mode measured (MHz)
dynamic tuner	101.25	176.150 (meas.)	176.200 (+ 50 kHz)	159.586 (meas.) 161.4 (sim.)
static tuner	191.75	176.109 (-50 kHz)	176.159 (sim.)	228.128 233.5 (sim.)








# Injector switching and matching sections



- Includes collimation
- Hot standby injector with full diagnostics e.g. fast faraday cup
- Tuning beam dumps
- MINERVA only with 1 injector (various layout options for upgrading to 2 injectors)


# Injector switching and matching sections







# SC-linac

- 30 cryo modules with each 2 single spoke cavities (352.2 MHz,  $\beta = 0.352$ )
  - Initially 24 cryomodules
- Warm section with doublet & diagnostic
- BPM & correctors integrated into quadrupoles







# Fault tolerance

- RF overhead to compensate for failed cavities




# Single Spoke RF cavities

- Two 352.2 MHz single spoke cavities @2K per CM
- Pre-series cavity production completed at RI  research instruments





# SRF Spoke Cavities

- Pre-series tested at IJCLab,
  - 4 from 6 cavities were re-tested @ FREIA with similar results
  - Typical limitation: Field emission
- Series testing being done at FREIA (Uppsala)






# Magnetic shield




 > 20 mG  
 < 5 mG




Manufacturing ongoing at Meca Magnetic

# RF Coupler

- Water-cooled inner antenna
- SHe-cooled outer coax line
- TiN-coated RF window
- Tender in publishing
- RF-Conditioning at IJCLab




# Cavity tuning system



IJCLab design


+

Cold Power Drive




or

Warm Power Drive




SCK CEN design


- **Fast & frequent detuning needed**
- Core part designed by IJCLab
- Baseline: warm motor solution but cold motor option as backup
- Conceptual design of the power train and the warm motor assembly are finished.
- Heat loads of power train:  $<0.5 \text{ W@2K}$
- Upcoming test-stand for warm motor solution at IJCLab



# Thermal shield & tie-rods




- Made from Aluminum
- Access ports to reach the tie-rods and fiducials








# Cryo vessel



- Standard CF connections are used for the access ports.
- Conceptual buffer tank redesign done




# Overview



# Cooling circuits and heat loads

Simplified cooling circuits of one QCELL as seen by the cryogenic distribution



Required cooling capacity (static | dynamic | total), excluding contingency margins.



Equipment	2 K Circuit [W]	TS Circuit [W]	Coupler Circuit [g/s]
Single QCELL	13.9   9.1 <sup>a</sup>   23.0	184   -   184	0.040   0.012   0.052
- QM only	9.3   9.1 <sup>a</sup>   18.4	122   -   122	0.040   0.012   0.052
SRF linac			
- No margin → - Min turndown <sup>b</sup>	334   -   334	4423   -   4423	0.96   -   0.96
- Full margin +50% → - Nominal operation	418   187   605	5529   -   5529	1.20   0.36   1.56
- Limited margin +20% → - Max. operation	418   242   660	5529   -   5529	1.20   0.16   1.49

<sup>a</sup> 4.25 W of RF losses per cavity at 7 MV/m.


<sup>b</sup> hypothetical staged installation of 24 QCELLs.

# CRYO Backbone

Reference design by ACS  
Design and  
implementation in final  
tender preparation




ACS France



# Cryoplant

- ~ **3.5 kW @4.5 K**, of which
- ~ **900 W @2 K** (70% of total heat loads)
- ~ 700 kg of Helium inventory

## Cryoplant Architecture






# Other Components



- Solid state amplifiers
  - Being produced by Cyroelectra
  - Drain voltage adaptation for efficiency gain
- MPS:
  - 1W/m
  - Differential beam current measurement & beam loss monitors
- Magnet design & follow up by ACT
- LLRF
  - RF based PRDS (being tendered)
  - Great collaboration with DESY!
    - E.g. aiming for direct sampling with DESY-uTCA card developed for Petra IV
  - CW quench detection/protection ...
  - 0.1° phase, 0.1% amplitude

# Low-Level RF project: history, strategy, outlook






# 100 MeV "HEBT"






Pulse pattern  
(RF = CW)





# Control system

- **Agile** based lifecycle including **DevOps** and **Test Driven Development (TDD)**
- based on **EPICS**, **μTCA4**, **White Rabbit** and standard industrial solutions
- **In-house team of 6 persons** to coordinate and gather input
- Solution delivery mainly by **Framatome Hungary** and **EvoPro Innovation**




# PTF: ISOL

- TRIUMF ARIEL concept at the basis of the facility design 
- 4mA,  $\leq 250\text{Hz}$ ,  $\leq 0.5\text{ms}$  on non-actinide or  $\leq 0.2\text{ms}$  on actinide targets
- RIB mass resolving power: initial  $\approx 1500$ , upgradable to 10 000



Test stand available



Target heated up to 2000K




# Full Power Facility (FPF)


- Inspired by IPF@LANSCE
- Beam dump for reliability studies
- Fusion material research:
  - Direct proton irradiation
  - Via spallation neutrons



Beam window test stand



# Building & infrastructure



- Footprint:
  - Accelerator related: 8 000 m<sup>2</sup>
  - User building: 3 600 m<sup>2</sup>
- Electrical: 9.8 MVA

- **Approach:**
  - One Design Engineer from conceptual design till commissioning
  - Buildings, systems and specialized systems contractor



# Construction progress

- Official groundbreaking Q2'24
- Construction start Q4'24






# Facility layout





# Summary

- MYRRHA Phase 1 is funded & international not-for-profit organization established since 2022 as legal entity enabling interested parties (countries, organizations, companies) to join MYRRHA
- Design consolidation of accelerator optics & components finalized
- First series components in production
- Ground breaking in 2024
- Heavily relying on collaborations & industry



# Copyright © SCK CEN

All property rights and copyright are reserved.

This presentation contains data, information and formats for dedicated use only and may not be communicated, copied, reproduced, distributed or cited without the explicit written permission of SCK CEN.

If this explicit written permission has been obtained, please reference the author, followed by 'by courtesy of SCK CEN'.

Any infringement to this rule is illegal and entitles to claim damages from the infringer, without prejudice to any other right in case of granting a patent or registration in the field of intellectual property.

## **SCK CEN**

Belgian Nuclear Research Centre  
Studiecentrum voor Kernenergie  
Centre d'Etude de l'Energie Nucléaire

Foundation of Public Utility  
Stichting van Openbaar Nut  
Fondation d'Utilité Publique

## **Registered Office:**

Avenue Herrmann-Debrouxlaan 40 - 1160 BRUSSELS - Belgium

## **Research Centres:**

Boeretang 200 - 2400 MOL - Belgium  
Chemin du Cyclotron 6 - 1348 Ottignies-Louvain-la-Neuve - Belgium