

A 3D wireframe model of a particle accelerator ring, showing the complex structure of the ring and the various components involved in the acceleration process. The ring is depicted in a perspective view, highlighting its large scale and intricate design.

FAIR Secondary Beams

H. Simon


International Conference on Science and Technology for FAIR in
Europe 2014, Oct 13th-17th in Worms

From GSI to FAIR: novel opportunities



Primary Beams

- $2-3 \times 10^{11}/s$; $1.5-2 \text{ GeV/u}$; $^{238}\text{U}^{28+}$
- **Factor 100-1000**
over present in intensity
- $2(4) \times 10^{13}/s$ **30 GeV protons**
- $10^{10}/s$ $^{238}\text{U}^{73+}$ up to 35 (- 45) GeV/u



Secondary Beams

- Broad range of **radioactive beams** up to $1.5 - 2 \text{ GeV/u}$; up to factor **10 000** in intensity over present
- **Antiprotons 3 - 30 GeV**

Storage/Cooler Rings

- Radioactive beams
- e – A collider
- 10^{11} antiprotons
Stored and cooled
at $0.8 - 14.5 \text{ GeV}$


High intensities are of key importance!

e.g. Current frontier: ^{26}O




^{24}F 0.34 s	^{25}F 50 ms	^{26}F 10.2 ms	^{27}F 4.9 ms	^{28}F unbound	^{29}F 2.6 ms
^{23}O 82 ms	^{24}O 61 ms	^{25}O unbound	^{26}O unbound		

Low energy response





- 1) Beam intensity
 $3 \cdot 10^{10} \text{ } ^{40}\text{Ar/spill}$
 $\rightarrow \sim 0.1 \text{ } ^{27}\text{F/s}$
- 2) Multi neutron detection and acceptance.



MSU

$E_r = 150^{+50}_{-150} \text{ keV}$
 $\Gamma = 5 \text{ keV}$

E. Lunderberg et al.
PRL108(2012)
142503



Thesis: C.Cäsar 2012

TUDa/GSI

Layout of the Super-FRS (Full Version)

Design Parameters:

$\epsilon_x = \epsilon_y = 40 \pi \text{ mm mrad}$
 $\varphi_x = \pm 40 \text{ mrad}$
 $\varphi_y = \pm 20 \text{ mrad}$
 $\Delta P/P = \pm 2.5 \%$

$B_p = 2 - 20 \text{ Tm}$
 $R_{sc} = 750 / 1500$
 (first / second stage)

Spot size on target
 $\sigma_x = 1.0 \text{ mm}$
 $\sigma_y = 2.0 \text{ mm}$

Projectile:


- Elements p - U
- Energy up to 1.5 GeV/u
- Intensity up to $10^{12} / \text{s}$ (depending on element)
- DC or pulsed operation

In-Flight Separation:


- Universal (all elements)
- Fast (submicroseconds)
- Efficient (kinematic focusing)
- Mono-isotopic or cocktail beams

Features:


- Two Separator-stages
- Multi-branch system
- Large acceptance utilizing sc magnets
- Handling concept for high-radiation area



Superconducting FRagment Separator




Stepping stone towards the facility




The pbar separator

pbar separator
240 π mm mrad
 $p = 3.82$ GeV/c
 $\Delta p/p = \pm 3\%$



target & collector

29 GeV p from SIS 100




See Talk by Klaus Knie on Friday

SC Multiplets



Remote Handling




Target




Local Cryogenics





Driver Accelerator



Radiation Resistant Magnets





SC Dipoles



Super-FRS Target Area


Major Installation

- Target chamber & plug inserts
 - German in-kind in collaboration with KVI-CART
- Target wheel & plug inserts
 - German in-kind in collaboration with KVI-CART
- Beam catcher
 - Indian in-kind
 - chamber and plug inserts for slow and fast extracted beams



Major Infrastructure

- Hot Cell Complex
 - German in-kind
 - So far planning by nuclear engineering company
- Shielding flask
 - Finnish in-kind
- Iron shielding (approximately 6.000 ton)



x/y Slit-systems

- Overall 18 slit pairs required
- Remote handling foreseen
- ✓ Specification established
- ✓ Collaboration contract with KVI-CART
- ✓ Kick-off done 01/2014
- ✓ PDR done 08/2014,
 - Pre-design existing
 - thermal simulation / cooling issues considered
- Pre-Series slit-system expected Q3/2015

x-slit system:




block size: 200mm x 200 mm

y-slit system:

Block size: 400mm x 90 mm



Material: Densimet

Media panel,
robot operated



Radiation Resistant Magnets (at the Target Area of Super-FRS)

- Normal conducting magnets using MIC cable
- 3 dipole units, 3 quadrupoles, 2 sextupoles
- Prototype dipole built (95 ton) and tested by BINP
- Handling tests at GSI in 08/2014
- Remote alignment under revision
- Remote connectors under revision
- Specification in preparation,
- Tendering via FAIR Q1-Q2/2015



Handling Test Dipole

(Mobile crane in dedicated hall “Testinghalle”)



Handling Test Dipole (... yoke juggling ...)



{2}

Handling Test Dipole

(Reassemble the magnet)



Intervisibility was required

Mechanical guides are not sufficient dimensioned



→ Small revisions necessary after full size test .


SC Dipole Magnets



Status:

- ✓ Collaboration agreement with CEA/Saclay on:
 - Detailed design & Technical follow-up
 - Participation at CERN testing
- ✓ Technical Kick-off 1/2014
- ✓ IMP Visit 4/2014 (CEA & GSI)
- ✓ PDR done 7/2014 (including external advisor)
- FDR planned for 11/2014 (without **special dipoles**)
- Tender by FAIR starting 12/2014
- First of Series ready for testing: Q3/2016
- Series production & testing: Q4/2016 – Q1/2019

- 3 dipole units 11°
- 21 dipole units 9.75°
 - 3 times modified cryostat
- Iron dominated/warm iron
- SC coil
- Aperture $\pm 190\text{mm} \times \pm 70\text{mm}$
- Weight: 50 to 60 ton
- Prototype built and tested (FAIR China Group)



Collaboration with CEA/Saclay



Overall Status



- Focus on short dipole


Project includes:

- Magnetic design
- Cryogenic Design
- Quench Analysis
- Mechanical Design (including cool down, magnetic forces)
- Protection & Quench Detection
- Instrumentation
- Interfaces with GSI/FAIR (cryogenics, PC, DMU, ...)



- Procurement Strategy under discussion (FAIR/GSI/CEA)
 - 3 lots (yoke, cold mass, integration)
 - branching units as option
 - ✓ pre-ordering of wire (running)
 - ✓ 'pre-bidder conference' (running, 8 companies applied)
- Time Schedule updated


SC Multiplets



- **Tender Status:**
- ✓ Tender opened Q3/2013
- ✓ Bidder submitted quotes Q4/2013
- ✓ 1st round negotiation finished Q1/2014
- ✓ 2nd round negotiation finished Q2/2014
- 3rd round negotiation still running
- signing of contract expected for Q4/ 2014
- FAT of first short multiplet Q2/2016
- FAT of first long multiplet Q3-Q4/2016
- Series production: Q4/2016 – Q1/2020

- 25 long multiplets (MS)
- 8 short multiplets (PS)
- Quadrupol triplet / QS configuration
- up to 3 sextupoles and 1 steerer
- Octupole coils in short quadrupoles

- iron dominated, cold iron (≈ 40 tons)
- common helium bath
- warm beam pipe (38 cm inner diameter)
- per magnet 1 pair of current leads
- max. current < 300 A for all magnets



Multiplet tendering: Comparison of Timelines




	FAT short multiplet (month after project start)	FAT long multiplet (month after project start)	Release of SP (month after project start)	FAT 1st series (month after project start)	FAT last series (month after project start)
Project Plan	19	23	27	31	62
Bidder 1	20	22	26	33	68,5
Bidder 2	22	25	27	36	73
Bidder 3	24	27	28	34	56

- Overall time for production of 33 multiplets \approx 5.5 years
- Start in Q4/2014,
 - 1st multiplet at CERN: Q2 /2016
 - WP runs at least until **Q1/2020**
- Series Production Rate approximately \approx 1 unit/month;
 - Bidder 3 produces too fast (<2 years, requires 4 test benches at CERN)

Magnet Testing & Mapping @ CERN

- ✓ GSI-CERN Agreement K1727/DG & Addendum #2 (signed)
- Scope (separator magnets):
 - ✓ 24 Dipoles (PS & MS),
 - ✓ 31 Multipletts (+ 2 spare)
- Place: CERN building 180
- 3 universal test benches, basically:
 - 1 setting-up & cool-down
 - 1 measuring
 - 1 warm-up & disassemble



- Ready for testing: Q1/2016
- Time estimate (single multiplet): 44 days
 - Installation, connection, cool-down: 15 days
 - Cold test (powering, magnetic field): 15 days
 - Warm-up, disassembly: 14 days
- overall series measurement time: \approx 3-3.5 years


Magnet Testing Area @ CERN

Existing equipment


- magnet-measurement station, crane
- Cryo: GHe Buffer, distribution box pre-cooler (10kW) + compressor

New required equipment (mainly cryo-parts):

- 2nd pre-cooler (10kW) + compressor
- 3 satellite valve-boxes & cryogenic lines
- LN2 & LHe tank







Layout, 3 benches & two pre-coolers



Super-FRS Local Cryogenics


- Flow scheme / Cooldown processes
 - Total cold mass (PS + MS): ≈ 1.100 ton
 - Cryogenic operation modes
- Revision of feedboxes
- Updates of cryogenic interfaces
- Emergency cases
 - Normal quench \rightarrow 70% of energy deposited in quench protection system
 - Worst case \rightarrow full energy in He
 - \rightarrow safety valves/burst disc dimensions



Magnets for Energy Buncher

- Magnets are Indian in-kind,
- Revised parameters defined
- VECC colleague at GSI to finalize magnetic design
- 3 dipole units with 30° deflection angle
 - superferric, warm iron, SC coils
 - challenging: required field quality
 - new design: weight ≈ 70 ton (old design 115 ton)
- Multiplet: individual magnets as in the separator
- Magnet testing technically possible at CERN

Maximum field	1.6 T
Minimum field	0.15 T
Bending angle	30°
Radius of curvature	4.375 m
Effective length	2.29 m
Good field aperture - elliptical	± 25 cm (horizontal) ± 7 cm (vertical)
Vertical pole gap	± 8.5 cm
Integrated Field quality $\Delta B/B$	$\pm 1.5 \times 10^{-4}$
Pole face rotation	0°
No. of magnets	3



Configuration:

M1: St, Q800, Q800, Q800, Sext

M2, M3, M4: St, Q800, Q800, Sext

M5: Q800, Q800, Q800

Option 1: M1 and M2

Option 2: Option 1 and M3 and M4

Option 3: Option 2 and M5



DIPOLE MAGNET FOR ENERGY BUNCHER - 2014

Low Energy Branch – involvement of physics community

LEB building not in MSV!

*2 feasibility studies by
architect office ion42*

In-flight spectroscopy (HISPEC)
&
Decay spectroscopy (DESPEC)

Laser spectroscopy (LASPEC)
and Precision mass
measurements (MATS)

Super-FRS Coll.
High-Resolution
Spectrometer exp.



MSV:
12,40 m x 11,40 m

See Talk by
Nasser today


LEB task force
very active!

Beam Diagnostics


- Full isotope identification (x, y, x', y', DE and TOF)
- Operation modes: fast- and slow-extracted beams
- Special devices (slits, degrader, secondary target, ...)
- Controls → machine safety
- DAQ (in-kind GSI / Sweden)
- Various detector systems
 - GEM-TPC (Finnish in-kind) **Test @ GSI 10/2014**
 - SEM-GRID & ladder system (Finnish in-kind) “
 - Silicon detectors (EoI Russia) **Test @ GSI 08/2014**
 - Diamond detectors (EoI Finland) “
 - MUSIC detectors (EoI Finland) **Test @ GSI 10/2014**
- **Various test beam-times at FRS/Cave C**



GEM TPC prototype



Diamond strip detector





Existing research opportunities at GSI

Decay studies,
In-beam spectroscopy

evolving towards NUSTAR

Reaction studies


production and
separation of
exotic nuclei



Ground state properties
inverse reactions



Areal view of the combined facility



- The secondary beam production facilities @FAIR are progressing!
 - main components are defined and mostly in purchasing process.

- The facilities @SIS are needed as:
 - test bench,
 - for commissioning runs,
 - and viable experiments with already existing novel instrumentation. (2017+)

- FAIRs intensities and opportunities are of key importance to maintain international competitiveness.