PANDA Mechanics



Lars Schmitt, FAIR

CM XLVII, GSI, Dec 9 2013

Agenda

PANDA Hall Status

Racks and Services

Hall Planning Steps



MEC Agenda



Mechanics Workshop at CM XLVII.

Monday 09 December 2013 from **09:00** to **16:00** (Europe/Berlin) at GSI (TSR)

Monday 09	Decem	ber 2013						
09:00 - 10:30	Status 09:00	Cus of Integration Overview of CAD Status 30' Speaker: Jost Lühning (GSI Helmholtzzentrum für Schwerionenforschung GmbH(GSI))						
	09:30	Individual System CAD Status 30'						
	10:00	Discussion 20'						
10:30 - 11:00	Break							
11:00 - 13:00	Details	Details of Target Spectrometer						
	11:00	Issues in Forward Endcap Integration 30'						
		Speaker: Jost Lühning (GSI Helmholtzzentrum für Schwerionenforschung GmbH(GSI))						
	11:30	Discussion 30'						
	12:00	Layout of Target Platform 20'						
		Speaker: Alexander Täschner (Institut für Kernphysik, Westfälische Wilhelms-Universität Münster)						
		Material: Slides 🔁						
	12:20	Discussion 20'						
13:00 - 14:00	Lunch							
14:00 - 16:00	Planning							
	14:00	Hall and Installation Planning 30'						
		Speaker: Lars Schmitt (Gesellschaft für Schwerionenforschung mbH)						
	14:30	Discussion 30'						
	15:00	Beam Pipe and MVD 20'						
		Speakers: Giuseppe Giraudo (INFN Torino) , Daniela Calvo (Instituto Nazionale di Fisica Nucleare (INFN (INFN-Torino))						
	15:20	Discussion 10'						
	15:30	Status of Lumi Mechanics 20'						
		Speaker: Prometeusz Jasinski (Kernphysik Mainz)						



PANDA Hall Status



Architectural plans

- In August 2D hall plans were acknowledged
- Placement of GHe tank, gas line routing and position of dipole power supply are communicated
- Open issue: Cryo system requires pressure bottles for He recovery, placement of small recovery compressor
- Phase 5 (execution plans) can only be finalized next year

Cables and supplies

- Cables and supplies routing follow next year
- PANDA routing should not collide with hall infrastructure
- Some issues related to magnet supplies (power, cooling, LHe)


Technical infrastructure

- Ventilation and temperature control of apparatus: tent in hall
- Cooling concept for racks and equipments




PANDA Hall Status









Total Available Rack Space



Counting house:

- E10: Supply area, 45 racks
- E20: DAQ floor, 61 racks
- E30: Online computing, 59 racks, (not for detectors)

Beam area:

- Target Spectrometer: 14+6 racks
 - 6 racks on auxiliary platform
 - 8 racks attached to solenoid yoke
 - 6 racks (only 2m high) on top of solenoid (reserved for target and solenoid power supply)
- Forward Spectrometer: 8 racks on platform
- → As many supplies as possible in E10
- → At TS/FS only electronics where long cables are not advisable

Availability (1 rack = 47 U)

E10: 45 racks, 2115 U

E20: 61 racks, 2867 U

E30: 59 racks, 2773 U


Area TS: 14 racks, 658 U

Area FS: 8 racks, 376 U

187 racks, 8789 U


PANDA Counting House: E10






PANDA Counting House: E20





PANDA Counting House: E30





PANDA Beam Area



Auxiliary

platform

Exceptional locations:


- Mounting directly to the barrel yoke
- Mounting to BE EMC support

•

Forward spectrometer racks

Solenoid yoke side racks

Solenoid top platform



Forbidden locations:

- Mounting to magnet doors
- Mounting in the path of movement of TS

(Beam from the right)

Present Rack Requirements



Subsystem	Infos by	19 " U					Specials	Sum	Racks
		E10	E20	E30	TS	FS			
Forward endcap	Fritz-Herbert Heinsius				81		1xATCA crate (13U)	94	2
Forward Tracker 1-4	Jerzy Smyrski					67		352	8
Forward Trackers 5,6	Jerzy Smyrski					59			
Forward Tracker	Jerzy Smyrski					226			
MVD pixel	Daniela Calvo				112			442	10
MVD strip	Daniela Calvo				90				
MVD general	Daniela Calvo				20				
MVD counting room	Daniela Calvo				220				
Target	Alfons Khoukaz	1x47	2PCs		3x47		- Cryo- compressor 1x1m + water cooling pipes - forepumps 2x1m for beam dump		3(TS) 1(E10) 2PCs
GEM Trackers	Bernd Voss	32	20		10			62	2(Mixed)
STT	Paola Gianotti				2x47			94	2(TS)

Recommendations for Placement



Counting house:

- E10 Supply area:
 - HV/LV Supplies
 - Gas mixing units
 - Heat exchange for cooling circuits
- E20 DAQ floor:
 - Concentrators with optical input
 - Other DAQ units with long cables

Beam area

- Target Spectrometer:
 - Solenoid supply
 - Target racks
 - Analog electronics
 - Compact power supplies
- Forward Spectrometer:
 - Analog electronics
 - Separate FSC crates
 - Compact power supplies



Recommendations for Placement



Counting house:

- E10 Supply area:
 - HV/LV Supplies
 - Gas mixing units
 - Heat exchange for cooling circuits
- E20 DAQ floor:
 - Concentrators with optical input
 - Other DAQ units with long cables

Missing information:

- Barrel EMC, BW EMC, Muon
- Small needs: DIRCs, TOFs, Lumi
- Separate: FSC

Beam area

- Target Spectrometer:
 - Solenoid supply
 - Target racks
 - Analog electronics
 - Compact power supplies
- Forward Spectrometer:
 - Analog electronics
 - Separate FSC crates
 - Compact power supplies



Further Planning Steps



Hall planning

- Details of equipment placement
- Details of PANDA cables and supplies routing


Installation planning

- Plan area needs for first mounting/installation, leave out shielding, use beam area and maintenance area
- Overall installation sequence, individual procedures



Power and Cable Routing





Assembly phases



• Phase 1: pre-assembly of components \rightarrow at the institutes

Phase 2: pre-assembly of modules

Phase 3: test of modules

Phase 4: storage of modules

Phase 5: assembly on-site

at pre-assembly sites (FZJ, GSI, ...)



Assembly Areas in PANDA Hall



