

STT News

Peter Wintz (IKP, FZJ)

PANDA Collaboration Meeting, Dec-2013, FAIR

STT News









- Recent STT activities
 - Workshop summary
 - Straw production & straw layout
 - Readout systems
 - Test system installations
- Beam tests 2014
- STT timelines
- STT pre-series test in 2015/16

STT Workshop in Oct-2013

STT Hardware meeting

Thursday 10 October 2013 from 08:00 to 18:30 (Europe/Berlin)
at FZ Juelich

Thursday 10 October 2013

09:00 - 10:00	Straw Tube production 1h00' Speaker: Peter Wintz (FZ Juelich) Material: Slides 
10:00 - 11:00	Straw Tracker mechanics 1h00' Speaker: Dario Orecchini (INFN-LNF) Material: Slides 
11:00 - 11:30	coffee break
11:30 - 12:30	STT gas system 1h00' Speaker: Vincenzo Lucherini (LNF) Material: Slides 
12:30 - 13:30	Lunch Break
14:00 - 15:00	Front End Electronics 1h00' Speaker: Dominik Przyborowski (AGH) Material: Slides 
15:00 - 15:30	timing measurements 30' Speaker: Henner Ohm (Forschungszentrum Jülich) Material: Slides 
15:30 - 16:30	FADC Readout Option 1h00' Speaker: Liubov Jokhovets (FZ Juelich) Material: Slides 
16:30 - 17:30	STT Digital readout 1h00' Speaker: Marek Palka (Jagiellonian University) Material: Slides 
17:30 - 18:30	STT HV and Slow Control Systems 1h00' Speaker: Alexandru-Mario Bragadireanu (IFIN-HH) Material: Slides 


STT work packages discussed

- Straw and layer-module production (FZJ)
- STT general mechanics (LNF)
- Gas system (LNF)
- Frontend / analog electronics (Krakow, FZJ)
- Digital readout (Krakow, FZJ)
- Detector control & HV system (IFIN-HH)

Straw Layout in STT

- STT straw layout:
 - New straw pitch: 10.12 mm (~ 10 μ m gap)
 - Straw diameter: ~ 10.05 mm (pressurized)
 - Mylar film wall: 27 μ m

- Straw layer modules
 - Determine all straw positions (soon)
 - Group straws into 4-layer modules, stereo-layer modules
 - Periphery, mounting elements, ..
 - **Integration in mechanical frame → iteration with Dario**



Straw Productions

- Straw production
 - final straw film specification, leakage tests successful
 - straw **series production started in Oct-2013**
 - **complete** straw mass **production takes 3-4 years**, including **~50% spares**
- Quality checks
 - **leakage and wire tension** measurement for each straw
 - **long-term** test sample

Electronic Readout Status

- Currently in preparation: **large-scale systems**
- ASIC-ToT + TRBv3:
 - new ASIC chip in design, in production soon
 - available in (late) Q2/2014, ~ 100chips ($\times 8$ ch)
- FADC based readout
 - new design amplifiers & cabling, FPGA/FADC architecture
 - available in Q2/2014

Test System Installations

- **Permanent STT test systems** with DAQ in Juelich
- PC network (“strawnet”)
- ASIC-TRBv3 readout installed last week by Cracow
 - 3× ASIC-boards, 96 channels
- **Greg’s, Jacek’s talks**
- Cosmic ray tests as preparation for next beam tests
 - tuning setups, straw electric coupling, HV distribution
 - optimise electronic parameters (ASIC shaping)
 - define default straw operation settings (gas gain)
 - clean tracking → resolution limits

Beam Tests 2014

- Beam time requests for 2014 (COSY)
 - 1 week in Jun-2014, protons at 3.0, 0.8, 0.6 GeV/c
 - 1 week in Sep-2014, deuterons at 2.0, 1.3, 1.0 GeV/c
 - 1 week in Nov-2014, protons at 2.0, 1.3, 1.0 GeV/c
 - dE/dx range ~ 10× mips
 - **aim for prot./deuteron separation**
- 2 straw setups for both readouts
 - 8×24 straws and 8×16 straws
- Optional: larger straw setups if new RO systems available



2 Straw setups, beam coming from the back (Big Karl area @ COSY)

STT Milestones & Roadmap

- M3: TDR approval 1.03.2013
- M8: Pre-series test accepted 31.03.2016
- M9: Final STT construction, acceptance test 31.03.2018
- M10: Shipment to FAIR / approval for installation 30.06.2018
- M11: Ready for beam 30.09.2018
- M12: Commissioning done / ready for operation 20.12.2018

Official timelines transmitted to FAIR


STT Milestones & Roadmap

- M3: TDR approval 1.03.2013
- **M8: Pre-series test accepted 31.03.2016**
- M9: Final STT construction, acceptance test 31.03.2018
- M10: Shipment to FAIR / approval for installation 30.06.2018
- M11: Ready for beam 30.09.2018
- M12: Commissioning done / ready for operation 20.12.2018

Official timelines correlated with money flow

STT Pre-Series Test

- **One complete STT sector (~ 800 straws)**
 - final design of straw-layer modules
 - mechanical frame
 - electronic RO system (800 channels)
 - supply system & DCS
- **Assembly and installation in 2015**
- **Beam test at COSY 2015/16**
- **Complete! test**



Pre-Series Test Program

- **Tracking + dE/dx** measurements
 - position calibration by reconstructed tracks
 - isochrone + dE/dx calibration methods
 - scatter target? → fiber, foil, .. in beam
 - final resolution
- **Continuous DAQ**, (PANDA-DAQ v1?)
 - high particle rates ~ 1 MHz
 - online tracking
- **No magnetic field**, straight tracks

