## The Status of the SciTil

Carsten Schwarz, GSI

- Motivation
- Setup
- Mechanics
- Readout
- Work packages
- Status India
- Costs



# **Motivation: Event Timing**

Events 1,2,3,4,5,6,7,8... for 50Mhz interaction rate with 6 tracks



Klaus Götzen, Influence of Particle Timing on Event Building PANDA collaboration meeting March 2011, GSI PANDA Collaboration Meeting, GSI, March 2014

# **Motivation: Conversion Detection**



SciTil important for relative timing and PID



less light path fluctuations larger detection efficiency





### ASIC for SiPM readout

**TOF-PET ASIC for PET applications** M.D. Rolo JINST 8 C02050



C. Schwarz

### **Results of test beam time in Juelich, Feb. 2014**

Ken Suzuki:

With analog SiPM, with a preliminary online analysis, we reached almost 100ps (sigma) intrinsic time resolution. With a careful offline analysis we'll probably reach 100ps, one of the goal of the project.

With digital SiPM together with Philips, we reached an astonishing <50ps (sigma) intrinsic time resolution.

More will be reported at the next PANDA meeting.

# Work packages

Work package	Interested institutes	
Simulation	BARC	
Module design	GSI, BARC	construction
Scintillator	Dubna, Gatchina	R&D
Silicon PM	EU HP3, BARC, Dubna, Ga	itchina
Readout design	EU HP3, BARC	
Mechanical design	GSI	
Prototype production	BARC	

Status: DAE - BRNS Workshop on Hadron Physics - 2011

### R&D: Vienna, Mainz, Erlangen for R&D with test stands Vienna, GSI, Experiments in beam

Work Package	Interested Institutes
SiPM test facility	BARC

construction



## **PANDA - India Present Status**

**Bidyut Roy** 

(on behalf of Panda - India collaboration)

# **Present Members (PANDA-India Collaboration)**

BARC, Mumbai IIT Bombay, Mumbai AMU, Aligarh BITS-Pillani, Goa campus, Goa Gauhati university, Gauhati IIT Indore, Indore Sardar Patel univ., Vallabh Vidyanagar, Sardar Vallabhbhai National Inst. of Tech., Surat Veer Narmad South Gujrat univ., Surat

P. D. Patel Inst. of Applied Science, Anand (in Theory Advisory Board)

## Membeship applied: > Visva bharati univ,

> B.R. Ambedkar National Inst. of Technology

03/11/14

SciTil Status, B.Roy Mach 2014

### On SciTil work:

Gauhati University got DST fund, one JRF has been appointed

AMU Aligarh got BRNS fund + 1 JRF being appointed

Visva Bharati got BRNS fund, 1 JRF being appointed

C. Schwarz

PANDA Collaboration Meeting, GSI, March 2014

11

### SiPM / SciTil test facility at BARC



## Most of the necessary equipments are purchased and Setup ready, initial R&D work being carried out.

SciTil Status, B.Roy Mach 2014

12





Time resolution ~ 500 ps achieved.

Initial results but very encouraging.

There are ways to minimize the spread/contribution from electronics, and are being studied. Time resolution  $\sim 200$  ps or better is feasible.

Shifting to a new lab space, which is more or less ready. Work will resume soon.

## Costs

		2011		2014
	device	sum	device	sum
Tile	25	140k	25	145k
SiPM	30	330k	90	1060k
Readout	20	220k	50	590k
Mechanics		50k		53k
Total		740k		1848k

Costs driven by SiPM prices in India SiPM prices in Europe go down

## Conclusions

- R&D / test in beam done by
  - Vienna, Mainz, Erlangen
  - 100ps is reached
- Construction planned in India
  - SiPM infrastructure is setup at BARC
  - Critical mass of man power not yet reached
- Cost increase due to expensive SiPM in India
  Funding?