
NeuLAND@R3B: Status and Perspectives

- NeuLAND design goals
- status of the NeuLAND project
 - Technical Design Report
 - prototype experiment \$406
 - build up of the demonstrator
 - demonstrator in GSI beam times 2014
 - ongoing production
 - NeuLAND excursion to RIKEN
- next steps



NeuLAND: The High Resolution Neutron Time-of-Flight Spectrometer for R³B



NeuLAND detector parameters:

- full active detector using RP/BC408
- face sice 250x250 cm²
- active depth 300 cm
- 3000 scintillator bars
- 6000 PM / readout channels
- 32 tons

NeuLAND design goals:

- >90% efficiency for 0.2-1.0 GeV neutrons
- Multi-hit capability for up to 5 neutrons
- invariant-mass resolution: NeuLAND-target distance 35 m ΔE < 20 keV at 100 keV above the neutron threshold



Performance Examples




		$600 \; \mathrm{MeV}$				
		generated				
	%	1n	2n	3n	4n	5n
detected	1n	92	22	2	0	0
	2n	2	71	32	7	1
	3n	0	6	55	32	9
	4n	0	0	10	57	50
	5n	0	1	1	4	35
	6n	0	0	0	0	5

high efficiency for low neutron energies:


E _n [MeV]	Eff. [%]		
50	79		
100	94		
150	95		
200	91		

high resolution at the particle threshold:



From Submodules to Complete NeuLAND





30 double-plane build up NeuLAND face sice 250x250 cm² active depth 300 cm



build one double-plane

Important Stages for NeuLAND

2011

- · NeuLAND design decision
- Technical Design Report handed in in Nov.

2012

- 5406 experiment with Prototype (150 modules)
- · Approval of Technical Design Resport

2013

- · April: first double-plane built at GSI
- · start of continuous production

2014

- · NeuLAND demonstrator successfully tested in GSI beam times
- preseries of final HV distribution arrived

2015

- 4 double-planes installed at RIKEN
- continuation of production



Important Stages for NeuLAND

2011

- · NeuLAND design decision
- · Technical Design Report handed in in Nov.

2012

- · 5406 experiment with Prototype (150 modules)
- · Approval of Technical Design Resport

2013

- · April: first double-plane built at GSI
- start of continuous production

2014

- · NeuLAND demonstrator successfully tested in GSI beam times
- · preseries of final HV distribution arrived

2015

- · 4 double-planes installed at RIKEN
- continuation of production

2016


ongoing production


2017


· commissioning of NeuLAND at Cave C




S406: breakup of deuteron on CH₂ target @200 to 1500 AMeV










important feedback from data to simulations!



K. Boretzky for NeuLAND@R3B - NUSTAR Meeting March 2015

NeuLAND double planes





collaborative consortium:

GSI PMA
PNPI Gatchina
Univ. Frankfurt
Univ. Cologne
TU Darmstadt
(TU Dresden)
(ATOMKI Debrecen)



NeuLAND building blocks: Scintillator Bars



3000 bars needed



270 cm long: 250x5x5 cm³ detector volume

+ 2x100 cm built in light guide

purchase of bars:

- frame contract: 4 years (2013-2017) at fixed price
 - 1st order: 430 bars (2013)
 - 2nd order: 200 bars (2014)
- second provider:
 - 1st order: 101 bars (2014)
- next steps:
 - in-kind contribution PNPI/Russia (V. Kuznetsov et al.)
 - · future orders within frame contract from german funding




SAT Scintillator Bars: combined LED and Cosmic Test

Light-Production Measurement

- detect transversing cosmic rays
- read-out at one or two sides
- check on scintillation quality

Light-Output Measurement

- LED light from one side of bar
- read-out at far side
- check surface quality





NeuLAND building blocks: Photomultiplier

6000 PMTs needed

- state of the art readout:
 - H8619 w. active voltage divider
 - ordered for in total 8 double-planes
 - "plug and play"



frame contract (2013 -2017, fixed price)

- future perspectives I: check PMTs from Russia as costeffective alternative
- future perspectives II: development of larger Si-PMTs ongoing

(HZDR team - D. Bemmerer et al.)



NeuLAND building blocks: High Voltage Distribution System

6000 HV channels needed

- HVDS system from PNPI (L. Uvarov et al.) is based on 2kV primary power supply with controllable dividers
- individual down-regulation of each channel
- form factor fits to NeuLAND double planes



- pre-series (200 channels) delivered in December 2014
- Site Acceptance Test ongoing
- Delivery of full system up to 2017








NeuLAND building blocks: Electronics



transition from LAND-TacQuila readout (ASIC based)



to TAMEX2 (FPGA based) final layout in development by GSI RBEE





NeuLAND for April beam time at GSI









NeuLAND June to October 2014 GSI beam times







Three GSI Beam Times

- 5438a April'14:
 - 1 double-plane, Tacquila readout
 - neutrons from Coulomb breakup of Ni
- 5438b Oct'14:
 - 4 double-planes, Tacquila readout
 - 2 single-planes, TAMEX readout
 - neutrons from nuclear breakup of Ca
- 5438c Oct'14:
 - as before but
 - neutrons from fission of ²³⁶U and others



5438a - Coulomb Breakup of 58Ni April 2014






K. Boretzky for NeuLAND@R3B - NUSTAR Meeting March 2015

TOF [ns]

S438b - Nuclear Breakup of ⁴⁸Ca Oct 2014




Demonstrator
1/6 of final NeuLAND
50 cm depth:

- 4 double-planes, Tacquila readout
- 2 single-planes,
 TAMEX readout

Neutron hit distribution in 8 layers

- → confirmed time resolution
- → background in accordance to simulation
- → pattern studies








NeuLAND Event Display Cosmic Event




by courtesy of Kenjiro Miki



NeuLAND Event Display One Neutron Event



by courtesy of Kenjiro Miki






NeuLAND Event Display One Neutron Event




by courtesy of Kenjiro Miki



NeuLAND Event Display Two Neutron Event









S438c: SOFIA Experiment Fission of ²³⁶U et al. - Oct 2014

(Picture by T. Gorbinet taken from ELOG)







- → little background due to SOFIA trigger
- → all 800 modules functional and well calibrated
- → pattern studies of multineutron events



K. Boretzky for NeuLAND@R3B - NUSTAR Meeting March 2015

GSI -> RIKEN





4 double-planes sent to RIKEN for 2 years

transport box 5.75 tons $401 \times 344 \times 128$ cm³

participation in several experiments during 2015 to 2017.



Summary

- NeuLAND demonstrator built and tested
- · data collected to work on simulation and analysis code
- production ongoing
- goal: up to 1 double-plane per month
 → complete detector during 2017
- Cave C can host the full-size detector
- goal: commissioning in late 2017
 first physics experiment in 2018

