# Forward Endcap Status and Testbeam Results

#### Malte Albrecht

Ruhr-Universität Bochum Institut für Experimentalphysik I

PANDA L. Collaboration Meeting INFN Frascati, September 09<sup>th</sup> 2014





Subunit Production	PCB and Cables	ELSA Beamtime
●00		

## Final Subunits

- Two final endcap subunits have been produced, one equipped with APDs, the other with VPTTs
- Photodetectors are glued to the crystals with Dow Corning 3145 (irreversible)
- Photodetecor-preamplifier units are filled with Elastosil RT601 casting compound
- Both subunits were mounted to the Proto192 to test mounting, cabling and response at the ELSA beamtime





Subunit Production

PCB and Cables

ELSA Beamtime

#### Production of APD Subunit





# Glueing of APD-Units

- Each glueing is inspected and archived using a DSLR photo
- Illumination of glued surface through the crystal was problematic
- → Usage of a LED-illumination ring (made in Bochum) improved image quality drastically
  - Photos of glueings are archived in the Forward Endcap Production Database using the barcode of each unit





bunit Production	PCB and Cables	ELSA Beamtime
	00000	

#### Subunit Production - Cables

No. of Cables	VPTT Subunit	APD Subunit	and the second second
Signal	16	32	
High Voltage	$2 \times 16 = 32$	$4 \times 16 = 64$	
Low Voltage	$3 \times 16 = 48$	$3 \times 16 = 48$	
GND Lead	16	16	Seite [ 2 : 1 ]
Sensors	2	2	
TOTAL	114	162	Uniter ( 2 . 1 )

- Keep these cables short to make mounting of subunits easier
- Cables are connected to Patch-Panel PCB, which will be placed on the backplate for each subunit (Design presented on June CM by C.Schmidt)

Malte Albrecht (RUB EPI)



FW Endcap Status & Testbeam Results

## Test: Mounting Subunit To Mini-Backplate



Malte Albrecht (RUB EPI) FW Endcap Status & Testbeam Results

## Test: Mounting Subunit To Mini-Backplate





- Cabling of VPTT-Subunits works fine
- Mounting of APD-Subunit is problematic: Too many and too stiff cables
- PCB cannot be pushed/mounted to the backplate!
- $\rightarrow\,$  Need more flexible/thinner HV cables in APD subunits

Malte Albrecht (RUB EPI) FW Endcap Status & Testbeam Results

Subunit Production	PCB and Cables ०००●००	ELSA Beamtime
Caliliana	d Deutien in the Fernind Federa	

#### Cabling and Routing in the Forward Endcap

- Used in Proto192 for the two final subunits:
  - Signal: 1  $\times$  16 (VPTTs) or 2  $\times$  16 (APDs) Huber&Suhner Enviroflex coaxial cable
  - HV: 4 H&S Enviroflex cables per subunit (4 VPTTs / 8 APDs)
  - LV: Standard AWG20 wire connected to pin header on PCB (needs to be changed in final version)
  - Sensors: 1 flat ribbon-cable (pitch: .5 mm) for 2 sensors

 $\rightarrow\,$  Sophisticated routing scheme (including light fibres!) is needed



Malte Albrecht (RUB EPI)



FW Endcap Status & Testbeam Results

Subunit Production	PCB and Cables	ELSA Beamtime
	000000	

#### Cables and Routing in the Forward Endcap

- Foreseen for FW endcap:
  - Signal: Feasibility of using H&S Enviroflex is being checked (Possible alternatives: Samtec FCF8 micro coax cable (AWG38); Nexans Filotex 50VMTX)
  - HV: H&S Enviroflex, as in Proto192
  - LV: under investigation
  - Sensors: as in Proto192



Diameter	0.6mm	1.2mm	1.8mm
Attenuation @700Mhz	-3dB/m	-1.9dB/m	-1.3dB/m
Conductor wires	7	1	7
Malte Albrecht (RUI	B EPI)	- W Endcap Status	s & Testbeam Result

# Routing Scheme

Subunit Production

- only ≈ 30 mm space between backplate and insulation
- Current idea for the routing scheme:
  - Light Fibres, high voltage, low voltage and sensor cables will be routed vertically as well as horizontally below and inbetween the Patch-Panel PCBs, directly on the aluminium backplate
  - Signal cables will be routed both **vertically** and **horizontally** in a layer **on top of** the PCBs



PCB and Cables

00000

#### PCB and Cables

#### ELSA Beamtime



Malte Albrecht (RUB EPI) FW Endcap Status & Testbeam Results

## ELSA Beamtime - Setup and Measurement Program

- Used direct electron beam delivered by ELSA (tagger magnet turned off)
- Energies: 1.25, 2.4, 3.2 GeV
- Fibre hodoscope in front of Proto192 for triggering and tracking
- Proto192 mounted on XY-table
- Shot centrally in each of the 32 crystals with all 3 energies for calibration
- Additional measurements with high rates
- Goal of beamtime:
- → Measure response of APD and VPTT units to finally fix design/amplification factor of preamplifier



#### Subunit Production

## Analysis

- Detailed analysis and calibration of data is in progress
- Performed MC simulation with fully featured Proto192 geometry (Geant4) as for previous beamtimes
- Simulations for all energies / targetted crystals finished
- High-Gain/Low-Gain calibration finished
- Energy calibration is being prepared



## Response of VPTTs: Calculation vs. Measurement

$$U_{\mathsf{Preamp}}(50\Omega) = \mathsf{LY} \cdot \frac{A_{\mathsf{cath.}}}{A_{\mathsf{xtal}}} \cdot G_{\mathsf{VPTT}} \cdot \mathsf{QE}_{\mathsf{VPTT}} \cdot G_{\mathsf{Preamp}}$$

- $LY \approx 380 \text{ Ph/MeV}$  at  $-25^{\circ} \text{ C}$
- $\frac{A_{\text{cath.}}}{A_{\text{xtal}}} = \frac{201.1 \,\text{mm}^2}{676 \,\text{mm}^2}$
- $G_{\rm VPTT} \approx 48$
- QE = 23%
- $G_{\text{Preamp}} = 0.46 \text{ V/pC}$ 
  - $\Rightarrow U_{\mathsf{Preamp}}(50\Omega) = 92 \, \frac{\mathsf{mV}}{\mathsf{GeV}}$



- Response is (only!) 30% larger than expected (maybe due to reflective foil, ...)
- Largest signals to be expected (w/o magnetic field!)  $\approx 1.5 \text{ V}@50\Omega \rightarrow \text{could}$  use higher gain of preamp?

1GeV energy deposit

#### ELSA Beamtime

#### PCB and Cables

## Response of APDs

Subunit Production

- Yield measured in the lab
  - +20° C
  - APDs operated at *M* = 100 voltage (Hamamatsu)
  - Used blue light pulser and PIN diode reference system
  - $\rightarrow$  Nicely homogeneous response of all APDs (variations  $\approx$ 7%)
- Yield measured at beamtime
  - -25° C
  - Shared HV for 8 APDs
  - Matching performed with  $M = 200@ 25^{\circ}$  C voltages from Frankfurt/GSI
  - → Response shows two 'groups' of APDs with large difference in response (factor of 2!)



# Ringing of APD Preamplifiers

Subunit Production

- Observed massive HF-induced ringing of APD preamplifiers (lab + beamtime)
- Triggered by large HF-spike, all 32 APD preamps start ringing
- Light pulser (blue diode) produces such a spike (rapid capacitor discharge)  $\rightarrow$  no measuments with LP and APDs were possible
- Source of the problem not yet fully understood: Characteristics of latest APDs? Behaviour of preamp?
- $\rightarrow\,$  Trying to solve that problem together with Basel colleagues

Subunit	Production

ELSA Beamtime

## Blue Light Pulser on APD - Preamp Output Signal









#### Blue Light Pulser on APD - RINGING (Zoom)



- No rail-to-rail ringing
- Typically around 200-400 mV pp.
- Frequency:  $\approx 230\,\text{MHz} \rightarrow$  resonance frequency of OP-amp circuit

#### Subunit Production

PCB and Cables

## Summary

- Analysis of beamtime data is ongoing
- Production of final VPTT subunits can start: Mechanics, cables and electronics are almost fixed
- Second batch of 100 VPTTs has arrived at U Bonn last week!
- Response of APDs needs to be understood
- Ringing of APD preamps is being investigated
- Routing scheme for cables in the cold volume of the endcap is being planned

