

EMC cooling machine prototype

Tobias Triffterer

Experimentelle Hadronenphysik
Ruhr-Universität Bochum

LIV. \bar{P} ANDA Collaboration Meeting
08th September 2015

RUHR
UNIVERSITÄT
BOCHUM

RUB

 **JÜLICH**
FORSCHUNGSZENTRUM

 **panda**


Purpose of the cooling system prototype

- Cooling system intended to be used for testing of the forward endcap EMC at FZ Jülich
- Capable of cooling the complete endcap and one barrel slice
- Cooling system for the complete EMC: Scaled-up version of this system (if everything works as intended)
- Work sharing:
 - Hardware designed and built by IN2P3 Orsay
 - Control software created by EP1 Bochum
 - Chiller and heat exchanger bought from French company Eurodifroid
- Total value: $\approx 52,000 \text{ €}$ (mostly paid by Gießen)

Technical data

- Power of cooling compressor: 5 kW
- Power of main pump: 1.5 kW
- Underpressure system
- Two circuits connected to chiller:
 - Primary circuit: Coolant flowing through calorimeter
 - Secondary circuit: Transports heat from cooling compressor to heat exchanger outside
(Alternative: Direct connection to cooling water supply of experiment hall)
- Cooling agent primary circuit: Methanol-water mixture
- Operating temperature: -32°C
- Reservoir of $\approx 330\text{ L}$
- Cooling agent secondary circuit: Water


Preliminary schematic diagram



legend:


- primary circuit (methanol water mixture)
- secondary circuit (water)
- underpressure system

Panorama photo of the setup




Control system

- Raspberry Pi in switchboard
- Relais connected to its GPIOs
- USB-RS485 adapters connected to USB
- Control of pump, flow meter, chiller
- EPICS (DCS software) running on Raspberry Pi
- Connection to rest of DCS via network




Cooling flow

- Primary circuit filled with glycol (Ethan-1,2-diol) at IN2P3
- Flow at $T = -32^{\circ}\text{C}$ with current pump setup: $10 \frac{\text{L}}{\text{min}}$
- Experience (IN2P3): Factor 2 for methanol-water, i.e. $20 \frac{\text{L}}{\text{min}}$
- Requirement for forward endcap: $200 \frac{\text{L}}{\text{min}}$
- Remote control unit for pump has been ordered today
- Flow can be increased
- Maximum for pump
 $5.8 \frac{\text{m}^3}{\text{h}} \approx 97 \frac{\text{L}}{\text{min}} ?$
- Issue will be investigated when chiller is in Bochum



Internal insulation


- Primary circuit system insulated by large foam box
- Air inside \Rightarrow ice
- Insulation will be reworked in Bochum



Stability I


- Measured for 42 minutes at $T = -32^\circ\text{C}$
- Started ca. 30 minutes after reaching target temperature
- Measurement dominated by resolution of chiller sensor

Chiller temperature vs. time



Stability II

- Parameters of chiller regulation can be edited
- Will check if stability can be improved (better parameters or temperature sensor), but already $\frac{\sigma_{rms}}{\langle T \rangle} \approx 0.1\%$



Summary & Outlook

- Cooling system works generally
- Software written for the chiller tested successfully
- Expected arrival in Bochum: Week 39 (21st-25th September)
- Several issues to be sorted out before cooling system is usable for endcap preassembly
- Issue solving will begin in October

The End

Thank you
for your
attention!

