


# Update on the Endcap Disc DIRC






Simon Bodenschatz, Lisa Brück, Michael Düren, Erik Etzelmüller, Klaus Föhl,  
Avetik Hayrapetyan, Jan Hofmann, Sophie Kegel, İlknur Köseoğlu,  
Jhonatan Pereira de Lira, Mustafa Schmidt, Marc Strickert


PANDA CM 18/2 – PID-Cherenkov - 2018/06/05

# Optical Gluing Tests

# Optical Gluing tests - Setup





# Optical Gluing tests - Results




- Tests done with float glass samples
- Different glues were tested:
  - APM Epicol (2k)
  - Epotek 301-2 (2k)
  - NOA-61 (UV)
- High quality glue joints with all three adhesives were achieved (NOA-61 required some careful treatment)

# Optical Gluing tests – Load tests



- First load test with 15 Nm (expected force due to magnetic field)
- Precision scale shows elastic deformation of about 80  $\mu\text{m}$
- NOA-61 failed even at low weight!

# Optical Gluing tests – Load tests





- Extended tests with up to 45 Nm (current status)
- Deformation up to 300  $\mu\text{m}$  observed

# Optics

# Optics – Glue Transmission Measurements

Comparison of glue samples




- Test samples have a thickness of about 80  $\mu\text{m}$
- AMP-Epicol has not a sharp edge like EPO-301 at 300 nm
- NOA-61 shows a clear drop below 400 nm

measurements and plots were done by Lisa Marie Brück




# Optics – Filter transmissions



- 355 Edge Basic by Semrock is a dielectric filter with anti-reflective coating
- The remaining samples were color filters
- Transmission values are not corrected for Fresnel-losses

measurements and plots were done by Lisa Marie Brück


# Optics – Filter transmissions



- Transmission of dielectric filter depends on the angle of incidence
- Significant shift if filter is placed between fused silica windows
- We are going to test other dielectric filters to see if they match our requirements better

measurements and plots were done by Lisa Marie Brück

# Optics – Focusing Elements



- New setup for FEL qualification is being developed
- Blue shows simulation
- Green shows data
- Good agreement
- Measurement can be done mainly automatically (CCD sensor has to be shifted)

- solid lines correspond to the deviation from a linear fit to the imaging function

measurements and plots were done by Sophie Kegel



# Front-end Electronics

# Front-end Electronics

Trigger Plate

Scintillating Bars

Trigger Plate




- Cosmic Test Stand (under construction)
- SiPM readout works well
- PMT readout for trigger plates now, too


scintillating bar box by S.Bodenschatz, supported by I.Köseoğlu and A.Hayrapetyan, M.Strickert

# Front-end Electronics


FEM128



- FEM128 contains two FEB/A\_v2
- 128 channels available
- Another 8 boards (1024 channels) to arrive by mid-June
- Tests ongoing




FEB/D\_v2



# Development of a EDD-FEE-Board

Sketch: Available Space for Front-End Electronics (side view)

13.03.2018




\*positions and type yet have to be defined

E. Etzelmüller

# Development of a EDD-FEE-Board

12 DAQ-Boards in total



Requirements:

- at maximum 100 kHz per channel  
→ converts to 30 MHz per ROM
- ✓ FEB/D allows up to  $10^8$  events/s
- ✓ DAQ-Board allows up to  $2.5 \cdot 10^8$  events/s
  - 8 ROMs per DAQ-Board
  - 3 DAQ-Boards per Quadrant
  - 12 DAQ-Boards in total  
(72 FEE-Boards)




# Development of a EDD-FEE-Board

- Meeting with PETsys in Lisbon at the end of April
- Boundary conditions were discussed and open questions addressed
  - DC-DC convertes: Use some LDOs? Alternatives inside the magnetic field?
  - Optical link: Versatile link needed?
    - detailed radiation map in preparation by M.Schmidt
- Meeting at CERN with electronic engineer
- Project will be supervised/pushed forward by İlknur Köseoğlu

# Testbeam

# Testbeam - EDD prototype readout scheme


DAQ Scheme Testbeam 2018



2018/06/03

# Testbeam - EDD prototype readout scheme

DAQ overview Testbeam CERN 2018



# Testbeam – New MCP-PMT

New MCP-PMT (PHOTONIS Aqua) was just shipped to Erlangen for a first evaluation



Thanks to Markus for the sensor pictures

# Testbeam preparations

- Preparations are ongoing
- Setup similar to DESY 2016, but
  - more channels
  - TOFPET version 2
  - new MCP-PMT (Aqua)
- TOFPET version 2 still has to be tested in more depth
- Remaining boards should arrive until Mid of June according to PETsys
- Some PCBs missing
- Great man (and woman) power available during testbeam
- Preparative simulations are getting started
  - J.Hofmann and J.Pereira de Lira supervised by M.Schmidt