



Strategieworkshop


Beschleuniger-Großprojekte
in „Deutschland“

ein Überblick

Viele Folien von und herzlichen Dank an:
Hans Weise, Winni Decking, Rainer Wanzenberg, Reinhard Brinkmann,
Andreas Jankowiak, Oliver Boine-Frankenheim, Frank Tecker

Kurzübersicht

**XFEL
PETRA IV**



BESSY VSR

FAIR


HL-LHC

Kurzübersicht



European XFEL at a Glance

- ❑ International project realised in Hamburg area, Germany
- ❑ Accelerator and large parts of infrastructure built by international consortium under the coordination of DESY
- ❑ Accelerator operation and development by DESY
- ❑ Superconducting accelerator in 10 Hz pulsed mode with 97 modules / 776 cavities
- ❑ Up to 17.5 GeV and 27000 bunches/s
- ❑ Three variable gap undulators for hard and soft X-rays (250 eV to 25 keV)
- ❑ Initially 6 equipped experiments
- ❑ All accelerator and beamlines in tunnels 6 -25 m below surface







European XFEL




Superconducting linear accelerator
demonstrates design performance:
Reached design energy of 17.5 GeV
Accelerated full bunch train of 27000 bunches/second






Commissioning Milestones 2016-2018



March 13, 2018



April 27, 2017



Dec 12, 2015: 130 MeV
Mar 19, 2016: 2700 bunches/RF pulse

Feb 2, 2017: 600 MeV
Feb 22, 2017: 2.5 GeV

Jan 15, 2017: 130 MeV
Jan 19, 2017: 600 MeV

Feb 25, 2017: 2.5 GeV
Apr 8, 2017: 12 GeV
Oct 23, 2017: 14.9 GeV
July 12, 2018: 17.6 GeV

Nov 2, 2018: 2699 bunches/RF pulse

Upgrades

- ❑ Self Seeding in the hard X-ray regime:
 - ❑ SASE2 chicanes installed and operational
 - ❑ Commissioning with beam started in SASE2
 - ❑ SASE1 chicanes available
- ❑ SASE3 Helical Afterburner and Two Color Scheme
 - ❑ Hardware installation starts in Winter shutdown 2019/2020
 - ❑ Hardware complete and first photons in 2021
- ❑ Still two empty tunnels suitable for FELs;
Let's call them SASE4 and SASE5
 - ❑ Ideas to extend photon energy range in hard and soft x-ray regime are developed
 - ❑ Technical and scientific cases are explored
 - ❑ Proof of principle tests, e.g. Harmonic Lasing Self-Seeding (HLSS) have already been demonstrated at SASE3 reaching 4.5 keV
- ❑ R&D towards CW operation and a second fan

SRF R&D for XFEL

R&D @ DESY → future cw upgrade

- srf gun development
 - optimum cavity treatment
 - beam dynamics simulation
 - dedicated diagnostics
 - ...



- Niobium material and treatment:

- Large grain Nb
 - N₂ infusion/doping,
 - special treatment recipes



- cw srf modules

- ...




PETRA III



PETRA IV

PETRA III



Strong Focusing and Low Dispersion

First used for MAX-IV.

D. Einfeld *et al.*, Proc. PAC 95, Dallas TX

PETRA IV – Timeline


Presently: CDR preparation phase

FIS-process pre-proposal submitted


Helmholtz association:

FIS = **F**orschungs**I**nfra**S**truktur

Large-scale research infrastructure



PETRA IV conceptual design



Baseline: H7BA – ESRF style lattice

8 cell / arc, 26.2 m cell length
 + 4 undulator cells in the long
 straight sections ★
 (10 m long undulators)

Storage Ring:

Baseline: H7BA style lattice (64 cells)
 on axis injection,

Option (considered during TDR)
 maintain several beamlines
 (23 m long cell with strong magnets)

Injector:

new booster synchrotron, DESY IV
 low emittance ~ 20 nm rad
 refurbished Linac II

with full intensity gun

Option

consider the possibility to include in
 the future an injector based on
 laser plasma wakefield acceleration

Technical sub-systems:

Magnets, bore radius 13 mm

Option: 9 ... 10 mm

Vacuum system, 10 mm inner radius

Option: 7 mm


PETRA IV – parameters and challenges

Dynamic Aperture and nonlinear dynamics

→ Sufficient for on axis injection (> 1 mm mrad)

Momentum acceptance and Touschek lifetime


→ MA is sufficient for >1 h lifetime in timing and >4 h lifetime in brightness mode



Alignment tolerances and start-up simulation

→ $30 \mu\text{m}$ (rms) alignment tolerances on girder

PETRA III: Max von Laue Hall, achieved $32 \mu\text{m}$ (rms)



PETRA legacy and tunnel stabilization

→ Building reinforcement and temperature stabilization ($< 0.5 \text{ }^\circ\text{C}$)

Parameter	Value (with 29 IDs)
Energy E	6 GeV
Length L	2304 m
Tune Q_x/Q_y	164.18 / 68.27
Nat. chromaticity ξ_x/ξ_y	-230 / -185
Damping part. number J_x	1.175
Nat. emittance ϵ_x	7.6 pm*rad
MCF α_c	1.485e-5
Energy spread σ_e	0.92e-3
Hor. damping time τ_x	19.5 ms
Ver. damping time τ_y	22.9 ms
Long. damping time τ_e	12.6 ms
Energy loss per turn U_0	4.0 MeV
Rf voltage (500 MHz)	8 MV

Notes: (lattice version 15.7)

- Zero-current values – without IBS!


BESSY VSR




BESSY-VSR – short & long electron pulses simultaneously

$$\sigma \propto \delta_0 \sqrt{\frac{E_0}{\omega_0} \cdot \frac{\alpha}{\omega_{rf} V_{rf}}} \quad I \propto \alpha$$

high voltage (20 MV/m) cw multi-cell SC cavities allow to increase the total voltage gradient by two orders of magnitude
→ ca. 1/10 bunch length @ constant bunch current



Combining two RF systems with different frequencies (1.5 GHz & 1.75 GHz) generates long and short buckets, which can be filled individually to generate optimized fill pattern.



1.5 MV @ 0.5 GHz
16 MV @ 1.5 GHz
14 MV @ 1.75 GHz


J. Feikes, P. Kuske, G. Wüstefeld, EPAC2006
G. Wüstefeld, A. Jankowiak, J. Knobloch, M. Ries, IPAC2011

VSR – variable pulse length storage ring

Technical realisation



One cryo-module with:
2 x 4 cell @ 1.5 GHz & 2 x 4 cell @ 1.75 GHz
operating at **1.8 K LHe** temperature
active length: **1.50 m with 20 MV/m**
total gradient: **2π 50 MV×GHz (x 60 increase)**

A. Velez, A. Neumann, F. Glöckner, J. Knobloch et al. HZB




sacrificing one
low beta straight

Installation of 1.8 K Cryo-System



BESSY VSR – status and realisation


4 cell, 1.5/1.75 GHz waveguide
damped HOM cavities
(based on bERLinPro designs)



1.8K cryo plant



Module design &
system integration



2018 > 2019 > 2020 > 2021 > 2022 > 2023 > 2024 > 2025 > 2026



tendering
cavities &
SSA transmitter &
couplers

installation &
commissioning
cryo-plant

prep. phase cryo-module
2 x 1.5 GHz
(assembly, test, beam test)

full BESSY VSR
2 x 1.5 GHz & 2 x 1.75 GHz
(assembly, test, user
operation)

- **short, intense bunches - scaling behaviour bunch-length vs. current**
- **development and operation of high gradient superconducting cavities**
 - 1.5 GHz and 1.75 GHz @ 20 MV/m gradient cw
 - 200W @ 1.8 K cooling plant (30% margin), 260 W @ 4.5K, 2 kW @ 50 K
 - particle free (clean) vacuum around cavity straight, 10^{-10} mbar
 - module integration (space, synchrotron radiation) in general
- **HOM damping to fight coupled bunch instabilities**
 - induced by sc cavity impedance, higher order modes of sc cavities
 - proper HOM damping design of sc cavities, waveguide HOM dampers
 - sufficiently strong bunch by bunch feedback
- **operation with large (transient) beam loading and in regime of possible Robinson instability**
 - lifetime reduction, phase shift over bunch train, losses
 - careful set up and control of RF-parameters
 - appropriate low-level RF-control
- **top up operation: injection from booster in short VSR bunches, lifetime**
 - bunch length in booster 60 ps, injection efficiency > 90%
 - bunch “compression” in booster at least by factor 2 needed
 - solved by some modification of the booster and optimization of injection!**



FAIR project status


Status FAIR construction / components



SIS100 tunnel segment




SIS100 sc dipole modules in GSI storage area:
half of the dipoles delivered and accepted.




Kick-off of Super-FRS magnet testing facility at CERN:
First of series (FoS) multiplet.

FAIR completion dates



FAIR accelerator physics R&D

- Fast ramping sc magnets for synchrotrons
- Large aperture sc magnets for fragment separators
- Fast beam cooling at medium and high energies
- Beam dynamics: Intensity limitations and advanced stabilization schemes
- Control of UHV pressures for intense ion beams
- Simulation tools and advanced optimization schemes for commissioning and intensity ramp up




LHC



HL-LHC



HL-LHC parameters and timeline



- LS2 (2019-2020):**
- LHC Injectors Upgrade (LIU)
 - Civil engineering for HL-LHC equipment P1, P5
 - Installation of (part of) 11T Nb₃Sn dipoles for HL-LHC
 - Phase-1 upgrade of LHC experiments

- LS3 (2024-2026):**
- HL-LHC installation
 - Phase-2 upgrade of ATLAS and CMS


LIU will provide beams of intensity and brightness needed by HL-LHC (2.3×10^{11} p/bunch, $\epsilon \sim 2.1 \mu\text{m}$)

Linac 4: 160 MeV H⁻
 PSB: 1.4 → 2 GeV
 PS: new injection and feedback systems
 SPS: new 200 MHz RF system



LHC / HL-LHC Plan

LHC



Technical limitation on the Instantaneous Luminosity:

1. **Collider** (cryolimit in the triplet region) at $2 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$ twice the nominal design luminosity)
2. **Experiments** (pile up in the detectors). Designed for peak of 40 they are actually dealing with 60!

Technical limitation on Integrated Luminosity:

1. **Collider** (radiation damage to the IT magnets – correctors and quadrupoles)
2. **Experiments** (radiation damage in the Inner Tracker)

**Rebuilding ~1.2km of LHC
(the most complicated bit!)**

**But also touches very many
other systems around the
machine**

- **New IR-quads Nb₃Sn (inner triplets)**
- **New 11 T Nb₃Sn (short) dipoles**
- **Other NbTi magnets in the IR**
- **Collimation upgrade**
- **Cryogenics upgrade**
- **Crab Cavities**
- **Cold powering**
- **Machine protection**
- ...



3 "CRAB" CAVITIES
8 superconducting "crab" cavities for each of the ATLAS and CMS experiments to tilt the beams before collisions.



4 BENDING MAGNETS
2 pairs of shorter and more powerful dipole bending magnets to free up space for the new collimators.



1 FOCUSING MAGNETS
12 more powerful quadrupole magnets for each of the ATLAS and CMS experiments, designed to increase the concentration of the beams before collisions.



5 COLLIMATORS
15 to 20 new collimators and 60 replacement collimators to reinforce machine protection.




6 SUPERCONDUCTING LINKS
Electrical transmission lines based on a high-temperature superconductor to carry current to the magnets from the new service galleries to the LHC tunnel.




2 CIVIL ENGINEERING
2 new caverns and two new 300-metre service galleries, two new large shafts; 10 new technical buildings on surface in P1 and P5 (ATLAS and CMS)



7 CRYOGENICS
2 new large 1.9 K helium refrigerators for HL-LHC near ATLAS and CMS



LHC / HL-LHC Plan



HL-LHC TECHNICAL EQUIPMENT:



HL-LHC CIVIL ENGINEER:



- Now deep into the construction phase ...
- Some installations already during LS2 as well as civil engineering works
- Main installation work during a 30 month stop (LS3): 2024-2026

