



STT Status Update

June-26, 2019 | Peter Wintz for the STT Group

Status Outline

- STT
- STS1 @ HADES (Phase 0)



STT Workpackage Status



Assigned WPs (funding by in-kind contracts)

1. Straws series & module production, integration, FoS readout (FZ Jülich)
2. Electronic readout system incl. data concentrator (AGH & JU Krakow)
3. Detector control & HV system & LV system (IFIN Bucharest)

Not assigned WPs, no funding (former EoI INFN)

4. STT mech. system: holding frame & cable routing cage
5. Gas system (EoI FZJ ??)
 - Option: design & production by CERN
6. Central Systems Frame structure (BP/MVD/STT) (EoI GSI)
 - New concept worked out by Stefan Koch & Jost Lühning

Further WPs (non-construction)

7. SW real-time: data processing, track&event association, ..
8. SW methods: calibration, tracking, PID

Phase-0 WP: STS1 @ HADES

- In-kind contracts
 - WP 'electronic readout system' final approval expected soon (PSP xx.3)
 - Assigned groups: AGH & JU Krakow (M. Idzik)
 - STT & FT electronic readout are combined
 - Important: ~ 200k EUR not covered (e.g. front-end layout, cooling)
 - Contract renewal for FZ Jülich submitted (PSP xx.1)
 - former contract was for period 2013-2018
 - Contract for IFIN Bucharest secured (PSP xx.4)
- Planning of final STT system assembly and installation → TEC session on Friday
 - Impacts from neighbouring systems (MVD, backEMC, CSF, ..)
 - STT system pre-assembly option to be discussed
 - (In-beam pre-commissioning at COSY?)

STT DCS Workpackage Status





IFIN Bucharest

1. Detector control system
2. HV & LV system
3. Gas system interface to DCS

Status (report by Mario & Stefan Ghinescu)

- Generic gas system interface system was set up
 - one pressure controlled supply line
 - controllers set & read, meters read
 - 4 operation modes, alarm server
 - detailed scheme when WP gas system assigned



Current issue under discussion

- integration of electronic readout control/status in DCS (ASIC control via FPGA)
- ASIC/TRB DAQ system required in Bucharest, but no spare system available

STT Project Reporting To FAIR



MLS (Milestone Loaded Schedule)

- To be updated and harmonized, STT installation planned for 2024
- Open WP (STT mech. & gas system) to be included when assigned, now as risk factor

Project risk register

- Risk factors & mitigation, .. for (sub-) WPs, followed up continuously

FAIR CID (Component ID, FAIR-wide)

- Component declaration will be started, PANDA-STT: CID = 24 04 xx xxxxx
- List of components (xx) and device number (xxxxx) to be defined, but stay simple
- Important: CID declaration has consequences for
 - Procurement and logistics of components (e.g. storage, ..)
 - Safety and conformity for operation, maintenance and repair

Project progress score for STT

- 40% (Jan '19), mainly by completion of straw series production and FoS readout system
- STS1 activities (phase 0) in 2017-19, not included in progress score

Current MLS



1.4.1.4.1

Component: Straw Tube Tracker [STT]

Owner: Peter Wintz

Editors: p.wintz@fz-juelich.de

a.belias

l.schmitt

u.kurilla

Progress score: Please, set your system's score!

Planning ▾

M3:

01/03/2013

ME1:

22/02/2019

M4:

27/06/2019

M7:

30/12/2019

Construction ▾

ME2:

30/06/2020

M8F:

–

MX1:

30/06/2020

ME:

23/09/2020

M9F:

–

M9:

30/11/2022

Installation ▾

M10:

30/11/2023

M11:

08/03/2024

M12:

06/09/2024

Funding
established
and contracts
signed not yet
for all WPs

To be updated

STT Upcoming Timemarks






- PASTTREC ASIC order asap when in-kind budget available
 - Final number of ASICs for STT & FT
 - Good news: extended production lifetime of AMS 0.35 μ m CMOS technology (> 2019)
- Completion of phase 0 STS1 planned for Sep '19 (mech. frame delay)
- Installation at HADES by end 2019
- Phase 0 experiments in period 2020-22
- STT straw module assembly planned to start in end 2019
- STT sector built-up in prototype mech. frame starting 2020
- **Urgent: freeze of STT dimensions**
 - STT/MVD integration required and agreement
 - STT dimensions: inner/outer radius, length, half-barrel gap size

STS & HADES (Phase-0)



Reminder


- Experiment program: hyperon radiative and Dalitz decays with HADES at SIS18
- Upgrade by two forward straw tracker stations (STS1&2) for small polar angles $\theta < 7^\circ$
 - STS1 by Julich STT group
 - STS2 by Krakow FT group
- Later use of STS1&2 modules in PANDA – FTS 3/4 and 5



HADES upgrade by EMC, two forward straw tracker stations (STS1/2), RPC and DAQ..

STS1 @ HADES Status


- STS1 modules
 - Straw length 766mm, 10mm straw diameter
 - 20 modules with 640 straws
 - 4 double-layers, orientations: 90°, 0°, 0°, 90°
 - 2x64 shorter straws for beam hole (~ 8x8 cm²)
 - Ar/CO₂ at 2 bar pressure (abs.)
- Use modules in PANDA FT3/4 after phase 0
 - specific STT → FT straw module design required
- FEBv3 front-end boards w/ PASTTREC-ASIC
- TRB3 readout (experiment HW trigger)



One STS1 double-layer



Compact FEBv3 (one FEBv1 added)




*STS1 modules,
2x16 straws each*

STS1 @ HADES Status




- Rails in HADES-ECAL frame installed (Orsay)
- STS1 support frame re-design (now in Julich)
- STS1 straw module mounting ongoing
- FEE and cabling ongoing
- DAQ set up next (TRB3)



*STS1 system in HADES
ECAL-frame (CAD by Artur D.)*

- Cosmic tests in Julich planned
 - Functional channel tests
 - Calibrations, thresh/BL tuning, ..
- Straw alignment
 - Laser beam & ^{90}Sr data
- Installation at HADES in Sep. '19
- Testbeam (\sim h) possible in end '19



Thank you

for

your attention